#### ASSESSMENT OF THE NEW AASHTO DESIGN PROVISIONS FOR SHEAR AND COMBINED SHEAR/TORSION AND COMPARISON WITH THE EQUIVALENT ACI PROVISIONS

by

#### ABDUL HALIM HALIM

B.Sc., Kabul University, 2007

#### A THESIS

submitted in partial fulfillment of the requirements for the degree

#### MASTER OF SCIENCE

Department of Civil Engineering College of Engineering

KANSAS STATE UNIVERSITY Manhattan, Kansas

2010

Approved by:

Major Professor Dr. Asad Esmaeily

# Copyright

ABDUL HALIM HALIM

Fall 2010

## Abstract

The shear and combined shear and torsion provisions of the AASHTO LRFD (2008) Bridge Design Specifications, as well as simplified AASHTO procedure for prestressed and non-prestressed reinforced concrete members were investigated and compared to their equivalent ACI 318-08 provisions. Response-2000, an analytical tool developed based on the Modified Compression Field Theory (MCFT), was first validated against the existing experimental data and then used to generate the required data for cases where no experimental data was available. Several normal and prestressed beams, either simply supported or continuous were used to evaluate the AASHTO and ACI shear design provisions

In addition, the AASHTO LRFD provisions for combined shear and torsion were investigated and their accuracy was validated against the available experimental data. These provisions were also compared to their equivalent ACI code requirements. The latest design procedures in both codes propose exact shear-torsion interaction equations that can directly be compared to the experimental results by considering all  $\varphi$  factors as one. In this comprehensive study, different over-reinforced, moderately-reinforced, and under-reinforced sections with high-strength and normal-strength concrete for both solid and hollow sections were analyzed. The main objectives of this study were to:

- Evaluate the shear and the shear-torsion procedures proposed by AASHTO LRFD (2008) and ACI 318-08
- Validate the code procedures against the experimental results by mapping the experimental points on the code-based exact interaction diagrams
- Develop a MathCAD program as a design tool for sections subjected to shear or combined shear and torsion

# **Table of Contents**

List of Figures vi
List of Tables
Acknowledgementsix
Chapter 1 - Introduction
Overview1
1.1 Objectives
1.2 Scope
Chapter 2 - Literature Review
2.1 Experimental studies on reinforced concrete beams subjected to shear only
2.2 Experimental studies on reinforced concrete beams subjected to combined shear and
torsion
2.3 Procedure for Shear Design of a Concrete Section
2.3.1 AASHTO LRFD General Procedure for Shear Design
2.3.2 Simplified Procedure for Shear Design of Pre-stressed and Non-prestressed Concrete
Beams19
2.3.3 ACI Code Procedure for Shear Design of Pre-stressed and Non-prestressed Reinforced
Concrete Beams
2.4 Design Procedure for Sections under Combined Shear and Torsion
2.4.1 AASHTO LRFD Design Procedure for Sections Subjected to Combined Shear and
Torsion
2.4.2 ACI 318-08 Design Procedure for Sections Subjected to Combined Shear and Torsion
Chapter 3 - Formulation for Evaluating Ultimate Capacity
3.1 Evaluation of Response-2000
3.1.1 Review of Experimental Data Examined and Validity of Response-2000 to Determine
the Shear Strength of a Concrete Section
3.2 Plotting Exact AASHTO LRFD Interaction Diagrams for Combined Shear and Torsion. 34

3.2.1 Exact Shear-Torsion Interaction Diagrams Based on AASHTO LRFD (2008)	
Provisions	35
3.2.2 Exact Shear-Torsion Interaction Diagrams Based on ACI 318-08 Provisions	36
Chapter 4 - Development of AASHTO Based Shear-Torsion Design Tool (MathCAD)	38
Chapter 5 - Results and Discussion	46
5.1 Analysis for Shear Only:	46
5.2 Analysis for Shear and Torsion	52
Chapter 6 - Conclusions and Recommendations	59
Summary:	59
6.1 Conclusions:	59
6.1.1 Members Subjected to Shear Only	59
6.1.2 Members Subjected to Combined Shear and Torsion	60
6.2 Recommendations and possible modifications to AASHTO LRFD Bridge Design	
Specifications (2008)	61
6.3 Suggestions For Future Research	62
References	63

# List of Figures

Figure 2.1 Traditional shear test set-up for concrete beams
Figure 2.2 The ratio of experimental to predicted shear strengths Vs transverse reinforcement for
the panels
Figure 2.3 (a) Cross-section of normal strength, non-prestressed simply supported reinforced
concrete beam (b) Cross-section with the crack control (skin) reinforcement
Figure 2.4 (a) Cross-section of high-strength, continuous non-prestressed reinforced concrete
beam (b) Cross-section with the crack control (skin) reinforcement
Figure 2.5 Profile and cross-section at mid-span of normal strength, simply supported, Double-T
(8DT18) pre-stressed concrete member
Figure 2.6 Profile and sections at mid-span and at end of high strength, continuous Bulb-T (BT-
72) member
Figure 2.8 Typical beam section for
Figure 2.7 Typical beam section tested by Klus (1968)
Figure 2.9 (a) NU2 & HU2 (b) For all other specimens (c) Hollow section NU3 & HU3 (Ref-13)
Figure 3.1 Typical Response-2000 interface
Figure 3.1 Typical Response-2000 interface
Figure 3.1 Typical Response-2000 interface30Figure 3.2 (Vexp/VResp-2000-Depth) Relationship for 34 reinforced concrete sections
Figure 3.1 Typical Response-2000 interface30Figure 3.2 (Vexp/VResp-2000-Depth) Relationship for 34 reinforced concrete sections
<ul> <li>Figure 3.1 Typical Response-2000 interface</li></ul>

Figure 5.6 Predicted shear strength along the length of SE100B-M-69, high strength continuous
non-prestressed reinforced concrete member with longitudinal crack control reinforcement
Figure 5.7 Shear-torsion interaction diagrams along with experimental data for specimens tested
by Klus (1968)
Figure 5.8 Shear-torsion interaction diagrams for RC2 series
Figure 5.9 Shear-torsion interaction diagrams for High-Strength over-reinforced specimens HO-
1, and HO-2
Figure 5.10 Shear-torsion interaction diagram for NO-1 and NO-2
Figure 5.11 Shear-torsion Interaction diagram for High-Strength box section HU-3
Figure 5.12 Shear-torsion interaction diagram for NU-2

# List of Tables

Table 2.1 Details of the cross-section and summary of the experimental results for the sel	ected
panels	6
Table 2.2 Properties of reinforcing bars	12
Table 2.3 Cross-sectional properties of the beam studied	13
Table 3.1 Experimental and Response-2000 shear and moment results at shear-critical	
section of the beams considered	32

# Acknowledgements

I hereby thank my major professor Dr.Asad Esmaeily, my committee members Dr. Hayder Rasheed and Dr. Yacoub Najjar for their continuous support and contribution to this research, also the Kansas Department of Transportation (K-DOT) for their financial support.

## **Chapter 1 - Introduction**

#### Overview

In this study the shear or combined shear and torsion provisions of AASHTO LRFD (2008) Bridge Design Specifications, simplified AASHTO procedure for prestressed and nonprestressed, and ACI 318-08 for reinforced concrete members are comparatively studied. Shearcritical beams were selected to evaluate the shear provisions for the mentioned codes. Because of the absence of experimental data for various beams considered for the analysis and loaded with shear, Response-2000 which is an analytical tool and is based on Modified Compression Field Theory (MCFT) was checked against the experimental data for cases where experimental data existed. Consequently, the shear capacity of simply supported beams was slightly underestimated by Response-2000, while continuous beams were accurately quantified. To evaluate the corresponding shear provisions for AASHTO LRFD and ACI Code; a simply supported double-T beam with harped prestressed strands, continuous bulb-T beam with straight and harped prestressed strands, simply supported and continuous rectangular deep beams with and without longitudinal crack control reinforcement were selected for the analysis. The shear capacity using the aforementioned shear provisions has been calculated at various sections along the beam span and the results are plotted in chapter five of this document.

In addition, the AASHTO LRFD provisions for combined shear and torsion have been investigated and their accuracy has been validated against available experimental data. The provisions on combined shear and torsion have also been compared to the pertinent ACI code requirements for the behavior of reinforced concrete beams subjected to combined shear and torsion. The latest design procedures in both codes lend themselves to the development of exact shear-torsion interaction equations that can be directly compared to experimental results by considering all  $\phi$  factors to be equal to one. In this comprehensive comparison, different sections with high-strength and normal-strength concrete as well as over-reinforced, moderately-reinforced, and under-reinforced sections for both solid and hollow sections were analyzed. The exact interaction diagrams drawn are also included in chapter five of this document.

### **1.1 Objectives**

The objectives of the research are:

- Evaluate shear and shear-torsion procedures proposed by AASHTO LRFD (2008) and ACI 318-08.
- Develop a MathCAD program to design sections subjected to shear or shear and torsion.
- Validate the procedure with experimental results by drawing exact interaction diagrams and mapping experimental points on them

## 1.2 Scope

**Chapter Two** presents the experimental studies on shear or shear and torsion. In addition, design procedure for shear and combined shear and torsion using the AASHTO LRFD (2008) Bridge Design Specifications, and ACI 318-08 are also discussed in detail.

**Chapter Three** addresses the validity of Response-2000 for shear against available experimental data. Furthermore, the procedure to draw exact interaction diagrams using the AASHTO LRFD and ACI Code for beams under combined shear and torsion is discussed.

**Chapter Four** presents the flow chart for the developed MathCAD design tool for shear or shear and torsion.

**Chapter Five** presents the results and discussion with all the necessary plots for shear or shear and torsion.

**Chapter Six** presents the conclusions reached and provides suggestions or recommendations for future research.

## **Chapter 2 - Literature Review**

Beams subjected to combined shear and bending, or combined shear, bending, and torsion frequently happens in practice. Often times one or two of the cases may control the design process while the other considered as secondary. In this study, structural concrete beams subjected to shear or combined shear and torsion are considered while the effects of bending moment are neglected. This chapter is devoted to the experimental studies and explaining the design procedures for the structural reinforced concrete beams with no controlling bending effects.

#### **2.1 Experimental studies on reinforced concrete beams subjected to shear only**

Even though the behavior of structural concrete beams subjected to shear has been studied for more than 100 years, there isn't enough agreement among researchers about how the concrete contributes into shear resistance of a concrete beam. This is mainly because of the many different mechanisms involved in shear transfer process of structural concrete members such as aggregate interlock or interface shear transfer across cracks, shear transfer in compression (un-cracked) zone, dowel action, and residual tensile stresses normal to cracks. However, there is a general agreement among researchers that aggregate interlock and compression zone are the key components of concrete contribution to shear resistance.




Figure 2.1 Traditional shear test set-up for concrete beams

Figure 2.1 shows the traditional shear test set-up for concrete beams. From the figure it is concluded that the region between the concentrated loads applied at the top of the beam is subjected to pure flexure whereas the shear spans are subjected to constant shear and linearly varying bending moment. It is very obvious that the results from such test could not be used to develop a general theory for shear behavior. Since it is almost impossible to design an

experimental program where the beam is only subjected to pure shear, this in turn is one of the main reasons where the true shear behavior of beams has not been understood throughout the decades.

After conducting tests on reinforced concrete panels subjected to pure shear, pure axial load, and a combination of shear and axial load, a complex theory called Modified Compression Field Theory (MCFT) was developed in 1980s from the Compression Field Theory (Vecchio and Collins, 1986). The MCFT was able to accurately predict the shear behavior of concrete members subjected to shear and axial loads. This theory was based on the fact that significant tensile stresses could exist in the concrete between the cracks even at very high values of average tensile strains. In addition, the value for angle  $\theta$  of diagonal compressive stresses was considered as variable compared to the fixed value of 45° assumed by ACI Code.

To simplify the process of predicting the shear strength of a section using the MCFT, the shear stress is assumed to remain constant over the depth of the cross-section and the section is considered as a biaxial element in case any axial stresses are present. This in turn produces the basis of the sectional design model for shear where the AASHTO-LRFD Bridge Design Specifications have been based on (Bentz et,al 2006).

Even though the AASHTO LRFD procedure to predict the shear strength of a section was straight forward, yet the contribution of concrete to shear strength of a section was a function of  $\beta$  and varying angle  $\theta$  for which their values were determined using the tables provided by AASHTO. The factor  $\beta$  indicated the ability of diagonally cracked concrete to transmit tension and shear. The modified compression field theory was even more simplified when simple equations were developed by Bentz et, al (2006) for  $\beta$  and  $\theta$ . These equations were then used to predict the shear strengths of different concrete sections and the results compared to that obtained from MCFT. Consequently the shear strengths predicted by the simplified modified compression field theory and MCFT were compared with the experimental results.

It was found that the results for both simplified modified compression field theory and MCFT were almost exactly similar and both matched properly to the experimental results. In addition, the results were also compared with the ACI Code where it was pretty much inconsistent in particular for panels with no transverse reinforcements.




Figure 2.2 The ratio of experimental to predicted shear strengths Vs transverse reinforcement for the panels

The above figure shows that the ACI method to predict the shear strength of concrete sections subjected to pure shear or a combination of shear and axial load under-estimates the shear capacity of sections. However, the simplified modified compression field theory and MCFT give relatively accurate results. Note that the horizontal line where the ratio of experimental to predicted shear strength equals to one represent a case where the predicted and the experimental results are exactly equal to each other. On the other hand, points above and below that line simply means that the shear strength of a particular section is either under or over-estimated. Because the points corresponding to the shear strength predicted by simplified modified compression filed theory and MCFT are closer to the horizontal line with unit value, it is concluded that the MCFT can accurately predict the shear behavior of a section.

The details of the specimens corresponding to Figure 2.2 are tabulated below. The data provided below is taken from ref (2).

		Reinforcement				Axial load		V <sub>exp</sub> /V <sub>predicted</sub>			
	f' <sub>c</sub> ,	r <sub>x</sub> ,	*f <sub>yx</sub> ,	**S <sub>x</sub> ,							
Panel	MPa	%	Mpa	mm	$r_z f_v / f_c$	***f <sub>x</sub> /v	$V_{exp}/f_c$	MCFT	MCFT	ACI	
Yamaguchi et al, a <sub>g</sub> =20mm											
S-21	19.0	4.28	378	150	0.849	0	0.34	0.89	1.37	1.50	
S-31	30.2	4.28	378	150	0.535	0	0.28	0.80	1.10	1.52	
S-32	30.8	3.38	381	150	0.418	0	0.28	0.87	1.14	1.58	
S-33	31.4	2.58	392	150	0.323	0	0.26	0.86	1.04	1.46	
S-34	34.6	1.91	418	150	0.230	0	0.21	0.91	0.92	1.25	
S-35	34.6	1.33	370	150	0.142	0	0.163	1.15	1.15	0.97	
S-41	38.7	4.28	409	150	0.452	0	0.31	0.95	1.23	1.91	
S-42	38.7	4.28	409	150	0.452	0	0.33	1.02	1.32	2.06	
S-43	41.0	4.28	409	150	0.427	0	0.29	0.91	1.16	1.86	
S-44	41.0	4.28	409	150	0.427	0	0.30	0.94	1.19	1.91	
S-61	60.7	4.28	409	150	0.288	0	0.25	0.90	1.01	1.98	
S-62	60.7	4.28	409	150	0.288	0	0.26	0.91	1.03	2.01	
S-81	79.7	4.28	409	150	0.220	0	0.20	0.92	0.92	1.82	
S-82	79.7	4.28	409	150	0.220	0	0.20	0.92	0.93	1.83	
Andre a <sub>g</sub>	=9mm; K	P a <sub>g</sub> =20	)mm			-					
TP1	22.1	2.04	450	45	0.208	0	0.26	0.92	1.02	1.21	
TP1A	25.6	2.04	450	45	0.179	0	0.22	0.89	0.90	1.14	
KP1	25.2	2.04	430	89	0.174	0	0.22	0.89	0.90	1.12	
TP2	23.1	2.04	450	45	0.199	3	0.114	1.01	1.02	0.72	
KP2	24.3	2.04	430	89	0.18	3	0.106	1.03	1.06	0.68	
TP3	20.8	2.04	450	45	0	3	0.061	1.27	1.34	2.75	
KP3	21	2.04	430	89	0	3	0.054	1.15	1.22	2.47	
TP4	23.2	2.04	450	45	0.396	0	0.35	1.09	1.39	1.68	
TP4A	24.9	2.04	450	45	0.369	0	0.35	1.14	1.41	1.77	
KP4	23	2.04	430	89	0.381	0	0.30	0.94	1.20	1.44	
TP5	20.9	2.04	450	45	0	0	0.093	1.49	1.42	1.28	
KP5	20.9	2.04	430	89	0	0	0.063	1.01	0.98	0.87	

Table 2.1 Details of the cross-section and summary of the experimental results for the selected panels

 $\label{eq:fyx} $$ $$^{f_{yx}} Yield stress of longitudinal reinforcement $$ $$^{x}S_x$ Vertical spacing between the bars aligned in the x-direction $$ $$ $$^{x*s}f_x/v$ Ratio of axial stress to shear stress $$$ 

As stated earlier, the AASHTO LRFD Bridge Design Specifications for shear design are based on the sectional design model which in turn is based on MCFT. The current AASHTO LRFD (2008) bridge design specifications uses the simple equations for  $\beta$  and  $\theta$ . These equations removed the need to use the table provided by AASHTO LRFD to find the values for  $\beta$  and  $\theta$ . In addition, the equations enable the engineers to set up a spread sheet for the shear design calculations.

To evaluate the AASHTO LRFD (2008) shear design procedure for shear-critical sections, six prestressed and non-prestressed reinforced concrete beams were selected for the analysis. Among the total six beams considered, four of them were rectangular non-prestressed reinforced concrete beams which were tested by Collins and Kuchma (1999) and shown in Figure 2.3 and Figure 2.4. The remaining two beams were prestressed Double-T (8DT18) and Bulb-T (BT-72) with harped or a combination of harped and straight tendons shown in Figure 2.5 and Figure 2.6 respectively. Because the AASTHO LRFD shear design procedure takes into account the crack control characteristics of a section, two of the non-prestressed beams were selected to have crack control (skin) reinforcement. Furthermore, to check the AASHTO LRFD shear design provisions for different support conditions, three of the beams were purposefully selected as simply supported and the remaining three as continuous beams.

It is important to note that the experimental data existed for only four of the nonprestressed reinforced concrete beams (BM100, BM100D, SE100A-M-69, and SE100B-M-69) failed in shear at a certain location. Further, the shear strength of the beams at that particular location was also determined using the analytical tool called Response-2000 which is in turn based on MCFT. Since the intention was to evaluate the AASHTO LRFD shear design provisions for different combinations of moment and shear, the predicted shear strengths at different sections throughout the beam was calculated using AASHTO LRFD (2008) and compared to the results obtained from Response-2000. The validity of the results from Response-2000 is discussed in chapter three of this document. Note that Response-2000 was also used to verify the predicted shear strength for the prestressed beams (BT-72, 8DT18). In addition to the AASHTO LRFD (2008), the shear design provisions for the simplified AASHTO and ACI Code were also evaluated.

7




Figure 2.3 (a) Cross-section of normal strength, non-prestressed simply supported reinforced concrete beam (b) Cross-section with the crack control (skin) reinforcement.




Figure 2.4 (a) Cross-section of high-strength, continuous non-prestressed reinforced concrete beam (b) Cross-section with the crack control (skin) reinforcement.




Figure 2.5 Profile and cross-section at mid-span of normal strength, simply supported, Double-T (8DT18) pre-stressed concrete member




Figure 2.6 Profile and sections at mid-span and at end of high strength, continuous Bulb-T (BT-72) member

# 2.2 Experimental studies on reinforced concrete beams subjected to combined shear and torsion

The behavior of reinforced concrete beams subjected to any combination of torsional, bending, and shear stresses have been studied by many researchers and various formulas have been proposed to predict the behavior of these beams. Structural members subjected to combined shear force, bending moment, and torsion are fairly common. However, in some cases one of these actions (shear, bending, or torsion) may be considered as to have a secondary effect and may not be included in the design calculations.

Significant research has been conducted by different researchers to determine the behavior of reinforced concrete beams subjected to any combination of flexural shear, bending, and torsional stresses. Tests performed by Gesund et.al (1964) shown that bending stresses can increase the torsional capacity of reinforced concrete sections. Useful interaction equations for concrete beams subjected to combined shear and torsion have been proposed by Klus (1968).

Moreover, an interesting experimental program was developed by Rahal and Collins (1993) to determine the behavior of reinforced concrete beams under combined shear and torsion. Using similar experimental program, Fouad, et.al (2000) tested a wide range of beams covering normal strength and high strength under-reinforced and over-reinforced concrete beams subjected to pure torsion or combined shear and torsion. Consequently, interesting findings were reported about the contribution of concrete cover to the nominal strength of the beams, modes of failure, and cracking torsion for Normal Strength Concrete (NSC) and High Strength Concrete (HSC).

It is obvious that most of the construction codes practiced today consider in many different ways the effects of any of the combinations of flexural shear, bending, and torsional stresses. In other words, there are a variety of equations proposed by each code to predict the behavior of beams subjected to any possible combination of the stresses mentioned above.

In this study, the current AASHTO LRFD (2008) and ACI 318-08 shear and tosion provisions are evaluated against the available experimental data for beams under combined shear and torsion. In addition, Torsion-Shear (T-V) interaction diagrams are presented for AASTHO LRFD (2008) and ACI and the corresponding experimental data points shown on the plots.

Even though efforts have been made in the past to check the AASHTO LRFD and ACI shear and torsion provisions; in most of those cases it is limited to a certain range of concrete strengths or longitudinal reinforcement ratios  $\rho$ . As an example; Rahal and Collins (2003) have drawn the interaction diagrams using the AASHTO LRFD and ACI shear and torsion provisions for beam series RC2. This series was composed of four beams and subjected to pure shear or combined shear and torsion. The properties for the reinforcing bars and cross-sections for RC2 and other beams studied by the other are tabulated in Table 2.2 and Table 2.3.

The Torsion-Shear (T-V) interaction diagrams for AASHTO LRFD provided by Rahal and Collins have been drawn as linear. In fact, this is because of the absence of equations at that time for the factor  $\beta$  and  $\theta$  which were calculated using discrete data from the Tables proposed by AASHTO. The factors  $\beta$  as defined earlier indicate the ability of diagonally cracked concrete to transmit tension and shear, while  $\theta$  is the angle of diagonal compressive stresses.

		Actual	Yield		Yield		Yield
	Nominal D:	Area	stress		stress		stress
П	Dia(mm)	$(mm^2)$	(Mpa)		(Mpa)	Collins	(Mpa)
et.al	8	50	275		265	Coll	-
	10	77	380	Klus	-		466
oua	12	108	399	KI	-	l and	-
E.Fouad.,	16	193	379		-	Rahal	-
	18	245	386		429	Rá	-
	22	380	-		429		_
	25	468	370		-		480

Table 2.2 Properties of reinforcing bars

	Concrete Dimensions				a	Longit	udinal l	idinal Reinforcement			C.I.	
	Specimen*	Width	Height	Cover	fc	Тор	þ	Bottom		Stirrups		
	-	b <sub>w</sub> (mm)	h (mm)	(mm)	(Mpa)	Type-1**	Type-2	Type-1**	Type-2	Dia (mm)	Spacing,s,(mm)	
	NU1	200	400	20	27.5	2d12	-	2d12	-	8	66.7	
	NU2	220	420	30	26.5	2d12	I	2d12	I	8	66.7	
	NU3 (Box)	100	400	20	26	2d12	I	2d12	I	8	66.7	
_	NU4	200	400	20	28	2d16	3d16	2d16	3d16	8	66.7	
et.al	NU5	200	400	20	27	2d16	3d16	2d16	3d16	8	66.7	
l., e	NU6	200	400	20	26.9	2d16	3d16	2d16	3d16	8	66.7	
uac	NO1	200	400	20	27.2	2d18	3d18	2d18	3d18	12	91	
E.Fouad., et.al	NO2	200	400	20	26.7	2d18	3d18	2d18	3d18	12	91	
Щ	HU1	200	400	20	75.6	2d16	I	2d16	I	10	91	
	HU2	220	420	30	74.9	2d16	1	2d16	I	10	91	
	HU3 (Box)	100	400	20	73.5	2d16	1	2d16	I	10	91	
	HU4	200	400	20	75.1	3d18	3d18	3d18	3d18	10	91	
	HU5	200	400	20	76.4	3d18	3d18	3d18	3d18	10	91	
	HU6	200	400	20	75	3d18	3d18	3d18	3d18	10	91	
	HO1	200	400	20	74.6	2d25	2d25	2d25	2d25	12	77	
	HO2	200	400	20	74	2d25	2d25	2d25	2d25	12	77	
	1	200	300	20***	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	2	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	3	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	4	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
Klus	5	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
KI	6	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	7	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	8	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	9	200	300	20	21.5	2d18,1d22	-	2d18,1d22	-	8	100	
	10	200	300	20	21.5	2d18,1d22	_	2d18,1d22	-	8	100	
pt	RC2-1	340	640	42.5	53.9	5d25	-	5d25	5d25	10	125	
ahal an Collins	RC2-2	340	640	42.5	38.2	5d26	-	5d25	5d25	10	125	
Rahal and Collins	RC2-3	340	640	42.5	42	5d27	-	5d25	5d25	10	125	
R	RC2-4	340	640	42.5	48.7	5d28	-	5d25	5d25	10	125	

Table 2.3 Cross-sectional properties of the beam studied

\* HU=High strength Under reinforced, HO=High strength Over reinforced, NU= Normal

strength Under reinforced, NO= Normal strength over reinforced

\*\* Top layer of reinforcement at the top and lower layer of the bottom reinforcement

\*\*\* The cover was not given, it was assumed as being 200 mm.

During this study, exact Torsion-Shear (T-V) interaction diagrams were drawn using the AASHTO LRFD (2008) shear and torsion provisions. The word exact is used to indicate that the shear and torsion relationships are not assumed as linear. This is due to the fact that the proposed tables for  $\beta$  and  $\theta$  have been replaced by the simple equations provided in the current AASHTO LRFD Bridge Design Specifications for shear and torsion.

For comprehensive evaluation of the AASHTO LRFD and ACI 318-08 shear and torsion equations for design, a wide range of specimens made of high-strength and normal strength concrete loaded with shear, torsion, or a combination of both were investigated in this study. The cases studied included under-reinforced, moderately-reinforced, and over-reinforced sections. Among the total 30 specimens studied, 22 were made of normal strength concrete while the remaining eight were specimens with high-strength concrete. Two hollow under-reinforced specimens, one made of high-strength and the other made of normal strength concrete were considered as well. The procedure for drawing the exact interaction diagrams are described in detail in chapter three of this document. Figures given below show some of the cross-sections for the specimens considered.




Figure 2.8 Typical beam section for RC2 series tested by Rahal and Collins (2003)




Figure 2.7 Typical beam section tested by Klus (1968)




Figure 2.9 (a) NU2 & HU2 (b) For all other specimens (c) Hollow section NU3 & HU3 (Ref-13)

#### 2.3 Procedure for Shear Design of a Concrete Section

The AASHTO LRFD Bridge Design Specifications (2008) proposes three methods to design a prestressed or non-prestressed concrete section for shear. It is important to understand that all requirements set by AASHTO to qualify a particular method have to meet prior to application of

that method. In this document only two methods to design a section for shear i.e., the general procedure and the simplified procedure for prestressed and non-prestressed members are discussed in detail. In addition, the current ACI provisions for shear design of a concrete section are described briefly.

#### 2.3.1 AASHTO LRFD General Procedure for Shear Design

The AASHTO LRFD general procedure to design or determine the shear strength of a section is based on the Modified Compression Field Theory (MCFT). As stated earlier, this theory has proved to be very accurate in predicting the shear capacity of a prestressed or non-prestressed concrete section. It is important to note that the current AASTHO LRFD provisions for the general method are based on the simplified MCFT.

The nominal shear strength of a section for all three methods is equal to

$$V_n = V_c + V_s + V_P$$
 (Eq - 2.3.1)

where:

 $V_n$  = nominal shear strength

 $V_c$  = nominal shear strength provided by concrete

 $V_s$  = nominal shear strength provided by shear reinforcement

 $V_p$  = component in the direction of the applied shear of the effective prestressing force

 $V_c$  is a function of a factor  $\beta$  which shows the ability of diagonally cracked concrete to transmit tension and shear. The factor  $\beta$  is inversely proportional to the strain in longitudinal tension reinforcement,  $\varepsilon_s$ , of the section. For sections containing at least the minimum amount of transverse reinforcement, the value of  $\beta$  is determined as

$$\beta = \frac{4.8}{(1+750\varepsilon_s)}$$
 (Eq - 2.3.2)

When sections do not contain at least the minimum amount of shear reinforcement, the value of  $\beta$  is determined as follow

$$\beta = \frac{4.8}{(1+750\varepsilon_s)} \frac{51}{(39+s_{xe})} \qquad (Eq-2.3.3)$$

The above equations are valid only if the concrete strength  $f'_c$  is in psi and  $s_{xe}$  in inches. If the concrete strength  $f'_c$  is in MPa and  $s_{xe}$  in mm, then 4.8 in Eq-2.3 becomes 0.4 while 51 and 39 in Eq 2.3.3 become 1300 and 1000 respectively.

 $s_{xe}$  is called the crack spacing parameter which can be estimated as

$$s_{xe} = s_x \frac{1.38}{a_q + 0.63} \qquad (Eq - 2.3.4)$$

 $s_x$  is the vertical distance between horizontal layers of longitudinal crack control (skin) reinforcement) and  $a_g$  is the maximum aggregate size in inches and has to equal zero when  $f'_c \ge 10$  ksi. Note that if the concrete strength is in MPa and  $s_{xe}$  in mm, the 1.38 and 0.63 in Eq-2.3.4 should be replaced by 35 and 16 respectively.

The nominal shear strength provided by the concrete  $V_c$  for the general procedure is equal to  $\beta \sqrt{f'_c} b_v d_v$  when the concrete strength is in MPa. However,  $V_c = 0.0316\beta \sqrt{f'_c} b_v d_v$  in case  $f'_c$  is in ksi. The coefficient 0.0316 is  $\frac{1}{1000}$  and is used to convert the  $V_c$  from psi to ksi.

The nominal shear strength provided by the shear reinforcement can be estimated as

$$V_s = \frac{A_v f_y d_v \cot\theta}{s} \qquad (Eq - 2.3.5)$$

where:

 $A_v$  = area of shear reinforcement within a distance s (in.<sup>2</sup>)

 $f_y$  = yield stress of shear (transverse) reinforcement in ksi or psi depending on the case.

 $d_v$  = effective shear depth (in.) and is equal to  $(d_v = \frac{A_{ps}f_{ps}d_p + A_sf_yd_s}{A_{ps}f_{ps} + A_sf_y})$ . Note that  $d_v \ge d_v$ 

Max(0.9d, 0.72h)

 $b_v$  = effective web width (in.)

s = spacing of stirrups (in.)

 $\theta$  = angle of inclination of diagonal compressive stresses (°) as determined below

$$\theta = 29(\text{degree}) + 3500\varepsilon_s \qquad (Eq - 2.3.6)$$

The above equation is independent of which units are used for  $f'_c$  or  $s_{xe}$ . The strain in longitudinal tension reinforcement  $\varepsilon_s$  is calculated using the following equation

$$\varepsilon_{s} = \frac{\left(\frac{|M_{u}|}{d_{v}} + 0.5N_{u} + |V_{u} - V_{p}| - A_{ps}f_{po}\right)}{E_{s}A_{s} + E_{p}A_{ps}}$$
(Eq - 2.3.7)

where:

 $M_u$  = factored moment, not to be taken less than  $(V_u - V_p)d_v$  (kip-in.)

 $N_u$  = factored axial force, taken as positive if tensile and negative if compressive (kip)  $V_u$  = factored shear force (kip)

 $A_{ps}$  = area of prestressing steel on the flexural tension side of the member (in.<sup>2</sup>)

 $f_{po} = 0.7$  times the specified tensile strength of pre-stressing steel,  $f_{pu}$  (ksi)

 $E_s$  = modulus of elasticity of non-prestressed steel on flexural tension side of the section

 $E_p$  = modulus of elasticity of pre-stressing steel on the flexural tension side of the section

 $A_s$  = area of non-prestressed steel on the flexural tension side of the section (in.<sup>2</sup>)

To make sure that the concrete section is large enough to support the applied shear, it is required that  $V_c + V_s$  should not exceed  $0.25f'_c b_v d_v$ . Otherwise, enlarge the section.

#### 2.3.1.1 Minimum Transverse Reinforcement

If the applied factored shear  $V_u$  is greater than the value of  $0.5\phi(V_c + V_p)$ ; shear reinforcement is required. The amount of minimum transverse reinforcement can be estimated as

$$A_v \ge 0.0316 \sqrt{f'_c} \frac{b_v s}{f_y}$$
 (Eq - 2.3.8)

#### 2.3.1.2 Maximum Spacing of Transverse Reinforcement

According to the AASHTO LRFD Bridge Design Specifications, the spacing of the transverse reinforcement shall not exceed the maximum permitted spacing,  $s_{maz}$  determined as

• If  $v_u(ksi) < 0.125 f'_c$ , then  $s_{max} = 0.8d_v \le 24$  in.

• If  $v_u(ksi) \ge 0.125 f'_c$ , then  $s_{max} = 0.4 d_v \le 12.0$  in.

Where  $v_u$  is calculated as

$$v_u = \frac{|V_u - \phi V_p|}{b_v d_v}$$
 (Eq - 2.3.9)

# 2.3.2 Simplified Procedure for Shear Design of Pre-stressed and Non-prestressed Concrete Beams

The nominal shear strength provided by the concrete  $V_c$  for perstressed and non-prestressed beams not subject to significant axial tension and containing at least the minimum amount of transverse reinforcement (specified in section 2.3.1.1 of this document) can be determined as the minimum of  $V_{ci}$  or  $V_{cw}$ .

$$V_{ci} = 0.02\sqrt{f'_c}b_{\nu}d_{\nu} + V_d + \frac{V_iM_{cre}}{M_{max}} \ge 0.06\sqrt{f'_c}b_{\nu}d_{\nu} \qquad (Eq - 2.3.10)$$

where:

 $V_{ci}$  = nominal shear resistance provided by concrete when inclined cracking results from combined shear and moment (kip)

 $V_d$  = shear force at section due to unfactored dead load and include both concentrated and distributed dead loads

 $V_i$  = factored shear force at section due to externally applied loads occurring simultaneously with  $M_{max}$  (kip)

 $M_{cre}$  = moment causing flexural cracking at section due to externally applied loads (kipin)

 $M_{max}$  = maximum factored moment at section due to externally applied loads (kip-in)

$$M_{cre} = S_c \left( f_r + f_{cpe} - \frac{M_{dnc}}{S_{nc}} \right) \qquad (Eq - 2.3.11)$$

where:

 $S_c$  = section modulus for the extreme fiber of the composite section where tensile stress is caused by externally applied loads (in.<sup>3</sup>)

 $f_r$  = rupture modulus (ksi)

 $f_{cpe}$  = compressive stress in concrete due to effective prestress forces only (after allowance for all pre-stress losses) at extreme fiber of section where tensile stress is caused by externally applied loads (ksi)

 $M_{dnc}$  =total unfactored dead load moment acting on the monolithic or noncomposite section (kip-in.)

The web shear cracking capacity of the section can be estimated as

$$V_{cw} = \left(0.06\sqrt{f'_{c}} + 0.30f_{pc}\right)b_{v}d_{v} + V_{p} \qquad (Eq - 2.3.12)$$

where:

 $V_{cw} = n$ ominal shear resistance provided by concrete when inclined cracking results from excessive principal tensions in web (kip)

 $f_{pc}$  = compressive stress in concrete (after allowance for all prestress losses) at centroid of cross-section resisting externally applied loads or at junction of web and flange when the centroid lies within the flange (ksi). In a composite member,  $f_{pc}$  is the resultant compressive stress at the centroid of the composite section, or at junction of web and flange, due to both pre-stress and moments resisted by precast member acting alone.

After calculating the flexural shear cracking and web shear cracking capacities of the section, i.e.,  $V_{ci}$  and  $V_{cw}$ ; the minimum of the two values is selected as the nominal shear strength provided by concrete. The nominal shear strength provided by the shear reinforcement is calculated exactly the same as in Eq-2.3.5 with the only difference that  $cot\theta$  is calculated as following

• If 
$$V_{ci} < V_{cw}$$
;  $cot\theta = 1$ 

• If 
$$V_{ci} > V_{cw}$$
;  $cot\theta = 1.0 + 3\left(\frac{f_{pc}}{\sqrt{f'c}}\right) \le 1.8$  (Eq-2.3.13)

To make sure that the concrete section is large enough to support the applied shear, it is required that  $V_c + V_s$  should not exceed  $0.25f'_c b_v d_v$ . Otherwise, enlarge the section. This is condition is exactly similar to the AASHTO general procedure explained above. Note that the amount of minimum transverse reinforcement and the maximum spacing for stirrups is calculated the same

as in sections 2.3.1.1 and 2.3.1.2 of this document. More importantly, the amount of longitudinal reinforcement should also be checked at all sections considered. This is true for both general and simplified procedures described above. AASHTO LRFD (2008) proposes the following equation to check the capacity of longitudinal reinforcement

$$A_{ps}f_{ps} + A_sf_y \ge \frac{|M_u|}{d_v\phi_f} + 0.5\frac{N_u}{\phi_c} + \left(\left|\frac{V_u}{\phi_v} - V_p\right| - 0.5V_s\right)cot\theta \qquad (Eq - 2.3.14)$$

where:

 $\phi_f \phi_v \phi_c$  = resistance factors taken from Article 5.5.4.2 of AASHTO LRFD (2008) as

appropriate for moment, shear and axial resistance.

For the general procedure, the value for  $\theta$  in degree is calculated using Eq-2.3.4. However, the value for *cot* $\theta$  is directly calculated from Eq-2.3.13 for the simplified procedure for prestressed and non-prestressed beams.

# 2.3.3 ACI Code Procedure for Shear Design of Pre-stressed and Non-prestressed Reinforced Concrete Beams

ACI Code 318-08 presents a set of equations to predict the nominal shear strength of a reinforced concrete section. Experiments have shown that the ACI provisions for shear underestimate the shear capacity of a given section and are uneconomical. However, it was recognized that ACI equations for shear over-estimates the shear capacity for large lightly reinforced concrete beams without transverse reinforcement Shioya, et.al (1989).

As stated earlier, the nominal shear strength of a concrete section is the summation of the nominal shear strengths provided by the concrete  $V_c$  and the transverse reinforcement  $V_s$ . The value of  $V_c$  for a non-prestressed concrete section subjected only to shear and flexure can be estimated as

$$V_c = 2\lambda \sqrt{f'_c} b_w d \qquad (Eq - 2.3.15)$$

In addition to the equation above, ACI 318-08 proposes a detailed equation in which the effects of bending moment present at the section is also considered.

$$V_{c} = \left(1.9\lambda \sqrt{f'_{c}} + 2500\rho_{w} \frac{V_{u}d}{M_{u}}\right) b_{w}d \qquad (Eq - 2.3.16)$$

Whereas the shear strength provided by the concrete for pre-stressed members can be estimated using the following equations

$$V_{ci} = 0.6\lambda \sqrt{f'_c} b_w d_p + V_d + \frac{V_i M_{cre}}{M_{max}} \ge 1.7\lambda \sqrt{f'_c} b_w d \qquad (Eq - 2.3.17)$$

or

$$V_{cw} = \left(3.5\lambda \sqrt{f'_{c}} + 0.3f_{pc}\right) b_{w} d_{p} + V_{p} \qquad (Eq - 2.3.18)$$

where  $d_p$  need not be taken less than 0.80*h* for both equations. The value of moment causing flexural cracking due to externally applied loads,  $M_{cre}$  at a certain section in (lb.in) is

$$M_{cre} = \frac{I}{y_t} \left( 6\lambda \sqrt{f'_c} + f_{pe} - f_d \right) \qquad (Eq - 2.3.19)$$

where:

 $f_{pe}$  = compressive stress in concrete due to effective pre-stress forces only (after allowance for all pre-stress losses) at extreme fiber of section where tensile stress is caused by externally applied loads (psi).

After calculating the values for  $V_{ci}$  and  $V_{cw}$ , the nominal shear strength provided by the concrete  $V_c$  is assumed as the minimum of  $V_{ci}$  or  $V_{cw}$ . It is important to note that the inclination angle  $\theta$  for the diagonal compressive stress is assumed as 45° in the shear provisions of the ACI Code. Hence to determine  $V_s$  which is the nominal shear strength provided by the shear reinforcement, Eq-2.3.5 is modified to

$$V_s = \frac{A_v f_{yt} d_v}{s} \tag{Eq - 2.3.20}$$

#### 2.3.3.1 Minimum Transverse Reinforcement

According to section 11.4.6.1 of the ACI Code, a minimum area of shear reinforcement  $A_{v,min}$  shall be provided in all reinforced concrete flexural members (prestressed and non-prestressed) where  $V_u$  exceeds  $0.5\phi V_c$ , except in members satisfying the cases specified by the code.

$$A_{\nu,min} = 0.75 \sqrt{f'_c} \frac{b_w s}{f_{yt}}$$
 (Eq - 2.3.21)

but shall not be less than  $\frac{50b_W s}{f_{yt}}$ . Also the concrete strength  $f'_c$  should be in psi.

According to section 11.4.6.4 of ACI Code, for pre-stressed members with an effective pre-stress force not less than 40 percent of the tensile strength of the flexural reinforcement,  $A_{v,min}$  shall not be less than the smaller value of (Eq-2.3.21) and (Eq-2.3.22).

$$A_{v,min} = \frac{A_{ps}f_{pu}s}{80f_{yt}d}\sqrt{\frac{d}{b_w}} \qquad (Eq - 2.3.22)$$

The above explanation can be written explicitly as

.

$$A_{\nu,min} = Min \left\{ Max \left( 0.75 \sqrt{f'_c} \frac{b_w s}{f_{yt}}, \frac{50b_w s}{f_{yt}} \right), \frac{A_{ps} f_{pu} s}{80 f_{yt} d} \sqrt{\frac{d}{b_w}} \right\}$$
(Eq - 2.3.23)

#### 2.3.3.2 Maximum Spacing of Transverse Reinforcement

According to section 11.4.5.1 of the ACI Code, spacing of shear reinforcement placed perpendicular to axis of member shall not exceed d/2 for non-prestressed members or 0.75*h* for prestressed members, nor 24 in. The maximum spacing shall be reduced by one-half if  $V_s$  exceeds  $4\sqrt{f'_c}b_w d$ . Furthermore, if the value for  $V_s$  exceed  $8\sqrt{f'_c}b_w d$ , the concrete at the section may crush. To avoid crushing of the concrete, a larger section should be selected.

#### 2.4 Design Procedure for Sections under Combined Shear and Torsion

Section 5.8.3.6 of the AASTHO LRFD Bridge Design Specifications (2008) provides pertinent equations to design a concrete section under combined shear and torsion. The procedure is mainly based on the general method for shear discussed earlier. No details have been provided in the code about how to design a section for combined shear and torsion if the simplified approach is used for the shear part. Hence, only the design procedure which is in the code is discussed here. At the end, the ACI procedure to design a section under combined shear and torsion is explained.

# 2.4.1 AASHTO LRFD Design Procedure for Sections Subjected to Combined Shear and Torsion

As stated earlier, the AASHTO LRFD general procedure is used to design a section under combined shear and torsion. The section is primarily designed for bending. The geometry and the

external loads applied on the section are then used to check the shear-torsion strength of the section. Since design is an iterative process, the cross-sectional properties and the reinforcement both longitudinal and transverse are provided different values until the desired shear-torsion strength is achieved.

Below are the necessary steps to design a section for shear and torsion:

- Determine the external loads applied on the section considered. To do this, the beam has to be analyzed for the external loads using the load combination that provide the maximum load effects. The section is then designed for bending and the cross-sectional dimensions and the amount of longitudinal reinforcement are roughly determined.
- 2. Having the external load effects (axial force, shear, and bending moment) at the section, the strain in the longitudinal tension reinforcement  $\varepsilon_s$  is calculated using Eq-2.3.7 provided above. It is required to substitute  $V_u$  in Eq-2.3.7 with the equivalent shear  $V_{u,eq}$ .

For solid sections:

$$V_{u,eq} = \sqrt{V_u^2 + \left(\frac{0.9P_h T_u}{2A_0}\right)^2}$$
 (Eq - 2.4.1)

For box sections:

$$V_{u,eq} = V_u + \frac{T_u d_s}{2A_0}$$
 (Eq - 2.4.2)

- 3. To determine the nominal shear strength of a section provided by concrete,  $V_c$ , the value of  $\varepsilon_s$  from step 2 is substituted into Eq-2.3.2 to determine the value for  $\beta$ . If the concrete strength  $f'_c$  is provided in ksi, then  $V_c = 0.0316\beta\sqrt{f'_c}b_v d_v$ . Otherwise  $V_c = \beta\sqrt{f'_c}b_v d_v$  if  $f'_c$  is given in MPa units.
- 4. Substitute the value of  $\varepsilon_s$  obtained from step 2 into Eq-2.3.6 to determine the modified angle of inclination of diagonal compressive stresses  $\theta$  (in degrees).
- 5. Is shear reinforcement required? no shear reinforcement is required if  $V_u < 0.5\phi(V_c + V_p)$
- 6. If  $V_u > 0.5\phi(V_c + V_p)$ , solve Eq-2.3.5 for  $\frac{A_v}{s}$  after substituting the value for  $\theta$  obtained in step 4. Note that  $V_s = \frac{V_u}{\phi} V_c V_p$

7. Calculate the torsional cracking moment for the section considered using the given

equation: 
$$T_{cr} = 0.125 \sqrt{f'_c} \frac{A_{cp}^2}{P_c} \sqrt{1 + \frac{f_{pc}}{0.125 \sqrt{f'_c}}}$$
 (Eq - 2.4.3)

where:

 $T_u$  = factored torsional moment (kip-in.)

 $T_{cr}$  = torsional cracking moment (kip-in.)

 $A_{cp}$  = total area enclosed by outside perimeter of concrete cross-section (in.<sup>2</sup>)

 $P_c$  = length of the outside perimeter of the concrete section (in.)

 $f_{pc}$  = compressive stress in concrete after prestress losses have occurred either at the centroid of the cross-section resisting transient loads or at the junction of the web and flange where the centroid lies in the flange (ksi).

 $\phi = 0.9$  (specified in Article 5.5.4.3 of the AASHTO LRFD (2008)

8. Should torsion be considered? If the external factored torsional moment  $T_u$  applied on the section is such that  $T_u > 0.25\phi T_{cr}$ , torsion must be considered. Otherwise, ignore the torsion.

$$T_n = \frac{2A_0A_tf_{yt}\cot\theta}{s} \tag{Eq-2.4.4}$$

where:

 $A_0$  = area enclosed by the shear flow path, including any area of holes therein (in.<sup>2</sup>). It is permitted to take  $A_0$  as 85% of the area enclosed by the centerline of stirrups.  $A_t$  = area of one leg of closed transverse torsion reinforcement in solid members (in.<sup>2</sup>)  $\theta$  = angle of crack as determined in accordance with Eq-2.3.6 using the modified strain  $\varepsilon_s$  calculated in step 2.

9. Solve Eq-2.4.4 for  $\frac{2A_t}{s}$  and sum it with the output of step 5.

$$\frac{A_{\nu+t}}{s} = \frac{A_{\nu}}{s} + \frac{2A_t}{s}$$
 (Eq - 2.4.5)

10. The amount of transverse reinforcement obtained from step 8 should be equal to or greater than the amount given by the equation below

$$A_{v,min} \ge 0.0316\sqrt{f'_c} \frac{b_v s}{f_{yt}}$$
 (Eq - 2.4.6)

- 11. According to the AASHTO LRFD, the spacing of transverse reinforcement shall not exceed the maximum permitted spacing,  $s_{max}$ , determined as:
  - If  $v_u(ksi) < 0.125 f'_c$ , then  $s_{max} = 0.8d_v \le 24$  in.
  - If  $v_u(ksi) \ge 0.125 f'_c$ , then  $s_{max} = 0.4 d_v \le 12.0$  in.

Note that  $v_u$  given in Eq-2.3.9 is modified for torsion using  $V_{u,eq}$  provided by Eq's-2.4.1 and 2.4.2

- 12. Is the cross-section large enough? If  $V_c + V_s < 0.25 f'_c b_v d_v$ , the section is large enough, otherwise enlarge the section.
- 13. As a last step, the longitudinal reinforcement in solid sections shall be proportioned to satisfy

$$A_{ps}f_{ps} + A_{s}f_{y} \ge \frac{|M_{u}|}{\phi d_{v}} + \frac{0.5N_{u}}{\phi} + \cot\theta \sqrt{\left(\left|\frac{V_{u}}{\phi} - V_{p}\right| - o.5V_{s}\right)^{2} + \left(\frac{0.45P_{h}T_{u}}{2A_{0}\phi}\right)^{2}} \qquad (Eq - 2.4.7)$$

while for box sections the longitudinal reinforcement for torsion, in addition to that required for flexure, shall not be less than

$$A_l = \frac{T_n P_h}{2A_0 f_y} \tag{Eq - 2.4.8}$$

# 2.4.2 ACI 318-08 Design Procedure for Sections Subjected to Combined Shear and Torsion

To design a pre-stressed or non-prestressed member under combined shear and torsion loading using the ACI 318-08 provisions, the following steps can be followed:

 Should torsion be considered? If the applied torsion on a section (pre-stressed or nonprestressed) is greater than the corresponding value given by Eq-2.4.9, the section has to be designed accordingly. Otherwise, torsion is not a concern and could be ignored. For non-prestressed members:

$$T_{th} = \phi \lambda \sqrt{f'_c} \left(\frac{A^2_{cp}}{P_{cp}}\right) \qquad (Eq - 2.4.9a)$$

For pre-stressed members:

$$T_{th} = \phi \lambda \sqrt{f'_c} \left(\frac{A^2_{cp}}{P_{cp}}\right) \sqrt{1 + \frac{f_{pc}}{4\lambda \sqrt{f'_c}}} \qquad (Eq - 2.4.9b)$$

 $P_{cp}$  is the outside perimeter of concrete cross-section and is equal to  $P_c$  defined earlier.

 $\phi$  is the resistance factor which is equal to 0.75. Note that  $T_{th}$  is the threshold torsion.

2. Equilibrium or compatibility torsion? According to section 11.5.2.1 of ACI Code, if the applied factored torsion,  $T_u$  in a member is required to maintain equilibrium and is greater than the value given by Eq-2.4.9 depending on whether the member is prestressed or non-prestressed, the member shall be designed to carry  $T_u$ . However, in a statically indeterminate structure where significant reduction in  $T_u$  may occur upon cracking, the maximum  $T_u$  is permitted to be reduced to the values given by Eq-2.4.10.

For non-prestressed members:

$$T_u = \phi 4\lambda \sqrt{f'_c} \left(\frac{A^2_{cp}}{P_{cp}}\right) \qquad (Eq - 2.4.9a)$$

For pre-stressed members:

$$T_u = \phi 4\lambda \sqrt{f'_c} \left(\frac{A^2_{cp}}{P_{cp}}\right) \sqrt{1 + \frac{f_{pc}}{4\lambda \sqrt{f'_c}}} \qquad (Eq - 2.4.9b)$$

3. Is the section large enough to resist the applied torsion? To avoid crushing of the surface concrete due to inclined compressive stresses, the section shall have enough cross-sectional area. The surface concrete in hollow members may crush soon on the side where the flexural shear and torsional shear stresses are added.

For solid sections:

$$\sqrt{\left(\frac{V_u}{b_w d}\right)^2 + \left(\frac{T_u P_h}{1.7A_{oh}^2}\right)^2} \le \phi\left(\frac{V_c}{b_w d} + 8\sqrt{f'_c}\right) \qquad (Eq - 2.4.10a)$$

For hollow sections:

$$\left(\frac{V_u}{b_w d}\right) + \left(\frac{T_u P_h}{1.7A_{oh}^2}\right) \le \phi\left(\frac{V_c}{b_w d} + 8\sqrt{f'_c}\right) \qquad (Eq - 2.4.10b)$$

Note that the above equations can be used both for pre-stressed and non-prestressed members. For pre-stressed members, the depth d in the above equations is taken as the distance from extreme compression fiber to centroid of the prestresses and non-prestressed longitudinal tension reinforcement but need not be taken less than 0.80h.

4. The stirrups area required for the torsion is calculated using Eq-2.4.4. This area is then added to the stirrups area required by shear calculated based on Eq-2.3.20. The angle  $\theta$  in Eq-2.4.4 is assumed as 45° for non-prestressed and 37.5° for prestressed members.

5. The minimum area of transverse reinforcement required for both torsion and shear shall not be less than

$$\frac{A_v + 2A_t}{s} \ge 0.75 \sqrt{f'_c} \frac{b_w s}{f_{yt}}$$
 (Eq - 2.4.11)

note that the spacing for transverse torsion reinforcement shall not exceed the smaller of  $\frac{P_h}{8}$  or 12 in.

6. he longitudinal reinforcement required for torsion can be calculated using the following equation

$$A_{l} = \left(\frac{A_{t}}{s}\right) P_{h}\left(\frac{f_{yt}}{f_{y}}\right) \cot^{2}\theta \qquad (Eq - 2.4.12)$$

The required longitudinal reinforcement for torsion should not be less than the minimum reinforcement proposed by ACI and given below

$$A_{l,min} = \frac{5\sqrt{f'_{c}A_{cp}}}{f_{y}} - \left(\frac{A_{t}}{s}\right)P_{h}\frac{f_{yt}}{f_{y}}$$
 (Eq - 2.4.13)

## **Chapter 3 - Formulation for Evaluating Ultimate Capacity**

The purpose of this chapter is to evaluate the analytical tool used to determine the shear capacity of a concrete section and develop exact interaction diagrams for concrete members subjected to combined shear and torsion. In chapter two of this document, necessary information about Modified Compression Field Theory (MCFT) and its application to determine the shear or combined shear and torsion capacity of a section were provided. Research performed by Bentz et.al (2006) showed that the MCFT and its simplified version give almost exactly the same results and conforms well to the experimental results. In this chapter, output from an analytical tool called Response-2000 which is based on modified compression field theory is evaluated. In addition, exact interaction diagram for the general procedure of AASHOT LRFD are drawn.

## 3.1 Evaluation of Response-2000

Response-2000 was developed by Bentz and Collins (2000). This windows program is based on MCFT which can analyze moment-shear, shear-axial load, and moment-axial load responses of a concrete section. Response-2000 is designed to obtain response of a section using the initial input data. The input data depends on the desired response of a section i.e., moment-shear, shear-axial load, moment-axial load.

Knowing the fact that Response-2000 is based on MCFT, the output values may shift slightly compared to AASHTO-LRFD (2008) general procedure for shear which is based on simplified MCFT.




Figure 3.1 Typical Response-2000 interface

# 3.1.1 Review of Experimental Data Examined and Validity of Response-2000 to Determine the Shear Strength of a Concrete Section

The purpose of this section is to show how close Response-2000 can approximate the shear capacity of a member at a particular section. To study the shear behavior of concrete members, often times simply supported rectangular reinforced concrete beams without shear reinforcement are tested in research laboratories. These beams often have a depth of 15 in. or less and loaded with point loads over short shear spans (NCHRP-549). Unfortunately these tests can not represent real cases such as deep continuous bridge girders supporting distributed loads and have shear reinforcement. To address this deficiency in available experimental data and generate experimental data for cases similar to real-world situations for which no experimental data exists,

the output from Response-2000 was evaluated for 34 beams. The experimental shear strengths for these beams were taken from ref (1).

Among the 34 beams selected, 22 beams were simply supported (Figure 2.3) with an overall depth, d, ranging between 125mm to 1000mm. These beams had a constant cross-sectional width,  $b_w$ , of 300mm, longitudinal reinforcement ratio,  $\rho_l$  of 0.5% to1.31%, and varying compressive strength,  $f'_c$  of 36 MPa to 98.8 MPa. The yield strength of longitudinal and shear reinforcement varied from 475 MPa to 550 MPa. In addition, two beams had shear reinforcement of #3 bars spaced 660 mm apart while the remaining twenty beams didn't have any shear reinforcement.

Twelve beams from the total 34 beams selected for the analysis were continuous (Figure 2.4) with an overall depth, d, and cross-sectional width, $b_w$  each ranging between 500 mm to 1000 mm and 169mm to 295 mm respectively. The longitudinal reinforcement ratio,  $\rho_l$ , varied between 1.03 to 1.36% while the concrete compressive strength,  $f'_c$  varied between 50 MPa and 91 MPa. The yield strength for the longitudinal and shear reinforcements varied between 475 MPa and 593 MPa. Four beams from the total twelve beams studied had shear reinforcement of D4 with spacing ranging between 276 mm to 440 mm.

All of the beams were shear critical in the sense that the member had enough capacity to support the associated bending moment. The longitudinal reinforcements for the simply supported beams were continued up to the ends. However, the longitudinal reinforcements for continuous beams were cut-off where bending moment had lower values. The critical section for the simply supported beam was assumed to be at the middle of the beam. This is due to the fact that the bending moment is a maximum at the middle and reduces from the full shear capacity of the section while the critical section for the continuous beam was located 1.2 m from the right support. The critical section is not necessarily where shear is a maximum; rather it is a section along the beam where the beam tends to fail in shear. For continuous beams, the critical section were not continued further. This in turn helped the strain  $\varepsilon_s$  to increase. Because the provided shear reinforcement was not enough, the cross-section was assumed to fail at that location.

To make sure that the beam exactly fails at this location, the shear-moment capacity along the length of the beam was determined using Respons-2000 and the location so called the critical-section provided the lowest moment-shear capacity. The experimental shear and moment capacity and the capacity determined using Response-2000 at shear-critical sections is tabulated in Table 3.1 .

		Simply Supported and Continuous* Beams						
		Beam Type	Beam Depth (mm)	Exp.Shear Force(KN)	Exp.Moment (KN.m)	Response 2000 (KN)	Resp-2000 Moment (KN.m)	V <sub>exp</sub> /V <sub>resp2000</sub>
Normal strength concrete	w/o crack control reinf.	B100	925	225	633.26	176	495.80	1.28
		BN100	925	192	544.16	175.3	496.90	1.10
		BN50	450	132	181.42	100.5	137.90	1.31
		BN25	225	73	49.68	57.6	39.50	1.27
		BN12	110	40	13.01	32.3	10.50	1.24
		B100L	925	223	627.86	158.9	447.70	1.40
		B100B	925	204	576.56	165.3	465.80	1.23
		BM100(w/stirrups)	925	342	949.16	317.5	874.90	1.08
		SE100A-45	920	201	274.49	221.06	299.20	0.909
		SE50A-45	459	69	43.78	79.91	51.00	0.863
	With crack control reinf.	B100D	925	320	889.76	213.9	595.20	1.50
		BND100	925	258	722.36	201.1	570.30	1.28
		BND50	450	163	223.27	108	147.90	1.51
		BND25	225	112	76.00	64.2	43.60	1.74
		BM100D (w/stirrups)	925	461	1270.46	308.8	851.20	1.49
		SE100B-45	920	281	370.46	261.56	346.30	1.074
		SE50B-45	459	87	54.57	88.82	56.40	0.980
High strength concrete	w/o crack control reinf.	В100Н	925	193	546.86	222.7	627.20	0.87
		B100HE	925	217	611.66	222.7	627.20	0.97
		BH100	925	193	546.86	215.5	610.90	0.90
		BH50	450	132	181.42	123.5	169.30	1.07
		BH25	225	85	57.78	68.6	46.80	1.24
		BRL100	925	163	465.86	167.6	479.40	0.97
		SE100A-83	920	303	396.86	256.36	340.40	1.182
		SE100A-M-69 (w/stirrups)	920	516	652.39	521.56	658.50	0.989
		SE50A-83	459	93	58.17	92.31	57.90	1.007
		SE50A-M-69 (w/stirrups)	459	139	85.77	142.31	88.20	0.977
	With crack control reinf.	BHD100	925	278	776.36	252.8	706.00	1.10
		BHD50	450	193	263.77	134.4	184.70	1.44
		BHD25	225	111	75.33	81.9	55.30	1.36
		SE100B-83	920	365	471.24	297.16	388.60	1.228
		SE100B-M-69 (w/stirrups)	920	583	732.77	637.57	797.90	0.914
		SE50B-83	459	101	62.97	101.32	63.50	0.997
		SE50B-M-69 (w/stirrups)	459	152	93.56	154.21	95.40	0.986

Table 3.1 Experimental and Response-2000 shear and moment results at shear-critical section of the beams considered

\* Data for continuous beams are shown shaded.

To generate data using Response-2000, the experimental shear and moment at shear critical sections and the necessary properties of the section such as  $f'_c$ ,  $f_y$ ,  $b_w$ , h, and reinforcement configuration were used as the initial input values. From Figure 2.3 and Figure 2.4, it is known that the shear is constant along the beams and is equal to V, which is the external applied load. To find the exact shear and moment applied at the critical section, the shear and moment from self-weight of the beams were also added. Refer to ref (1) for further details about the cross-sectional properties of the beams. From the data generated by Response-2000 and the experimental results tabulated in Table 3.1, it is concluded:

- For normal strength concrete, simply supported beams w/o crack control reinforcement; Response-2000 underestimated the shear capacity by 24% (average) for the eight beams studied. However, for the two continuous beams, it overestimated the shear capacity by 11%.
- For the five normal strength concrete, simply supported beams with crack control reinforcement, Response-2000 significantly under-estimated the shear capacity (51%), while for the two continuous beams, it underestimated the shear capacity by 2.7%.
- 3. For high-strength concrete, simply supported beams w/o crack control reinforcement, Response-2000 overestimated the shear capacity by 7.3% for the four beams out of six beams considered while it underestimated the shear strength by 15% for the remaining two beams. Nevertheless, on average, it can reasonably predict the shear capacity for all six beams. Meanwhile, Response-2000 underestimated the shear capacity by 3.9% for the four continuous beams.
- 4. For high strength concrete, simply supported beams with crack control reinforcement, Response-2000 considerably underestimated the shear capacity by 30% average for the three beams studied, while for the four continuous beams the shear capacity is underestimated roughly by 3.1%.

Based on the above explanation and Table 3.1, it is concluded that Response-2000 can accurately predict the shear strength for normal and high strength concrete continuous beams with and w/o crack control reinforcement. However, for the simply supported beams the shear strength predicted by Response-2000 differs from case to case as explained above. Nevertheless, according to NCHRP Web-Only-Document (78), the statistical data for the shear strength of 64 reinforced concrete members proved that Response-2000 gives the best shear strength

predictions for the members. Figure 3.2 is provided to graphically present the above conclusions for the two general categories of beams (simply supported, and continuous).




Figure 3.2 (Vexp/VResp-2000-Depth) Relationship for 34 reinforced concrete sections

The above figure shows the ratio of experimental shear and shear obtained from Response-2000 for all 34 beams considered. As stated earlier, it is observed that the ratio of  $\frac{V_{exp}}{V_{Res2000}}$  is close to 1.0 for continuous beams while the values are considerably higher for simply supported beams. The line drawn at the middle shows the boundary where the experimental shear strength is equal to that obtained from Response-2000. The data points lower than the line show cases where Response-2000 over-estimates the shear capacity at the critical sections, while the values above the line show cases where Response-2000 under-estimate the shear strength of the sections.

# 3.2 Plotting Exact AASHTO LRFD Interaction Diagrams for Combined Shear and Torsion

Shear-torsion interaction diagram for a section provides the ultimate capacity of a section under various combinations of shear and torsion. Depending on the equations used for the combined

shear and torsion response of a section, the interaction diagram could either be linear, a quarter of a circle, an ellipse, or composed of several broken lines. In the following section, the procedure to plot exact shear-torsion interaction diagrams using the corresponding provisions of AASHTO LRFD (2008) is presented.

To determine the nominal torsional capacity of a section (Eq-2.4.4), section 11.5.3.6 of the ACI Code permits to give  $\theta$  values from 30° to 45° while it is always assumed 45° for shear. For the purpose of comparison, the ACI shear-torsion interaction diagrams for  $\theta$  equal to 30° and 45° are also plotted.

## 3.2.1 Exact Shear-Torsion Interaction Diagrams Based on AASHTO LRFD (2008) Provisions

Knowing that the transverse reinforcement required for shear and torsion for a section shall be added together, this fact provides the basic equation to plot T - V interaction diagrams. From Eq's-2.3.5 and 2.4.4, the amount of transverse reinforcement required to resist shear and torsion can be found as

$$\frac{A_t f_{yt}}{s} = \frac{T_n}{2A_0 \cot\theta} + \frac{V_n - V_c}{2d_v \cot\theta} \qquad (Eq - 3.2.1)$$

The nominal shear strength provided by the concrete  $V_c$  can be substituted with  $0.0316\beta\sqrt{f'_c}b_v d_v$  when  $f'_c$  is given in ksi. However  $V_c$  is equal to  $\beta\sqrt{f'_c}b_v d_v$  when the concrete strength is given in MPa. The factor  $\beta$  in Eq-2.3.2 is given in terms of longitudinal strain  $\varepsilon_s$ . Depending on the case, the value for  $\varepsilon_s$  in Eq-2.3.7 shall be modified. Furthermore, assuming the section is subjected to combined shear and torsion, the value for shear in Eq-2.3.7 should also be modified using the equivalent shear given in Eq-2.4.1 and 2.4.2 for solid and box sections respectively. The modified expression for  $\varepsilon_s$  is then substituted into Eq-2.3.2 as a result of which an expression for  $\beta$  would be obtained in terms of V and T. In addition, the modified expression for strain  $\varepsilon_s$  is also substituted into Eq-2.3.6 to determine an expression for  $\theta$ . If the section is subjected to combined shear, torsion, and bending moment; the bending moment could either be written in terms of shear or a fixed value shall be provided. Consequently  $V_c$  and  $\theta$  are substituted into above Eq-3.2.1. Knowing the reinforcement and cross-sectional properties of the section, Eq-3.2.1 would yield an equation containing V and T as the only variables. For a certain range of values for V provided it does not exceed the pure shear capacity of the section, the

corresponding torsion is easily determined using "Excel Goal Seek" function or any other computer program.

To determine the maximum torsion that a section can resist corresponding to the shear values provided, the shear stress in Eq-2.3.9 is set equal to the maximum allowable value of  $0.25f'_c$  and the shear  $V_u$  modified using Eq-2.4.1 or 2.4.2. For a given value of shear, the related value for torsion is then determined by solving Eq-2.3.9.

On the other hand, Eq-2.4.7 is used to determine torsion that causes the longitudinal reinforcement to yield. To solve Eq-2.4.7, the same shear values as in the previous stages are substituted into the equation. Meanwhile the expression given as Eq-2.3.5 for  $V_s$  is also substituted. Note that the equation may further be modified depending on the case considered i.e.,  $A_{ps}$ ,  $f_{ps}$  and  $V_p$  for non-prestressed members and other terms not satisfying for a certain case shall be set to zero. It is extremely important to remember that V shall not be modified because it is already modified in Eq-2.4.7. Finally the equation is solved for T using "Excel Goal Seek" function.

For a particular value of shear, the corresponding minimum value for torsion is selected from the three analyses explained. Note that all resistance factors are assumed as 1.0 because the strength of a section that has already been designed is evaluated. Six T - V interaction diagrams representing 20 beams are included in chapter five of this document.

#### 3.2.2 Exact Shear-Torsion Interaction Diagrams Based on ACI 318-08 Provisions

The procedure to draw T - V interaction diagrams using the corresponding ACI provisions is simple compared to AASHTO LRFD (2008). The main equations used to plot the interaction diagrams are the equations based on the fact that the shear and torsion transverse reinforcement are added together and that the shear stress in concrete should not exceed beyond the maximum allowable limit of  $10\sqrt{f'_c}$ .

$$\frac{A_t f_{yt}}{s} = \frac{T_n}{2A_0 \cot\theta} + \frac{V_n - V_c}{2d} \qquad (Eq - 3.2.2)$$

Having  $V_c = 2\sqrt{f'_c}b_w d$  when the concrete strength is given in psi and  $\theta$  equal to 30° and 45°; the above equation is solved for *T* by providing different values for *V*. Making sure that *V* does not exceed the pure shear capacity of the section.


Eq-2.4.10a or 2.4.10b is solved for T depending on whether the section is solid or hollow to determine the maximum torsion that a section can support corresponding to a certain value of shear. The maximum torsion means that the concrete at section may crush if slightly larger torsion is applied on the section. Note that the resistance factor is set equal to 1.0.


The smaller values for *T* is selected for a particular value of shear and the same process is followed for other points on T - V interaction diagrams. The ACI interaction diagrams both for  $\theta$  equal to 30° and 45° are included in chapter five of this document.


# Chapter 4 - Development of AASHTO Based Shear-Torsion Design Tool (MathCAD)


A MathCAD design tool was developed to design sections subjected to combined shear and torsion using the corresponding AASHTO LRFD provisions. However, sections under shear and torsion where torsion is negligible can also be designed using the developed design tool. The program is developed for kip-in units and the initial input values shall be entered in the highlighted yellow fields. In addition, the address of each equation used is also provided in the AASHTO LRFD (2008) code. This may help to locate the equation in the code.


Brief description where ever needed has been provided in the program to help understand different variables used. It is essential to enter the required initial input with proper units as written in the program. Below is the flow chart for the MathCAD design tool to show how the program functions. Furthermore, an example solved using the developed file has been added in Appendix-C.




















## **Chapter 5 - Results and Discussion**

## 5.1 Analysis for Shear Only:

In Figure 5.1 the predicted shear strength at different sections along the span for BM100 using AASHTO LRFD general procedure, simplified AASHTO procedure for prestressed and non-prestressed concrete members, ACI 318-08, and Response-2000 are plotted. For ACI 318-08, the nominal shear strength provided by concrete was calculated both using ACI Eq (11-3) and ACI Eq (11-5). Knowing that Response-2000 underestimated the shear strength by 24% for normal strength concrete simply supported beams without crack control reinforcement, it can be concluded that the results obtained using the general AASHTO procedure are reasonably accurate.




Figure 5.1 Predicted shear strength along the length of BM100, normal strength, non-prestressed simply supported reinforced concrete beam

On the other hand, both simplified AASHTO and ACI 318-08 seem to slightly overestimate the shear capacity. As shown in the figure, both ACI Eq (11-3) and (11-5) used to predict  $V_c$  led to almost the same overall shear capacity of sections. However, using ACI Eq (11-3) the shear strength at different sections along the beam is constant because the beam is prismatic and has the same spacing 16 in. (406 mm) for transverse reinforcement throughout the span while the shear strength using ACI Eq (11-5) follows decreasing trend because of the increasing moment towards center of the beam. Note that ACI Eq (11-3) and (11-5) are numbered here as Eq-2.3.15 and 2.3.16.

The shear strength for the general AASHTO procedure and Response-2000 varies along the beam span because of the varying longitudinal strain  $\varepsilon_x$  which is one-half of the strain in non-prestressed longitudinal tension reinforcement given in Eq-2.3.7.




Figure 5.2 Predicted shear strength along the length of SE100A-M-69, high strength continuous non-prestressed reinforced concrete beam

The above figure shows the shear strength predictions for SE100A-M-69. From the previous evaluation of Response-2000, it was obtained that Response-2000 underestimates the

shear strength by 3.9% (average) for high strength concrete continuous beams without crack control reinforcement. In the above figure, it is seen that the shear strength predictions using the general AASHTO procedure closely follow Respnse-2000 predictions for most of the sections along the span. Note that Response-2000 highly underestimates the shear strength for sections subjected to large moment and relatively less longitudinal reinforcement. Such locations happen to be at 1m and 8 m from the left. Accordingly, Response-2000 highly overestimates the shear strength for locations with approximately zero moment and enough longitudinal reinforcement. An example for such location would be a section at 9 m from left along the beam (Figure 2.4). As shown in the figure, the simplified AASHTO and ACI 318-08 where  $V_c$  is calculated using ACI Eq (11-3) give conservative results while ACI Eq (11-5) is better in this regard. Overall, the general AASHTO procedure gives convincing results for this case. Meanwhile, the shear strength is influenced by the variations in moment and longitudinal tensile reinforcement both for simplified AASHTO and a case where  $V_c$  is calculated using ACI Eq (11-5).

Figure 5.3 shows the shear strength predictions using the aforementioned procedures for continuous prestressed high strength concrete girder (BT-72). The beam as depicted in Figure 2.6 has a span of 120 ft (36.6 m) and a total number of 44, half-inch (12.7 mm) diameter, seven wire, 270 ksi (1861 MPa) low relaxation prestress strands. The beam had a combination of draped and straight strands such that twelve of the strands were draped and the remaining 32 were straight. Noting the fact that Response-2000 was not validated for prestressed concrete beams, the shear strength results for all the methods are reasonably close to each other. In contrast to the previous cases, the shear strength for the entire methods follow decreasing trend as it goes far from the support. This is due to the fact that the detailed ACI Eq's. (11-10) and (11-12) takes into account the bending moment effects present at the section.




Figure 5.3 Predicted shear strength for Bulb-T (BT-72), high strength continuous pre-stressed concrete member

In Figure 5.4 the results for (8DT18) simply supported double-T prestressed beam with harped strands are plotted. The beam did not have any transverse reinforcement and the whole nominal shear strength for the section was provided by the concrete and the P/S effects. In other words, the results plotted show the nominal shear strength provided by the concrete  $V_c$ . As stated earlier, Response-2000 gives higher shear strength at section 1.5 ft (458 mm) from the support because of small bending moment and underestimates the shear strength at 16 ft (4.88 m) from the support where the moment is almost reaching its peak value. For cases other than this, both ACI 318-08 and simplified AASHTO give consistent results, however the general AASHTO procedure highly overestimates the shear strength or  $V_c$  in this case. To verify which method gives reliable results, more experimental work has to be done.




Figure 5.4 Predicted shear strength along the length of Double-T (8DT18), normal strength simply supported pre-stressed reinforced concrete beam

The results for BM100D are plotted in Figure 5.5. From the previous knowledge about Response-2000, it was found that Response-2000 underestimated the shear strength by 51% (average) for normal strength concrete simply supported beams with crack control reinforcement. As shown in the figure, the simplified AASHTO procedure highly underestimates the shear strength while the general AASHTO procedure gives reasonable results. The results for ACI are almost exactly the same as for BM100 (without crack control reinforcement). The only difference is that the predicted shear strength by the general AASHTO procedure increases and makes ACI results relatively accurate for BM100D.




Figure 5.5 Predicted shear strength along the length of BM100-D, normal strength simply supported non-prestressed reinforced concrete beam with longitudinal crack control reinforcement

Figure 5.6 presents results for SE100B-M-69. Both Response-2000 and the general AASHTO procedure give very close results except for the critical locations as mentioned earlier. This is in total conformance with the results showing 3.1% (average) difference obtained from qualifying Response-2000 against experimental results tabulated in Table 3.1. The shear strength predicted using the general AASHTO procedure and Response-2000 show considerable increase, while it remains unchanged for ACI and simplified AASHTO. In other words, ACI and simplified AASHTO fail to encounter the effect of crack control reinforcement on the nominal shear strength of a section.




Figure 5.6 Predicted shear strength along the length of SE100B-M-69, high strength continuous non-prestressed reinforced concrete member with longitudinal crack control reinforcement

## 5.2 Analysis for Shear and Torsion

Figure 5.7 shows the T-V interaction diagrams for AASHTO LRFD (2008) and ACI Code. Details of the reinforcement for these beams tested by (Klus 1968) are tabulated in Table 2.2 and Table 2.3. Having the related properties of the section, the torsion obtained from Eq-3.2.1 controlled. This means that the section will neither fail due to yielding of the longitudinal tension reinforcement nor the concrete crushing. For the pure shear case, the predicted shear capacity is the same for ACI when  $\theta$  is equal to 45° and 30°. This is due to the fact that the angle  $\theta$  in Eq-3b is only used in the term that includes torsion which in turn equals zero for the pure shear case. The equation for nominal shear capacity provided by shear reinforcement,  $V_s$ , of a section is independent of  $\theta$  for ACI. The value for  $\theta$  is inherently assumed as 45°.




Figure 5.7 Shear-torsion interaction diagrams along with experimental data for specimens tested by Klus (1968)

The flat plateau at the top of the graphs is due to the fact that the applied shear force is less than the nominal shear strength provided by concrete,  $V_c$ . Hence, the total transverse reinforcement is used to resist the applied torsion. In other words, the applied shear does not alleviate from the full nominal torsional capacity of the section. This is because of the fact that for  $V < V_c$ , the applied shear V is resisted by the concrete and not the shear reinforcement. This situation will continue until the applied shear, V, is greater than  $V_c$ .

In Figure 5.8, the AASHTO LRFD shear-torsion interaction curve for (RC2 series) is flat approximately up to a shear force of 269 kN; while for the curve based on the ACI it is horizontal up to a shear force of 222 kN. This is due to the fact that the value of  $V_c$  for AASHTO LRFD is calculated to be 279 kN while it is equal to 218 kN for ACI. After the section is subjected to greater shear force and torsion, the curve follows a decreasing trend as shown in the figure.




Figure 5.8 Shear-torsion interaction diagrams for RC2 series

From Figure 5.7 and Figure 5.8, it is evident that the experimental data is perfectly matching the AASHTO LRFD curve. On the other hand, the corresponding ACI curves for 30° and 45° are consistent in both figures. In a sense the ACI provisions for combined shear and torsion are very conservative and uneconomical when  $\theta$  is equal to 45°. However, these provisions seem to be slightly un-conservative when  $\theta$  is equal to 30° and the shear force is less than  $V_c$ .




Figure 5.9 Shear-torsion interaction diagrams for High-Strength over-reinforced specimens HO-1, and HO-2

The figure shown above shows the T-V interaction diagram for HO-1 and HO-2 specimens based on AASHTO LRFD and ACI 318-08. As stated earlier, the AASHTO LRFD provisions closely approximate the torsion-shear strength of HO-1 and HO-2 sections. The ACI procedure overestimates the shear-torsion strength for  $\theta$  equal to 30° up to a shear value as great as 250 kN.




Figure 5.10 Shear-torsion interaction diagram for NO-1 and NO-2

As shown in Figure 5.10, again the AASHTO LRFD provisions closely approximate the combined shear and torsion capacity for NO-1 and NO-2 specimens. However, when the combined shear force and torsion reaches 400 kN and 7 kN.m respectively, the equation produced from substituting the shear stress  $v_u$  with  $0.25f'_c$  in Eq-2.3.9 and substituting  $V_u$  with  $V_{u-eq}$  yields negative number under the square root. This means that the concrete crushes and no torsion would be obtained from the corresponding equation for applied shear force greater than 400 kN. To obtain the pure shear capacity of the section, T was set equal to zero and the pure shear capacity of the section was found to be  $0.25f'_c b_v d_v$ . The estimated capacity of the specimens where the equation yields negative number under the square root is shown as dotted line on the AASHTO LRFD curve.




Figure 5.11 Shear-torsion Interaction diagram for High-Strength box section HU-3

In the above figure, the predicted shear-torsion capacity for the box section HU-3 subjected only to combined shear force and torsion is shown. According to ref (13) the section is slightly underreinforced. Using the ACI provisions, the torsion is controlled by Eq-2.4.10b when the angle  $\theta$  is equal to 30°. This imply that the concrete crushes if shear-torsion greater than that shown in Figure 5.11 are applied on the section. However, the torsion is controlled by Eq-3.2.2 when  $\theta$  is equal to 45° and the shear force is lower than 22 kN. For shear force greater than 22 kN, the maximum torsion that the section can resist is controlled by Eq-2.4.10b. This simply means that the concrete may crush before the reinforcement yields if a larger torsion is applied. Since Eq-2.4.10b is independent of the angle $\theta$ , both curves for ACI (30° and 45°) give exact similar results after the curve for  $\theta$  equal to 45° bifurcates. The experimental result for pure torsion is exactly the same as predicted by ACI when  $\theta$  is 30°. The results for NU-3 which is not included here were also consistent with that shown in Figure 5.11. The only difference was that the experimental pure torsion strength was slightly greater compared to the strength predicted by ACI using 30,




Figure 5.12 Shear-torsion interaction diagram for NU-2

From the above figure, it is obvious that the ACI provisions for  $\theta$  equal to 30° are extremely unconservative for NU-2 which is an under-reinforced specimen made of normal strength concrete. The AASHTO LRFD curve seems to be conservative for most of the cases studied. However, when the shear and torsion reaches 111 kN and 3.85 kN.m respectively; the longitudinal reinforcement starts yielding. As a value for shear force greater than 111 kN is substituted in Eq-2.4.7 knowing that  $V_{p,N_u}$ ,  $A_{ps}$ , and  $M_u$  are zero, a negative number under the square root is produced and the equation remains unsolved. To determine the pure shear capacity of the section,  $T_n$  in Eq-2.4.7 was set equal to zero and the equation was solved for  $V_n$ . The portion of the curve where the reinforcement yields is shown by hidden lines in Figure 5.12. The same responses were observed for NU-1, HU-1, and HU-2 where ACI Code for  $\theta$  equal to 30° gave extremely un-conservative results.

## **Chapter 6 - Conclusions and Recommendations**

#### Summary:

In this study, shear and combined shear and torsion provisions for the general AASHTO LRFD procedure, simplified AASHTO LRFD procedure for prestressed and non-prestressed concrete members, and ACI 318-08 were comparatively studied. The results from the aforementioned procedures were compared with those obtained from Modified Compressions Field Theory (MCFT) using Response-2000. Note that the AASHTO LRFD provisions for shear and combined shear and torsion are based on simplified MCFT. In addition, exact shear-torsion interaction curves were drawn for the three methods for sections subjected to combined shear and torsion.

#### **6.1 Conclusions:**

#### 6.1.1 Members Subjected to Shear Only

The general AASHTO procedure proved to behave more realistically and in some cases economically. This was in particularly true for transversely reinforced simply supported and continuous beams with crack control reinforcement, while ACI 318-08 and simplified AASHTO were inaccurate in this regard. In addition, ACI 318-08 Eq (11-5) used to predict  $V_c$  has led to convincing results compared to ACI Eq (11-3). This was due to the fact that ACI Eq (11-5) takes into account the existing bending moment effects at section.

The simplified AASHTO procedure for prestressed and non-prestressed concrete members almost underestimated the shear strength for all of the beams considered in particularly for SE100A-M-69, SE100B-M-69, and BM100D.

The analytical program used in this study (Response-2000) which is based on Modified Compression Field Theory (MCFT) highly overestimated the moment effects on the overall nominal shear strength,  $V_n$ , of a section. This has caused  $V_n$  to be highly overestimated at sections with small bending moment and significantly underestimated at sections with large moment.

To analyze the shear strength of a concrete beam, it is extremely important to know that a shear-critical section may not be limited to locations where the section is subjected to maximum

shear; rather a section with less flexural reinforcement and relatively smaller shear could fail in shear. Because the higher the longitudinal strain,  $\varepsilon_x$ , the lesser the overall nominal shear capacity of the section. However, ACI 318-08 doesn't take this phenomenon into account.

The reason why Response-2000 and the general AASHTO procedure do not match well is because Response-2000 is based on MCFT while the general AASHTO procedure for shear is based on simplified MCFT. Furthermore, the limitations imposed by the AASHTO in regards to the effective depth, d, and  $M_u$  also has their rule to play.

#### 6.1.2 Members Subjected to Combined Shear and Torsion

A research program was conducted to explore the accuracy and validity of the AASHTO LRFD 2008 provisions for combined shear and torsion design, validating against 30 experimental data from different sections. These sections covered a wide range of specimens from over-reinforced to under-reinforced and made from normal tor high strength concrete. Solid or hollow sections were among the specimens for which the experimental data was used for comparison.AASHTO LRFD (2008) provisions were also compared to the ACI 318-08 provisions for combined shear and torsion design. AASHTO LRFD 2008 provisions consistently were more accurate and the predictions, while conservative in majority of the cases, were much closer to the experimental data for close to all of the specimens. This included over-reinforced and under-reinforced sections made of high strength and normal strength concrete.

During this study it was found that the AASHTO LRFD (2008) provisions to analyze a section under combined shear and torsion may not be able to predict the complete T-V interaction curve for cases leading to negative terms under the square root in the derivation process. This particularly happens for over-reinforced or under-reinforced sections made of high strength or normal strength concrete. The analytical reason is the limitation dictated by the AASHTO LRFD Equation 5.8.3.6.3-1 related to the amount of longitudinal steel and equations 5.8.3.3-2 and 5.8.2.1-6 or 5.8.2.1-7 related to the maximum sustainable shear stress by concrete which implicitly affects the level of the combined shear and torsion. However, it should be noted that the maximum shear stress limit of 0.25f°c dictated by the AASHRO LRFD 2008, was accurate in prediction of the behavior of sections experiencing relatively high levels of shear stress. This was especially true for over-reinforced sections.

On the other hand, the results by the ACI are frequently un-conservative when the angle  $\theta$  is equal to 30 degrees. This is especially true for the under-reinforced sections. However, when the angle  $\theta$  is considered to be 45 degrees, the results are conservative for close to all of the specimens. An important point for the ACI code is that the angle  $\theta$  is always considered as 45 degrees for shear even if the angle for torsion is used as 30 degrees. This is a discrepancy in the ACI code, while AASHTO is consistent from this perspective.

Compared to the ACI code, AASHTO LRFD 2008 provides a more detailed process to assess the shear/torsion capacity of a section. As a result, the capacities evaluated by the AASHTO LRFD 2008 were found to be closer to the experimental data, compared to those predicted by the ACI code. It should be noted that the strain compatibility is not directly considered in the ACI code, while it plays a critical role in derivation of the AASHTO LRFD 2008 design equations. This in turn has added more value to the AASHTO process in accurate assessment of the shear-torisonal capacity of a section.

# 6.2 Recommendations and possible modifications to AASHTO LRFD Bridge Design Specifications (2008)

The AASTHO LRFD Bridge Design Specifications needs to address the following items:

- The AASHTO LRFD is not clear where to substitute V<sub>u</sub> with V<sub>u-eq</sub> for section subjected to combined shear and torsion. C.5.8.2.1 on Page 5-61 of the AASHTO LRFD (2008) states "V<sub>u</sub> in Eqs. 5.8.3.4.2-1, 5.8.3.4.2.-2, and 5.8.3.4.2-3 for ε<sub>s</sub>, and in Eq 5.8.2.9-1 for v<sub>u</sub>, are not modified for torsion. In other words, the values used to select β, θ in Tables 5.8.3.4.2-1 and 5.8.3.4.2-2 have not been modified for torsion." This could be inferred either to modify V<sub>u</sub> for the applied torsion or simply use V<sub>u</sub> without any modification to it. However, section 5.8.3.6.2 on page 5-84 of the AASHTO LRFD Bridge Design Specifications (2008) defines θ as angle of crack with the modifications for v and V<sub>u</sub>.
- The strain  $\varepsilon_s$  in the longitudinal tensile reinforcement can be determined using Eq. 5.8.3.4.2-4 of the AASHTO LRFD (2008) or Eq-2.3.7 of this document. In the code, it is not explicitly stated whether the whole longitudinal reinforcement  $A_s$  should be used for sections subjected

to pure torsion or only the positive longitudinal reinforcement as defined on page 5-73 of the code shall be used in the corresponding equations for  $\varepsilon_s$ .

- AASHTO LRFD (2008) proposes Eq.5.8.3.6.3-1 to check the longitudinal reinforcement for solid sections subjected to combined shear and torsion. The resistance factor  $\phi$  used in this equation is the same for axial load, shear force, and moment. However, the resistance factor varies for axial load, shear force, and moment in Eq. 5.8.3.5-1 which is used to check the longitudinal reinforcement for solid sections subjected to shear not torsion.
- Also the resistance factor in the denominator of Eq. 5.8.2.9-1 shall be removed.
- To check the AASHTO LRFD (2008) provisions for sections subjected shear or combined shear and torsion, a wide range of beams such as pre-stressed or non-prestressed overreinforced, moderately reinforced, and under-reinforced concrete sections made of highstrength or normal strength concrete shall be tested. To get even more realistic results, it is highly recommended that the test specimens shall be designed using the applicable provisions of the AASHTO LRFD (2008).

#### **6.3 Suggestions for Future Research**

More experimental work is needed to investigate the behavior of normal strength and high strength, prestressed shear-critical simply supported and continuous concrete beams designed based on the AASHTO LRFD general and simplified procedures.

In addition, the simplified AASHTO provisions for shear have to be modified to accurately take into account the effects of crack-control reinforcement on the overall nominal shear strength of a section.

As stated earlier, in this study only exact shear-torsion interaction curves were drawn neglecting the effects of bending moment. However, in most close to all of the real world situations, the effects of bending moment exist, hence shear-bending moment- torsion (V - M - T) exact interaction curves are required to be developed for design.

#### References


- Collins, M. P. and Kuchma, D. (1999). How Safe Are Our Large, Lightly Reinforced Concrete Beams, Slabs, and Footings? : ACI Structural Journal, Vol. 96, No. 4, p. 482-490.
- Bentz, C. E., Vecchio, J. F. and Collins, P. M. (2006). Simplified Modified Compression Field Theory for Calculating Shear Strength of Reinforced Concrete Elements: ACI Structural Journal, Vol.103, No.4, p. 614-624.
- Collins, M. P., Mitchell, D., Adebar, P. and Vecchio, J. F. (1996). A General Shear Design Method: ACI Structural Journal, Vol. 93, No.1, p. 36-45.
- Collins, M. P. (1978). Towards A Rational Theory For RC Members In Shear: *proceeding*, ASCE, Vol. 104, No. ST4, p. 649-666.
- Vecchio, J. F. and Collins, P. M. (1986). The Modified Compression-Field Theory for Reinforced Concrete Elements Subjected to Shear: ACI Journal, proceedings, Vol. 83, No. 2, p. 219-231.
- AASHTO LRFD, Bridge Design Specification and Commentary: Interim 2008, Washington, D.C. (2008). p. 5.59-5.84.
- Bentz, E. C. and Collins, M. P. Response 2000: <u>http://www.ecf.utoronto.ca/~bentz/r2k.htm</u> (2000)
- Shioya, T., Iguro, M., Nojiri, Y., Akiyama, H. and Okada, T. (1989). Shear Strength of Large Reinforced Concrete Beams, Fracture Mechanics: Application to Concrete: Fracture Mechanics: Application to Concrete, SP-118, V. C. Li and Z. P. Bezant, eds., American Concrete Institute, Farmington Hills, Mich., p. 259-280.
- Adebar, P. and Collins, M. P. (1996). Shear Strength of Members Without Transverse Reinforcement: Canadian Journal of Civil Engineering, Vol. 23, No. 1, p. 30-41.
- Transportation Research Board of The National Academies. Simplified Shear Design of Structural Concrete Members, NCHRP Web-Only-Document 78: Washington, D.C. (2005). p. D-7.
- Transportation Research Board of the National Academies. Simplified Shear Design of Structural Concrete Members, NCHRP Report-549: Washington, D.C. (2005). p. 47.
- Klus, P. J. (1968). Ultimate Strength of Reinforced Concrete Beams in Combined Torsion and shear: ACI Journal, Title No. 65-17, March 1968, p. 210-215.

- Fouad, E., Ghoneim, M., Issa, M., and Shaheen, H. (2000). Combined Shear and Torsion in Reinforced Normal and High-Strength Concrete Beams (I), Experimental Study: Journal of Engineering and Applied Science, Vol. 47, No. 6, p. 1059-1078.
- Rahal, N. K., and Collins, P. M. (2003). Experimental Evaluation of ACI and AASHTO-LRFD Design Provisions for Combined Shear and Torsion: ACI Structural Journal, Vol. 100, No. 3, p. 277-282.
- Badawy, I. E. H., McMullen, E. A., and Jordan, J. I. (1977). Experimental investigation of the collapse of reinforced concrete curved beams: Magazine of Concrete Research, Vol. 29, No. 99, p. 59-69, June 1977.
- Rahal, N. K., and Collins, P. M. (1995). Effect of Thickness of Concrete Cover on Shear-Torsion Interaction – An Experimental Investigation: ACI Structural Journal, Vol. 92, No. 3, p. 334-342, May-June 1995.
- Ewida, A. A., McMullen, E. A. (1982). Concrete Members Under Combined Torsion and Shear: Journal of the Structural Division, Proceedings of the American Society of Civil Engineers, Vol. 108, No. ST4, p. 911-928.
- Rahal, N. K. (2006). Evaluation of AASHTO-LRFD General Procedure for Torsion and Combined Loading: ACI Structural Journal, Vol. 103, No. 5, p. 683-692.
- American Concrete Institute Code Requirements for Structural Concrete (ACI 318-08), and Commentary: An ACI Standard, Reported by ACI Committee 318, Farmingtol Hills, MI 48331.
- Wight, K. J., and MacGregor, G. J. (2009). Reinforced Concrete, 5<sup>th</sup> Edition: *Pearson Prentice Hall*, p. 233-286, 301-351.
- Nilson, H. A., Darwin, D., and Dolan, W. C. (2004). Design of Concrete Structures: *McGraw-Hill*, p. 115-160.

# Appendix A - AASHTO LRFD Simplified Procedure for Shear of Pre-Stressed and Non-Prestressed Members

### Example -1:

Determine the shear strength of the middle girder at 7.1 ft from the left support or/ first interior support from the left shown in Figure 2.4Error! Reference source not found., using the simplified AASHTO LRFD method for pre-stressed and non-prestressed members, AASHTO LRFD general procedure, and ACI 318-08. The girder is simply supported while the deck on the top of it is continuous. This girder has a combination of draped (harped) and straight pre-stressing strands. This example is based on example 9.6 of the PCI Bridge Design Manual.






Figure A. 1 profile and section of the bridge girder (BT-72)

 ε<sub>x</sub> is calculated at the section and all reinforcement should be on the tension side at that particular section.
 2).d<sub>p</sub> ?

3).fpe for composite section where the moment is negative equals zero.
4).for calculating Mcr in negative moment region, f'c for topping should be considered.<u>Also more importantly, if the applied moment is positive, substitute the correct values for "y or c" in flexure formula</u>.

5). The eccentricity, **e**, used to calculate fpc is the distance between the centroid of P/S and centroid of NON-composite section.

### Legend:

**Input Values** 

Final Answers for important parameters Not used in this or/other files

	Concrete Properties		* <i>Note</i> : In case the topping and girder both
fc', <sub>girder</sub>	7	ksi	have the same f'c, make sure that you enter
fc', <sub>deck/topping</sub>	4	ksi	$f'c_{, deck, topping}$ equal to that of $f'c_{, girder}$
n(modular ratio)	0.756		
γ <sub>concrete</sub>	0.15	kcf	
E <sub>c, slab, topping</sub>	3834.253513	ksi	
E <sub>c, beam</sub>	5072.240629	ksi	
	Prestressing Strands		
A <sub>ps</sub>	0.153	in <sup>2</sup>	(0.5 in. dia., seven-wire, low-relaxation)
f <sub>pu</sub>	270	ksi	
f <sub>py</sub>	243	ksi	
f <sub>po</sub>	189	ksi	(f <sub>po</sub> = A parameter for P/S)
f <sub>se</sub>	152.9	ksi	(f <sub>se</sub> = Effective prestress after all loses)
Ep	28500	ksi	
	Reinforcing Bars		
As	15.53	in <sup>2</sup>	
f <sub>y</sub>	60	ksi	
E	29500	ksi	

Over All Geometry and Sectional Properties:	•	-
Non-Composite Section		
Span Length, <b>L</b>	120	ft
Over All Depth of Girder, <b>h</b>	72	in.
Width of Web, b <sub>v</sub>		in.
Area of Cross-Section of Girder, <b>A</b> g	767	
Moment of Inertia, I <sub>g</sub>	545894	in <sup>4</sup>
Dis. From centroid to ext. bottom fiber, $oldsymbol{y}_{oldsymbol{b}}$	36.6	in.
Dis. From centroid to ext. top fiber, $oldsymbol{y}_{t}$	35.4	in.
Sec.modulus, ext.bottom fiber, <b>S</b> <sub>b</sub>	14915	
Sec.modulus, ext.top fiber, <b>S</b> <sub>t</sub>	15421	in <sup>3</sup>
Weigh of Beam	0.799	k/ft
Composite Section		
Over all depth of the composite section, <b>h</b> <sub>c</sub>	80	in.
Slab thickness, <b>t</b> s		in.
Total Area (transformed)of composite sect., <b>A</b> c	1412	in²
Moment of Inertia of the composite sec. I <sub>c</sub>	1097252	in <sup>4</sup>
Dis. From centroid of composite section to extreme bottom fiber, $\mathbf{y}_{bc}$	54.67	in.
Dis. From centroid of composite section to extreme <u>top fiber of beam</u> , <b>y<sub>tg</sub></b>	17.33	in.
Dis. From centroid of composite section to extreme <u>top fiber of slab</u> , $\mathbf{y}_{tc}$	25.33	in.
Composite section modulus for the extreme <u>bottom fiber of beam</u> , <b>S<sub>bc</sub></b>	20070.45912	in <sup>3</sup>
Composite section modulus for the extreme top fiber of beam, <b>S</b> <sub>tg</sub>	63315.176	in <sup>3</sup>
Composite section modulus for the extreme top fiber of slab, $S_{tc} = 1/n^*(I_c/y_{tc})$ Critical in case n=0	57304.69636	in <sup>3</sup>
Total # of P/S strands	44	
Area of P/S tension reinforcement	6.732	in <sup>2</sup>





Figure A. 2 Cross-section (BT-72)



\*Note: If modulus of Elasticity for topping, slab, is different than modulus of elasticity for girder, determin **n=E<sub>c,slab</sub>/E<sub>c,beam</sub>** called modular ratio and multiply it by the area of slab( b<sub>eff</sub> x slab thickness). Add the given value to Area of Girder for total area of composite section.

Figure A. 3 Composite Section(BT-72)

Sectional Forces at Design Section				
Axial Load				
N <sub>u</sub>	0	kips		
Shear Forces (D.L, L.L)				
Unfactored shear force due to beam weight, V <sub>d,girder</sub>	42.3	kips		
Unfactored shear force due to deck slab, V <sub>d, slab</sub>	64.6	kips		
Unfactored shear force due to barrier weight, <b>V</b> <sub>d,barrier</sub>	7.8	kips		
Unfact. shear force due to future wearing surface, $V_{d,wearing}$	14.2	kips		
Unfactored shear force due to <b>TOTAL</b> D.L, V <sub>d</sub>	128.9	kips		
Unfactored shear forces due to live load, $V_{LL}$	137.3	kips		
FACTORED SHEAR FORCE, <b>V</b> <sub>u</sub>	404.95	kips		
Moments (D.L,L.L)				
Unfactored moment due to beam weight, <b>M<sub>d,girder</sub></b>	272.7	kips-ft		
Unfactored moment due to deck slab, <b>M<sub>d, slab</sub></b>	417.1	kips-ft		
Unfactored moment due barrier, <b>M<sub>d,barrier</sub></b>	-139.6	kips-ft		
Unfact. moment due to future wearing surface, <b>M<sub>d, wearing</sub></b>	-244.4	kips-ft		
Unfactored moment due to <b>TOTAL</b> D.L, <b>M</b> <sub>d</sub>	305.8	kips-ft		
Unfactored moment due to live load, <b>M</b> <sub>LL</sub>	-1717.8	kips-ft		
FACTORED MOMENT, <b>M</b> <sub>u</sub>	-2877.57	kips-ft		

*Note: The factored shear and moment is calculated using the following combinations:
$V_{u}=0.9(V_{d,girder}+V_{d,slab}+V_{d,bearing})+1.50(V_{d,wearing})+1.75(V_{LL})$
$V_{u}=1.25(V_{d,girder}+V_{d,slab}+V_{d,bearing})+1.50(V_{d,wearing})+1.75(V_{LL})$
Select the MAX shear from above
$M_{u}=0.9(M_{d,girder}+M_{d,slab}+M_{d,bearing})+1.50(M_{d,wearing})+1.75(M_{LL})$
$M_{u}=1.25(M_{d,girder}+M_{d,slab}+M_{d,bearing})+1.50(M_{d,wearing})+1.75(M_{LL})$
Select the MAX moment from above
It is conservative to select the Max moment rather than the moment corresponding to Max shear (check the formula for $M_{\rm eff}$ for all value)
corresponding to Max shear. (check the formula for $M_u$ for abs.value)

# **SOLUTION:**

Calculation of Effective Depth, d <sub>v</sub> :				
d <sub>e</sub>	76.25	in.		
a (depth of compression)	6.02	in.		
d <sub>v</sub> =d <sub>e</sub> -a/2	73.24	in.		
$d_v=0.9d_e$	68.625	in.		
d <sub>v</sub> =0.72h	57.6	in.		
Max d <sub>v</sub> (controls )	73.24	in.		

\*d<sub>e</sub>=Effective depth from extreme compression fiber to the centroid of the tensile force in the tensile reinforcement

\**Note*: the value of "a"depends on location of cross-section.

**a=(A<sub>s</sub> or A<sub>ps</sub>)\*f<sub>y</sub>/(0.85\*f'c\*b)** because in this particular case it is intended to determine "a" at critical section 7.1 ft from support for continuous beam, only non-prestrestressed reinforcement at the deck is considered in the calculation.

a).Evaluation of Web-Shear Cracki	ing Strength:		
V <sub>cw</sub> =	V <sub>cw</sub> =(0.06*√f'c+0.3f <sub>pc</sub> )b <sub>v</sub> d <sub>v</sub> +V <sub>p</sub>		
$f_{pc}=P_{se}/A_g-P_{se}*e*(\gamma_{bc}-\gamma_b)/I_g+(M_{dg}+M_{ds})*(\gamma_{bc}-\gamma_b)/I_g$			
p <sub>se</sub> =# of Strands*A <sub>strand</sub> *f <sub>se</sub>			
V <sub>p</sub>	35.2	kips	
e(eccentricity)	18.79	in.	
P <sub>se</sub>	1029.3228	kips	
fpc	0.975795333	ksi	
V <sub>cw</sub>	233.5999877	kips	

b).Evaluation of Flexure-Shear Cra	<u> </u>		
V <sub>ci</sub> =0.02*√f'c l	o <sub>v</sub> d <sub>v</sub> +V <sub>d</sub> +V <sub>i</sub> M <sub>cr</sub>	/M <sub>max</sub> >=0.06√f'c	b <sub>v</sub> d <sub>v</sub>
	V <sub>i</sub> =V <sub>u</sub> -V	/ <sub>d</sub>	
	M <sub>max</sub> =M <sub>u</sub>	-M <sub>d</sub>	
M <sub>cr</sub> =(I <sub>c</sub> /y <sub>tc</sub> )*(0.2*√f'c+f <sub>pe</sub> -f <sub>d</sub> ) where	<u><b>f'c</b></u> for section v	with neg.moment is a	that for topping.
	f <sub>d</sub> =M <sub>dw</sub> y <sub>t</sub>	<sub>c</sub> /I <sub>c</sub>	
V <sub>i</sub>	276.05	kips	*Make sure
M <sub>max</sub>	-3183.37	kips-ft	that you put right f'c, y <sub>tc</sub> and
$\mathbf{f}_{pe} = \mathbf{A}_{ps} * \mathbf{No.P} / \mathbf{S}^* \mathbf{f}_{se} / \mathbf{A}_g + \mathbf{A}_{ps} * \mathbf{No.P} / \mathbf{S}^* \mathbf{f}_{se} * \mathbf{e}^* \mathbf{c} / \mathbf{I}_g$	0	ksi	f <sub>pe</sub> while
f <sub>d</sub> , put the right <b>y</b> <sub>tc</sub>	0.084712507	ksi	calculating Mcr
M <sub>cr</sub>	1138.142624	kips-ft	
V <sub>ci</sub>	250.8484721	kips	

c).Evaluation of Co	oncrete Contribution:
	V <sub>c</sub> = <b>Min</b> (V <sub>ci</sub> ,V <sub>cw</sub> )
Vc	233.5999877 kips

Explanation for Parts, "a" and "b":

 $f_{pc}$  = compressive stress in concrete (after allowance for all pretension losses) at centroid of cross-section resisiting externally applied loads.  $f_{pc}$  = compressive stress in concrete after all prestress losses have occurred either at the centroid of the crosssection resisting live load or at the junction of the web and flange when the centroid lies in the flange. In a <u>composite section</u>,  $f_{pc}$  is the resultant compressive stress at the centroid of the composite section, or at the junction of the web and flange when the centroid lies within the flange, due to both prestress and to the bending moments resisted by the precast member acting alone.

\* $V_p$  = vertical component of effective pretension force at section.(*strands which are not straight or draped or harped*)

\*e= eccentricity of P/S strands from the <u>centroid of the non-composite section</u> of crosssection.

\*I<sub>g</sub> = moment of inertia of <u>non-composite</u> section.

\*f<sub>pe</sub> = compressive stress in concrete due to effective pretension forces ONLY (after allowance for all pretension losses) at extreme fiber of section where tensile stress is caused by externally applied loads. In this particular case, where the beam at this section is under net negative moment, hence the top portion of deck slab is in tension where prestressing doesn't affect because P/S is limited to non-composite section. fpe=0 (Always satisfy for composite section under negative moment). When calculating fpe using flexure formula, consider Ic or comp.moment of inertia.

\* $f_d$  was calculated using  $f_d$ =M<sub>dw</sub>y<sub>tc</sub>/I<sub>c</sub>. Because this section is under net negative moment Mdw was evaluated conservatively by considering the DL negative moment as that resulting from the DL acting on a continuous span. \*V<sub>ci</sub>>0.06√f'cb<sub>v</sub>d<sub>v</sub>

d).Evaluation of Required Transve	erse Reinforce	ment:	
V <sub>s</sub> =A <sub>v</sub>	*f <sub>y</sub> *d <sub>v</sub> *cotθ/s		
CHECK:	Transverse	Reinforcement Required	
cot0	1		
Vs <sub>(Req'd)</sub>	216.34	-	
A <sub>v,min</sub> /S	0.0084		
A <sub>v</sub> /s <sub>(Req'd)</sub>	0.049231853	in²/in.	
Assume:			
S	12	in. c/c	ОК
Area (#5 stirrups)	0.306796158	in <sup>2</sup>	ОК
A <sub>v</sub> /s (Provided)	0.051132693	in <sup>2</sup>	
V <sub>s</sub> (Provided)	224.6975058	kips	
* <i>Note</i> : the assumed spacing and valid for CSA approach also. e).Checks:	selected bars a	are	
Maximum Spacing Limi			
v <sub>u</sub> /f'c	0.134828888		
S <sub>max</sub>	12	in. c/c	
Minimum Reinf A <sub>v,min</sub> ≥0	<mark>orcement Req</mark> ).0316√f'cb <sub>v</sub> S/1		
A <sub>v,min</sub>	0.10032689		
Maximum Nor V <sub>n</sub> ≤0	ninal Shear Re 0.25f'cb <sub>v</sub> d <sub>v</sub> +V <sub>p</sub>	sistance	
	OK		

### AASHTO LRFD General Procedure (Modified Compression Field Theory):

### a).Evaluation of $\varepsilon_x$

× ع	=(M <sub>u</sub> /dv+0.5N <sub>u</sub> + IV <sub>u</sub> -V <sub>p</sub> I -A <sub>ps</sub> *f <sub>po</sub> )/(2*(E <sub>s</sub> A <sub>s</sub> +E <sub>p</sub> *A <sub>p</sub>	))
# of A <sub>ps</sub>	12	If thereis no tension
Aps	1.836 in <sup>2</sup>	reinforcement in
ε <sub>x</sub>	0.000484093 in/in	conjunction with P/S. FsAs=0 in the

\**Note* : The parameters for caculating  $\varepsilon x$  is quite dependent on the location of crosssection for the support, such that  $\varepsilon x$  is the tensile stress at cross-sec caused by external and internal loads.

\*A<sub>ps</sub> , A<sub>s</sub>= P/S and non-prestressed reinforcement respectively at tensile zone NOT all cross-section.

 $*M_u$  = Absolute value of total factored moment at the cross-section.

\*N<sub>u</sub> = Factored axial force, taken as positive if tensile and negative if compressive (kips)

### **b).**Evaluation of $\beta$ and $\theta$

<del>θ=29+7000</del> *ε <sub>x</sub>			
θ	32.4	Degrees	
β	2.78		

\* For Calculating  $\beta$ , it is assumed that at least minimum amount of shear reinforcement is provided.

c).Evaluation of Concrete Contribution				
Vc=0.0	0.0316β√f'c b <sub>v</sub> d <sub>v</sub>			
Vc	102.164744	kips		
d).Evaluation of Required Transverse Reinforcement				
$V_s = A_v * f_v * d_v * \cot\theta / s$				
Check	Transverse	Reinforcement Required		
V <sub>s (Req'd)</sub>	312.6	kips		
A <sub>v</sub> /s <sub>Req'd)</sub>	0.0451	in²/in.		
Spacing, S	11.0	in.		
A <sub>v</sub> /s (Porvided)	0.05578112	in²/in.		
V <sub>s</sub> (Provided)	386.4236566	kips		

e).Checks:								
	Maximum Spacing Limit of Transverse Reinforcement:							
v <sub>u</sub> /f'c	0.135							
S <sub>max</sub>	12 in.							
Minimum Reinforcement Requirement:								
	A <sub>v,min</sub> ≥0.0316√f'cb <sub>v</sub> S/fy							
A <sub>v,min</sub>	A <sub>v,min</sub> 0.10032689 in <sup>2</sup>							
	Maximum Nominal Shear Resistance							
	$V_n \leq 0.25 f' cb_v d_v + V_p$							
	ОК							

Concrete Properties:							
fc', <sub>girder</sub>	7000	psi					
fc', <sub>deck/topping</sub>	4000	psi					
Prestr	essing Strand						
A <sub>ps</sub>	0.153	in <sup>2</sup>					
f <sub>pu</sub>	270000						
f <sub>py</sub>	243000	ksi					
f <sub>po</sub>	189000	ksi					
f <sub>se</sub>	152900	psi					
Ep	28500000	psi					
Total # P/S	44						
Total Area P/S	6.732	in <sup>2</sup>					
Slope of Draped P/S	7						
Centroid of Straight P/S (Frm-Bottom)	3.875	in.					
Centroid of Draped P/S (From-Bottom)	54.54	in.					
No.of Straight P/S strands	32						
No.of Draped P/S strands	12						
V <sub>p</sub>	34211.6983	lb					
General centroid of P/S strands from Bottom	17.6927273	in.					
e (eccentricity)	18.9072727	in.					
P <sub>se</sub>	1029322.8	lb					
Rei	nforcing Bars						
As	15.53	in <sup>2</sup>					
f <sub>y</sub>	60000	psi					
E	29500000	psi					
* <i>Note</i> : In case the topping and girder	(f <sub>no</sub> = A par	rameter for P/S)					
both have the same f'c, make sure that		tive prestress after all loses)					

ACI 318-08 approach for shear design (BT-72)

* <i>Note</i> : In case the topping and girder both have the same f'c, make sure that you enter f'c <sub>, deck, topping</sub> equal to that of f'c <sub>,girder</sub>	(f <sub>po</sub> = A parameter for P/S) (f <sub>se</sub> = Effective prestress after all loses)
(0.5 in. dia., seven-wire, low-relaxation)	

Overall Geometry and Sectional Properties:		
Non-Composite Section		
Over All Depth of Girder, <b>h</b>	72	in.
Width of Web, $b_v$		in.
Area of Cross-Section of Girder, <b>A</b> g	767	in²
Moment of Inertia, I <sub>g</sub>	545894	in <sup>4</sup>
Dis. From centroid to ext. bottom fiber, <b>y</b> <sub>b</sub>	36.6	in.
Dis. From centroid to ext. top fiber, $oldsymbol{y}_t$	35.4	in.
Composite Section		
Over all depth of the composite section, $oldsymbol{h}_{c}$	80	in.
Slab thickness, <b>t</b> <sub>s</sub>		in.
Total Area (transformed)of composite sect., <b>A</b> c	1412	in <sup>2</sup>
Moment of Inertia of the composite sec. I <sub>c</sub>	1097252	in <sup>4</sup>
Dis. From centroid of composite section to extreme bottom fiber, $\mathbf{y}_{bc}$	54.67	in.
Dis. From centroid of composite section to extreme top fiber of beam, $\mathbf{y}_{tg}$	17.33	in.
Dis. From centroid of composite section to extreme <u>top fiber of slab</u> , <b>y</b> <sub>tc</sub>	25.33	in.
Overall depth, d	76	in
distance from the top fiber to the centroid of P/S tendons, <b>d</b> <sub>p</sub> >= <b>0.8*h</b>	64	in.
Sectional Forces at Design Section		
Axial Load		
N <sub>u</sub>	0	lb
<b>Shear Forces (D.L, L.L)</b> Unfactored shear force due to beam weight, V <sub>d,girder</sub>	42300	lle
Unfactored shear force due to deck slab, $V_{d,slab}$		
Unfactored shear force due to barrier weight, $V_{d,slab}$	64600	
Unfact. shear force due to future wearing surface, $V_{d, wearing}$	7800	
Unfactored shear force due to $TOTAL$ D.L, $V_d$	14200	
Unfactored shear forces due to live load, V <sub>II</sub>	128900	
	137300	
FACTORED SHEAR FORCE, V <sub>u</sub> Moments (D.L,L.L)	404950	aı
Unfactored moment due to beam weight, <b>M</b> <sub>d,girder</sub>	3272400	lb.in
Unfactored moment due to deck slab, M <sub>d,slab</sub>	5005200	
Unfactored moment due barrier, M <sub>d,slab</sub>	-1675200	
Unfact. moment due to future wearing surface, <b>M<sub>d,wearing</sub></b>	-2932800	
Unfactored moment due to <b>TOTAL</b> D.L, M <sub>d</sub>	3669600	
STRACT CATION COLOR AND TO THE D.L. MA		
Unfactored moment due to live load, M <sub>LL</sub>	-20613600	lh in

# **SOLUTION:**

Detailed ACI Approach:

V -0 C		100 -1 70/5	lah d						
V <sub>ci</sub> =0.6	√f'c b <sub>w</sub> d <sub>p</sub> +v <sub>d</sub> +V <sub>i</sub> M <sub>cre</sub>		co <sub>w</sub> a						
V <sub>i</sub> =1.6*V <sub>LL</sub>									
	$M_{cre} = I_c / Y_{tension, Comp}$	•							
	M <sub>max</sub> =1.6I								
Vi	219680								
M <sub>max</sub>	-32981760	D							
f <sub>pe</sub>	0 p	si		,					
f <sub>d</sub>	84.7125072 p	si							
M <sub>cre</sub> , put the right <b>f'c</b>	12768531 II	p.in							
Vci	233223.379	D			-				
	V <sub>cw</sub> =(3.5√f'c+0.3f <sub>l</sub>	<sub>bc</sub> )*b <sub>w</sub> d <sub>p</sub> +V <sub>p</sub>							
f <sub>pc</sub> =P <sub>se</sub> /A <sub>g</sub> -P <sub>se</sub>	$e^{(y_{bc}-y_{b})/l_{g}+(M_{dg}-y_{b})/l_{g}+(M_{dg}-y_{b})}$	⊦M <sub>ds</sub> )*(y <sub>bc</sub> -y <sub>b</sub> )/	lg						
fpc	971.799582		psi						
V <sub>cw</sub>	258610.118		lb						
Ev	aluation of Concret	e Contributior	n:						
	V <sub>c</sub> =Min(V <sub>ci</sub>	,V <sub>cw</sub> )							
Vc	233223.379	lb							
	Transverse Reinf								
	φVc (Transverse Rei								
	/c/2 (Provide Minin φVc/2(No Trans.Rei								
	$V_s = V_u / \phi - V_c <$								
φVc	174917.534	lb							
Vs	305213.578	Ib							
Trans. F	Reinforc	ement	: Req'	d					
	A <sub>v</sub> /S=Vs/	f <sub>y</sub> d							
A <sub>v</sub> /S (Req'd)	0.0669328		in²/in.						
Assume:									
S	9	in. c/c							
Area (#5 stirrups)	0.306796								
A <sub>v</sub> /s (Provided)	0.068176	592 in <sup>2</sup>							
V <sub>s</sub> (Provided)	305213.5								

Minimum Shear Reinforcement						
1 A <sub>v,m</sub>	<sub>in</sub> =50b <sub>w</sub> s/f <sub>y</sub>					
2 A <sub>v,mir</sub>	=0.75√f'c b <sub>w</sub> s/f <sub>y</sub>		Select the larger			
3 A <sub>v,mi</sub>	3 A <sub>v,min</sub> =A <sub>ps</sub> f <sub>pu</sub> S/80f <sub>y</sub> d√(d/b <sub>w</sub> )					
A <sub>v,min</sub> =Min						
A <sub>v,min</sub> /S	0.005 in <sup>2</sup> /i	in.				
A <sub>v,min</sub> /S	0.00627495 in <sup>2</sup> /i	in.				
A <sub>v,min</sub> /S	0.01773308 in <sup>2</sup> /i	ín.				
Selected A <sub>v,min</sub> /S	0.00627495 in <sup>2</sup> /i	in.				

Maximum Spacing Allowed							
Max.Spacing= 0.75*h or 24in.							
If Vs > 4√f'c b <sub>w</sub> d Provide Max.Spacing/2							
Max.Spacing	Max.Spacing 24 in.						
Applicabe or Selected S <sub>max</sub>	12	in.					

Capacity Predictions: (V=Vc+Vs)							
Simplified Method (Kips) AASHTO LRFD (Kips) ACI (Kips) Response 2000 (Kips)							
458.2974935	488.588401	538.437	576.5555556				




Figure A. 4 Response-2000 output  $(V_u, M_u)$ 

## Development of Interaction Diagram for Combined Shear and Torsion using AASHTO LRFD General Procedure and Corresponding ACI 318-08 Provisions

Information required:							
bv	8	in					
h	12	in					
dv	9.27	in					
f'c	3.12	ksi					
Aoh	59.4	in <sup>2</sup>					
Ph	31.8	in					
At	0.077	in <sup>2</sup>					
fyt	38.4	ksi					
s	4	in					
Es	29000	ksi					
As	1.342	in <sup>2</sup>					
fy	62.3	ksi					

### AASHTO LRFD General Procedure:

AASHTO-LRFD APPROACH:	
V <sub>n</sub> =V <sub>c</sub> +V <sub>s</sub>	Eq-1
$T_n = 2^*A_o^*A_t^*f_{yt}^* \cot\theta/s$	Eq-2
$V_s = A_v * f_{yt} * d* \cot\theta / s$	Eq-3
$V_{c}$ =0.0316 $\beta$ (f'c) <sup>0.5</sup> $b_{v}d_{v}$	Eq-4
A <sub>o</sub> =0.85A <sub>oh</sub>	Eq-5
$A_t*f_{yt}/s=T_n/(2A_o*\cot\theta)+(V_n-V_c)/(2d\cot\theta)$	Eq-6
$\epsilon_s = [V^2 + \{0.9P_h * T/(1.7A_{oh})\}^2]^{0.5} / E_s A_s$	Eq-7
β=4.8/(1+750ε <sub>s</sub> )	Eq-8
θ=29+3500ε <sub>s</sub>	Eq-9

Perform Goal Seek function such that the value in column "L,M,N" is equal to zero by changing the values in column "C". Also the columns with pink color also require Goal Seek such that the value of column "F" has to equal zero by changing the value of column "E". It is very IMPORTAN to note that the goal seek for the columns with yellow backgraound has to be performed first.

	V, kip	T, kip.in (from Eq-6, above)	0.25fcb <sub>v</sub> d <sub>v</sub> =[V <sup>2</sup> +{0.9*Ph *T/(1.7*A <sub>oh</sub> )} <sup>2</sup> ] <sup>0.5</sup> T, kip.in	T, kip.in	T, satisfying long.reinf. AASHTO-LRFD (5.8.3.6.3-1)	Controlling, T (kip.in)	٤s	θ(Degree)	β	Vc	A <sub>t</sub> *f <sub>yt</sub> /s-T <sub>n</sub> /(2A <sub>o</sub> *cotθ)-(V <sub>n</sub> -V <sub>c</sub> )/(2dcotθ)=0
	0	118.84	204.09	366.62	0.00	118.84	0.00	32.03	2.91	12.05	0.00
	2	118.82	203.97	365.80	0.00	118.82	0.00	32.03	2.91	12.04	0.00
	4	118.75	203.61	365.00	0.00	118.75	0.00	32.05	2.90	12.02	0.00
	6	118.64	202.99	364.20	0.00	118.64	0.00	32.07	2.89	11.98	0.00
	8	118.49	202.13	363.42	0.00	118.49	0.00	32.10	2.88	11.93	0.00
S	10	118.30	201.02	362.64	0.00	118.30	0.00	32.15	2.87	11.87	0.00
	12	117.21	199.65	361.55	0.00	117.21	0.00	32.18	2.86	11.82	0.00
	14	108.19	198.03	357.49	0.00	108.19	0.00	32.03	2.91	12.04	0.00
$\mathbf{\Sigma}$	16	98.87	196.13	353.47	0.00	98.87	0.00	31.90	2.96	12.25	0.00
	18	89.43	193.96	349.63	0.00	89.43	0.00	31.80	3.00	12.43	0.00
	20	79.73	191.51	346.00	0.00	79.73	0.00	31.71	3.04	12.56	0.00
	22	69.67	188.76	342.62	0.00	69.67	0.00	31.66	3.06	12.66	0.00
	24	59.16	185.70	339.57	0.00	59.16	0.00	31.63	3.07	12.70	0.00
	26	48.11	182.32	336.93	0.00	48.11	0.00	31.64	3.07	12.69	0.00
	28	36.63	178.59	334.80	0.00	36.63	0.00	31.69	3.05	12.61	0.00
	30	24.57	174.50	333.23	0.00	24.57	0.00	31.77	3.01	12.47	0.00
	32	12.06	170.02	332.27	0.00	12.06	0.00	31.89	2.96	12.26	0.00
	33.8	0.25	165.63	331.94	0.00	0.25	0.00	32.04	2.91	12.03	0.00

### EXPERIMENTAL DATA FROM KHALDOUN. N. RAHAL, 2003:

Speci	Experimental								
men	T (kN.m)	T (kip.in)	V (kN)	V (kip)					
1		0		35.5					
2		0		35.3					
3		134.52		0					
4		125.88		0					
5		78.12		20.9					
6		52.08		26.4					
7		102.42		14.22					
8		110.64		6.94					
9		65.52		22.7					
10		29.256		29.7					




Figure A. 5 Shear-torsion interaction diagrams along with experimental data for specimens tested by Klus (1968)

For S	olid Se	ections:
bw	8	in
d	10.3	in
f'c	3.12	ksi
Aoh	59.4	in <sup>2</sup>
Ph	31.8	in
At	0.0767	in <sup>2</sup>
At fyt	38.4	
S	4	in
θ	45	Degree

ACI 318-08 assuming  $\theta = 45^{\circ}$ 

ATTN:
In Eq-4, the value for f'c has to be in psi.
Modify Eq-7 for hollow sections, ACI-08, Eq(11-19)

ACI APPRO	<mark>ΑCH θ=</mark> 45 D	eg:				
		V <sub>n</sub> =V <sub>c</sub> +V <sub>S</sub>				
$T_n = 2*A_o*A_t*f_{vt}*\cot\theta/s$						
	$V_s = A_v * f_{vt} * d * \cot\theta / s$					
	$V_{c}=2(f'c)^{0.5}b_{w}d$					
	A <sub>o</sub> =0.85A <sub>oh</sub>					
	A <sub>t</sub> *f <sub>yt</sub> /s=T	$\Gamma_n/(2A_o^*\cot\theta)+(V_n-V_c)/(2d\cot\theta)$				
Not	e: The valu	e of f'c for determining Vc is in (psi)				
Vc	9.205227	kips				

		***According To ACI-08 Equation (11-18):
		$[(V/(b_w d))^2 + (T*Ph/(1.7A_{oh}^2))^2]^{0.5} \le (10(f'c)^{0.5})^{10}$
V (kips)	T (kip.in)	T (kip.in), ACI(11-18)
0	74.3535936	3331.746793
5	74.3535936	3331.727133
10	70.45766283	3331.668154
15	45.94795409	3331.569853
20	21.43824536	3331.432226
24.3	0.359895842	3331.282411

## ACI Assuming $\theta = 30^{\circ}$

Soli	id Sect	ions:
bw	8	in
d	10.3	in
f'c	3.12	ksi
Aoh	59.4	in <sup>2</sup>
Ph	31.8	in
At	0.0767	in <sup>2</sup>
fyt	38.4	ksi
s	4	in
θ	30	Degree

ATTN:

In Eq-4, the value for f'c has to be in psi. Modify Eq-7 for hollow sections, ACI-08, Eq(11-19)

ACI APPRO	OACH:		
		V <sub>n</sub> =V <sub>c</sub> +V <sub>s</sub>	Eq-1
	T,	$_{n}=2*A_{o}*A_{t}*f_{yt}*\cot\theta/s$	Eq-2
		V <sub>s</sub> =A <sub>v</sub> *f <sub>yt</sub> *d*cotθ/s	Eq-3
		$V_{c}=2(f'c)^{0.5}b_{w}d$	Eq-4
		A <sub>o</sub> =0.85A <sub>oh</sub>	Eq-5
	A <sub>t</sub> *f <sub>yt</sub> /s=	$T_n/(2A_o^*\cot\theta)+(V_n-V_c)/(2d)$	Eq-6
	Note: The	value of f'c for determining Vc is	s in (psi)
Vc	9.205227	kips	

		***According To ACI-08 Equation (11-18):
		$[(V/(b_w d))^2 + (T*Ph/(1.7A_{oh}^2))^2]^{0.5} \le (10(f'c)^{0.5})^{0.5}$
V (kips)	T (kip.in)	T (kip.in), ACI(11-18)
0	128.7842018	3331.746793
5	128.7842018	3331.727133
10	122.0362518	3331.668154
15	79.584191	3331.569853
20	37.13213018	3331.432226
24.3	0.623357883	3331.282411

# **Appendix B - Verification of Response-2000**

B1		ORTEDC CASE:	Control : V-Gxy Control : M-Phi
	Member Prope		176.0 495.8
Total Spans Lengtr	5.4	m	
width, w	0.3	m	
height, h	1	m	
ritical section from	2.7	m	0.8 1.6
Yconcrete	23.56	KN/m <sup>3</sup>	
Wself-wt	7.068	KN/m	
/ <sub>expeirimental</sub>	225	KN	Note : Vexperimental is the shear where it causes shear failure at critical
	Force at Critical Sec	ion, L.L and D.L	section of the member.
V <sub>crit,D.L</sub>	0	KN	
V <sub>crit,LL</sub>	225	KN	Response2000
romit,LL ∕u	225	KN	Vresp2000 176 KN
	nent at Critical Secti		Vexp 225 KN
M <sub>cirt.D.L</sub>	25.76286	KN.m	Vexp/Vresp2000 1.278409
M <sub>cirt.LL</sub>	607.5	KN.m	
Mu	633.26286	KN.m	
	033.20200	KIN.III	
B1		ORTEDC CASE:	Control : V-Gxy Control : M-Phi 213.9 595.2
	Member Prope	ties:	
Fotal Spans Lengt			
	5.4	m	
	5.4 0.3	m m	
width, w height, h			
width, w	0.3	m	1.2 2.1
width, w height, h critical section from	0.3 1	m m	1.2 21
width, w height, h critical section from right support, L	0.3 1 2.7	m m m	1.2 2.1
width, w height, h critical section from right support, L Yconcrete Wsef-wt	0.3 1 2.7 23.56	m m KN/m <sup>3</sup>	1.2     2.1
width, w height, h oritical section from right support, L Yconcrete Ws <del>cliwt</del>	0.3 1 2.7 23.56 7.068	m m KN/m <sup>3</sup> KN/m KN	
width, w height, h critical section from right support, L Yconcrete Wsef-wt Vesperimental Shear	0.3 1 2.7 23.56 7.068 320	m m KN/m <sup>3</sup> KN/m KN	<i>Note</i> : Vexperimental is the shear where it causes shear failure at critical
width, w height, h oritical section from rightsupport, L Yconcrete Wself-wt Vesperimental Shear Vorit, D. L	0.3 1 2.7 23.56 7.068 320 Force at Critical Sec	m m KN/m <sup>3</sup> KN/m KN	<i>Note</i> : Vexperimental is the shear where it causes shear failure at critical
width, w height, h oritical section from rightsupport, L Yoonarete Wself-wt Verperimental Shear Vorit, D.L Vorit, LL	0.3 1 2.7 23.56 7.068 320 Force at Critical Sec 0	m m KN/m <sup>3</sup> KN/m KN ion, L.L and D.L KN	<i>Note</i> : Vexperimental is the shear where it causes shear failure at critical section of the member.
width, w height, h critical section from rightsupport, L Yooncete Wself-wt Verperimental Shear Vorit, D.L Vorit, LL Vu	0.3 1 2.7 23.56 7.068 50rce at Critical Sec 0 320	m m KN/m <sup>3</sup> KN/m KN kN ion, L.L and D.L KN KN KN	Note : Vexperimental is the shear where it causes shear failure at critical section of the member.  Response 2000
width, w height, h oritical section from rightsupport, L Yooncrete Wself-wt Verperimental Shear Vorit, D.L Vorit, LL Vu	0.3 1 2.7 23.56 7.068 507ce at Critical Sec 0 320 320	m m KN/m <sup>3</sup> KN/m KN kN ion, L.L and D.L KN KN KN	Note : Vexperimental is the shear where it causes shear failure at critical section of the member.         Response 2000         Vresp2000       213.9 KN
width, w height, h critical section from right support, L Yconcrete Wself-wt Vegerimental Shear Vorit, D.L Vorit, LL Vu Mon	0.3 1 2.7 23.56 7.068 320 Force at Critical Sec 0 320 320 ment at Critical Sec	m m KN/m <sup>3</sup> KN/m KN KN ion, L.L and D.L KN KN KN KN	Response 2000         Vresp2000       213.9 KN         Vresp2000       213.9 KN         Vresp2000       213.9 KN

## (Simply Supported Beams)

B1(	OOH SIMPLY SUPPOR	TEDC CASE:	Control : V-G	ixy		Control : M-Phi
DI			222.7		627.2	
otal Spans Length	Member Properties 5.4					
otal Spans Lengtr vidth, w	0.3	m			·	
eight, h	1	m	/			
ritical section from						
right support, L	2.7	m		0.9		1.8
Yconcrete	23.56	KN/m <sup>3</sup>		0.3	.   <u>v</u>	1.0
W <sub>self-wt</sub>	7.068	KN/m				
expeirimental	193	KN	Note : Vexperimental is the	e shear whe	re it cause	s shear failure at critical
	Force at Critical Section	, L.L and D.L	section of the member.			
crit.D.L	0	KN				
crit,LL	193	KN		Respo	onse <b>2000</b>	
'u	193	KN	Vresp2000	222.7		
Mon	nent at Critical Section,	LL and D.L	Vexp	193	KN	
l <sub>art,D.L</sub>	25.76286	KN.m	Vexp/Vresp2000	0.866637		
A <sub>cirt,LL</sub>	521.1	KN.m				1
/u	546.86286	KN.m				
B10		TEDCOME	Control : V-G	ixy		Control : M-Phi
BIU			222.7		627.2	2
	Member Properties					
otal Spans Length	5.4	m		×		
vidth, w eight, h	0.3	m				
ritical section from						
right support, L	2.7	m				
Yconcrete	23.56	KN/m <sup>3</sup>		0.9		1.
W <sub>self-wt</sub>	7.068	KN/m				
exneirimental	217	KN	Note : Vexperimental is the	e shear whe	re it cause	s shear failure at critical
	217 Force at Critical Section		Note : Vexperimental is the section of the member.	e shear whe	re it cause	s shear failure at critical
Shear	217 Force at Critical Section 0			e shear whe	re it cause	s shear failure at critical
Shear Shear	Force at Critical Section 0	, L.L and D.L KN				s shear failure at critical
Shear   crit,D.L crit,L.L	Force at Critical Section	, L.L and D.L			onse2000	s shear failure at critical
Shear crit,D.L crit,LL 'u	Force at Critical Section 0 217	, L.L and D.L KN KN KN	section of the member.	Respo	onse <mark>2000</mark> KN	s shear failure at critical
Shear crit,D.L crit,LL U Mon	Force at Critical Section 0 217 217	, L.L and D.L KN KN KN	section of the member.	Respo 222.7 217	onse <mark>2000</mark> KN	s shear failure at critical
Shear crit,D.L u Mon drt,D.L	Force at Critical Section 0 217 217 ent at Critical Section,	, L.L and D.L KN KN KN LL and D.L	section of the member.	Respo 222.7 217	onse <mark>2000</mark> KN	s shear failure at critical
Shear art,D.L art,L.L J Grt,D.L art,L.L	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9	, L.L and D.L KN KN KN LL and D.L KN.m	section of the member.	Respo 222.7 217	onse <mark>2000</mark> KN	s shear failure at critical
Shear arit,D.L J Mon dart,D.L lart,L.L lu	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286	, LL and D.L KN KN KN KN KN.m KN.m KN.m	vresp2000 Vexp Vexp Vresp2000	Responsibility           222.7           217           0.974405	onse2000 KN KN	s shear failure at critical
Shear arit,D.L J Mon dart,D.L lart,L.L lu	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9	, LL and D.L KN KN KN KN KN.m KN.m KN.m	section of the member.	Responsibility           222.7           217           0.974405	onse2000 KN KN	
Shear arit,D.L J Mon dart,D.L lart,L.L lu	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286	, LL and D.L KN KN KN LL and D.L KN.m KN.m KN.m	vresp2000 Vexp Vexp Vresp2000	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
Shear crit,D.L crit,LL U Grit,D.L Grit,D.L Iu U BLL BL	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE:	section of the member.	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
Shear i crit,D.L crit,L.L lart,D.L lart	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: S: M	section of the member.	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
Shear crit,D.L crit,L.L U Mon Mort,D.L Mort,L.L Mu B10 otal Spans Length ridth, w	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE:	section of the member.	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
Shear ) 'crit,D.L 'crit,D.L 'u Mon Mart,D.L Aart,LL Au Otal Spans Length vidth, w eight, h	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3 1	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: S: M	section of the member.	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
ferit,D.L ferit,LL fu Mon Mart,D.L Mu Mu B1 otal Spans Length vidth, w leight, h ritical section from	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE:	section of the member.	Resp           222.7           217           0.974405	nse2000 KN KN CC	ontrol : M-Phi
Shear )	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: CASE: M M M	section of the member.	Responsibility           222.7           217           0.974405	nse2000 KN KN CC	
Shear	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3 1	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: : : m m m KN/m <sup>3</sup>	section of the member.	Resp           222.7           217           0.974405	nse2000 KN KN CC	ontrol : M-Phi
Shear i crit, D.L	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 OOL SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: CASE: M M M	section of the member.	Resp           222.7           217           0.974405	nse2000 KN KN CC	ontrol : M-Phi
Shear i crit, D.L crit, L.L u Vart, D.L Vart, D.L Vart, L.L lu Vart, L.L lu Vart, L.L lu Vart, L lu Vart, Vart, Var	Force at Critical Section         0         217         217         217         217         217         217         217         217         217         217         217         217         217         217         217         25.76286         00L         SIMPLY SUPPORT         Member Properties         5.4         0.3         1         2.7         23.56         7.068	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: CASE: m m m m KN/m <sup>3</sup> KN/m	section of the member.	Resp.       222.7       217       0.974405	олье2000 КN КN Сс 447.7	ontrol : M-Phi
Shear i rit,D.L rit,D.L dirt,LL dirt,LL u B10 Shar Mon Shar Mon Shar Shar Shear	Force at Critical Section         0         217         217         217         217         217         217         217         217         217         217         217         217         217         217         217         217         25.76286         00L         SIMPLY SUPPORT         Member Properties         5.4         0.3         1         2.7         23.56         7.068         223	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: TEDC CASE: T M M KN/m <sup>3</sup> KN/m KN/m	section of the member.	Resp.       222.7       217       0.974405	олье2000 КN КN Сс 447.7	ontrol : M-Phi
Shear crit,D.L crit,D.L drt	Force at Critical Section         0         217         217         217         217         217         217         217         217         217         217         217         217         217         217         25.76286         001         SIMPLY SUPPORT         Member Properties         5.4         0.3         1         2.7         23.56         7.068         223	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: m m m KN/m <sup>3</sup> KN/m KN/m	section of the member.	Resp.       222.7       217       0.974405	олье2000 КN КN Сс 447.7	ontrol : M-Phi
Shear i crit,D.L crit,LL u lort,LL lort,LL lort,LL lort,LL lort,LL lort,LL lort,LL lort,LL lort,LL lort,LL lort,L lort,LL lort,L lort,LL lort,L lort,LL lort,DL lort,LL lort,DL lort,LL lo	Force at Critical Section         0         217         217         217         217         217         217         217         217         217         217         217         217         217         217         217         217         25.76286         00L         SIMPLY SUPPORT         Member Properties         5.4         0.3         1         2.7         23.56         7.068         223	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: TEDC CASE: T M M KN/m <sup>3</sup> KN/m KN/m	section of the member.	Resp.       222.7       217       0.974405	олье2000 КN КN Сс 447.7	ontrol : M-Phi
Shear ) Crit,D.L Crit,D.L Crit,D.L Crit,LL Crit,LL Crit,LL Crit,LL Crit,LL Crit,L Crit,LL Crit,L Cri	Force at Critical Section         0         217         217         217         217         217         217         217         217         217         217         217         217         217         217         25.76286         001         SIMPLY SUPPORT         Member Properties         5.4         0.3         1         2.7         23.56         7.068         223	, LL and D.L KN KN KN KN.m KN.m KN.m EDC CASE: m m m KN/m <sup>3</sup> KN/m KN/m	section of the member.	Respondent         222.7         217         0.974405	олье2000 КN КN Со 447.7	ontrol : M-Phi
Shear i crit,D.L crit,LL u Vart,D.L v v tart,D.L v start,D.L v sta	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 00L SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7 23.56 7.068 223 Force at Critical Section 0	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: COM COM KN.m KN/m <sup>3</sup> KN/m KN/m KN/m	section of the member.	Respondent         222.7         217         0.974405	re it cause	ontrol : M-Phi
Shear i crit, D. L i dit, L L i i dit, L L i dit, L L i i dit, L L i i dit, L L i i dit, section from right support, L i i cal section from ri i c	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 00L SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7 23.56 7.068 223 Force at Critical Section 0 223	, LL and D.L KN KN KN KN KN.m KN.m KN.m CDC CASE: CASE	section of the member.	Respr         222.7         217         0.974405         9         0.974405         9         0.9         0.9         0.9         Respr         158.9	nse2000 KN KN CC 447.7 re it cause nse2000 KN	ontrol : M-Phi
Shear i crit, D.L i crit, D.L i crit, LL i u i crit, LL i i i crit, LL i i i i i crit, D.L crit, D.L i i i i i crit, D.L i i i i i i i i i i i i i i i i i i i	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 00L SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7 23.56 7.068 223 Force at Critical Section 0 223 nent at Critical Section,	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: T T CCCASE: T M KN/m <sup>3</sup> KN/m <sup>3</sup> KN/m KN KN/m KN KN/m KN KN KN KN	section of the member.	Respondent         222.7         217         0.974405         V         0.9         0.9         0.9         Respondent         158.9         223	nse2000 KN KN Co 447.7 re it cause nse2000 KN KN	ontrol : M-Phi
Shear i crit, D.L itical Spans Length itical section from right support, L Ycancete WseiFwit crit, D.L crit, D.L Crit, LL itical Schear i crit, D.L Crit, D.	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 00L SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7 23.56 7.068 1 Force at Critical Section 0 223 nent at Critical Section, 25.76286	, LL and D.L KN KN KN.m KN.m KN.m KN.m CDC CASE: TEDC CASE: T TEDC CASE: KN/m <sup>3</sup> KN/m <sup>3</sup> KN/m KN/m KN KN KN KN KN KN KN KN KN KN	section of the member.	Respondent         222.7         217         0.974405         V         0.9         0.9         0.9         Respondent         158.9         223	nse2000 KN KN Co 447.7 re it cause nse2000 KN KN	ontrol : M-Phi
Shear crit,D.L u Vort,D.L v vort,D.L v vort,D.L v vort,D.L v vort,D.L v vort,D.L v vort,D.L crit,D.L crit,D.L v vort,D.L vort,	Force at Critical Section 0 217 217 nent at Critical Section, 25.76286 585.9 611.66286 00L SIMPLY SUPPORT Member Properties 5.4 0.3 1 2.7 23.56 7.068 223 Force at Critical Section 0 223 nent at Critical Section,	, LL and D.L KN KN KN KN.m KN.m KN.m CDC CASE: T T CCCASE: T M KN/m <sup>3</sup> KN/m <sup>3</sup> KN/m KN KN/m KN KN/m KN KN KN KN	section of the member.	Respondent         222.7         217         0.974405         V         0.9         0.9         0.9         Respondent         158.9         223	nse2000 KN KN Co 447.7 re it cause nse2000 KN KN	ontrol : M-Phi

B10		TEDC CASE:	Control : V-Gxy Control : M-Phi	
	Member Properties		165.3 465.8	
Total Spans Lengt	5.4	m		
width, w	0.3	m		
height, h	1	m		
ritical section from right support, L	2.7	m		
Yconcrete	23.56	KN/m <sup>3</sup>	1.5	.6
Wself-wt	7.068	KN/m		
experimental	204	KN	Note : Vexperimental is the shear where it causes shear failure at critical	
'expeirimental Shear F	orce at Critical Section		section of the member.	
/ <sub>crit,D.L</sub>	0	KN		
erit.LL	204	KN	Response2000	
*cmit,LL √u	204	KN	Vresp2000 165.3 KN	
	ent at Critical Section,		Vexp 204 KN	
M <sub>cirt.D.L</sub>	25.76286	KN.m	Vexp/Vresp2000 1.23412	
M <sub>cirt,LL</sub>	550.8	KN.m		
Mu	576.56286	KN.m		
	570.50200	N.V.III		
BN	LOO SIMPLY SUPPOR	TEDC CASE:	Control : V-Gxy Control : M-Phi 175.3 496.9	
	Member Properties	s:		
Fotal Spans Lengtr	5.4	m		
width, w	0.3	m		
height, h	1	m		
ritical section from right support, L	2.7	m	1.7	2.0
Yconcrete	23.56	KN/m <sup>3</sup>		
W <sub>self-wt</sub>	7.068	KN/m		
experimental	192	KN	Note : Vexperimental is the shear where it causes shear failure at critical	
	orce at Critical Section	, L.L and D.L	section of the member.	
/crit,D.L	0	KN		
V <sub>crit,LL</sub>	192	KN	Response 2000	
Vu	192	KN	Vresp2000 175.3 KN	
	ent at Critical Section,		Vexp 192 KN	
Mcirt,D.L	25.76286	KN.m	Vexp/Vresp2000 1.095265	
M <sub>cirt,LL</sub>	518.4	KN.m		
Иu	544.16286	KN.m		
BND	100 SIMPLY SUPPO	RTEDC CASE:	Control : V-Gxy Control : M-Phi	
	Member Properties		201.1 570.3	
fotal Spans Length	5.4	s. m		
width, w	0.3	m		
	1	m		
height, h				
	27	171		
-	2.7	m		21
ritical section from right support, L Υ <del>αοιαείε</del>	2.7 23.56	m KN/m <sup>3</sup>	1.2	2.1
ritical section from right support, L			1.2	2.1
ritical section from right support, L Υ΄ <sub>concrete</sub> W <sub>self-wt</sub>	23.56	KN/m <sup>3</sup>	Note : Vexperimental is the shear where it causes shear failure at critical	2.1
ni ti cal secti on from right support, L Yanarete WsetFwt Pespeinnental	23.56 7.068	KN/m <sup>3</sup> KN/m KN		2.1
ni ti cal section from right support, L Yanarete W <sub>self-wt</sub> /experimental Shear F	23.56 7.068 258	KN/m <sup>3</sup> KN/m KN	Note : Vexperimental is the shear where it causes shear failure at critical	2.1
ofitical section from right support, L ?conarete Wself-wt Verpeisimental Shear F Verit, D.L	23.56 7.068 258 Force at Critical Section	KN/m <sup>3</sup> KN/m KN	Note : Vexperimental is the shear where it causes shear failure at critical	2.1
critical section from right support, L Yaznarete Wseifwet expesimental Shear F Varit, D.L Varit, L.L	23.56 7.068 258 Force at Critical Section 0	KN/m <sup>3</sup> KN/m KN 1, L.L and D.L KN	<i>Note</i> : Vexperimental is the shear where it causes shear failure at critical section of the member.	2.1
zi ti cal secti on from right support, L Yaonaete Wseif-wt expesimental Crit,D.L erit,LL	23.56 7.068 258 Force at Critical Section 0 258	KN/m <sup>3</sup> KN/m KN t, LL and D.L KN KN KN	Note : Vexperimental is the shear where it causes shear failure at critical section of the member.	2.1
critical section from right support, L Yconcrete Wself-we Verpekinnental Shear F Verit, D. L Verit, L. L Vu Morri	23.56 7.068 258 orce at Critical Section 0 258 258	KN/m <sup>3</sup> KN/m KN t, LL and D.L KN KN KN	Note: Vexperimental is the shear where it causes shear failure at critical section of the member.         Response 2000         Vresp2000       201.1 KN	2.1
critical section from right support, L Yconcrete Wseif-wt Verpetimental Verit,D.L Verit,LL	23.56 7.068 258 Force at Critical Section 0 258 258 eent at Critical Section,	KN/m <sup>3</sup> KN/m I, L.L and D.L KN KN KN LL and D.L	Note : Vexperimental is the shear where it causes shear failure at critical section of the member.         Response 2000         Vresp2000         Vresp2000         Vresp2000         Vresp2000         Vresp2000         Vexp         Vexp	2.1
ri ti cal section from ri ght support, L Yanarete W <sub>self-wt</sub> experimental Crit,D.L at Morr Acirt,D.L	23.56 7.068 258 Force at Critical Section 0 258 258 ent at Critical Section, 25.76286	KN/m <sup>3</sup> KN/m , L.L and D.L KN KN KN LL and D.L KN.m	Note : Vexperimental is the shear where it causes shear failure at critical section of the member.         Response 2000         Vresp2000         Vresp2000         Vresp2000         Vresp2000         Vresp2000         Vexp         Vexp	2.1

BH	<b>100</b> SIMPLY SUPPOR	TEDC CASE:	215.5		610.9	Control : M-Phi
	Member Properties		6.612		010.5	,
Fotal Spans Length	5.4	m			<u> </u>	
width, w	0.3	m				
height, h	1	m				
ritical section from right support, L	2.7	m			_	
Ycancrete	23.56	KN/m <sup>3</sup>		1.	6	2.2
Wself-wt	7.068	KN/m				1
espeirimental	193	KN	Note : Vexnerimer	ntal is the shear wh	ere it cause	es shear failure at critical
	Force at Critical Section		section of the mer			
/crit,D.L	0	KN				
/ <sub>crit,LL</sub>	193	KN		Res	onse 2000	
/u	193	KN	Vresp20	00 215	5 KN	
Mon	nent at Critical Section,	LL and D.L	Vexp	19	3 KN	
Mairt, D. L	25.76286	KN.m	Vexp/V	resp2000 0.89559	2	
M <sub>art,LL</sub>	521.1	KN.m				1
Mu	546.86286	KN.m				
BHC	100 SIMPLY SUPPO	RTEDC CASE:	252.8	ol : V-Gxy	706	Control : M-Phi 5.0
	Member Properties	s:				
Fotal Spans Length	5.4	m				
width, w	0.3	m	/		N	
neight, h	1	m	<i>[</i>			
ritical section from	2.7	m				
right support, L					_ <b>_</b> /	~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~
right support, L Ycanarete	23.56	KN/m <sup>3</sup>		1	.3	2.2
	23.56 7.068	KN/m <sup>3</sup> KN/m		1 1	.3	2.2
Ŷcancrete W <sub>selFwt</sub>			Note : Vexperimer	İ	_   -	2.2 es shear failure at critical
Ycancrete W <sub>selF-wt</sub> experimental	7.068	KN/m KN	Note : Vexperiments section of the mer	ntal is the shear wh	_   -	
Ycanarete W <sub>selF-wt</sub> /experimental Shear I	7.068 278	KN/m KN		ntal is the shear wh	_   -	
Yconcrete WseF-wt /experimental Shear /crit,D.L	7.068 278 Force at Critical Section	KN/m KN I, L.L and D.L		i ntal is the shear wh nber.	ere it cause	
Ycanarete WselFwt (experimental Shear /orit,D.L /orit,L.L	7.068 278 Force at Critical Section 0	KN/m KN 1, L.L and D.L KN	section of the mer	ntal is the shear wh πber. Res	_   -	
Ycanarete WselFwt /expesimental /arit,D.L /arit,L.L /u	7.068 278 Force at Critical Section 0 278	KN/m KN I, L.L and D.L KN KN KN		ntal is the shear wh nber. Res 100 252	ere it cause	
Ycanarete WseFwt /experimental /crit,D.L /crit,LL /u Mon	7.068 278 Force at Critical Section 0 278 278	KN/m KN I, L.L and D.L KN KN KN	section of the mer	ntal is the shear wh nber. 100 252 27	ere it cause conse2000 8 KN 8 KN	
Ycanarets WseFwit experimental Shear Varit,D.L Varit,LL Vu Moirt,D.L	7.068 278 Force at Critical Section 0 278 278 ment at Critical Section, 25.76286	KN/m KN I, LL and D.L KN KN KN LL and D.L KN.m	section of the mer	ntal is the shear wh nber. 100 252 27	ere it cause conse2000 8 KN 8 KN	
Ycanarets WseFwit Verpekimental Shear Varit,D.L Varit,LL Vu Mairt,D.L Mairt,LL	7.068 278 Force at Critical Section 0 278 278 278 nent at Critical Section, 25.76286 750.6	KN/m KN I, LL and D.L KN KN KN LL and D.L KN.m	section of the mer	ntal is the shear wh nber. 100 252 27	ere it cause conse2000 8 KN 8 KN	
Y concrete WselF-wt /experimental Vorit,D.L /orit,LL /u Moirt,D.L Moirt,D.L Moirt,LL	7.068 278 Force at Critical Section 0 278 278 278 cont at Critical Section, 25.76286 750.6	KN/m KN LL and D.L KN KN KN LL and D.L KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the shear whe	ere it cause conse2000 8 KN 8 KN	
Ycancrete WseF-wt /experimental /crit,D.L /crit,L.L /u Moirt,D.L Mirt,L.L /u	7.068 278 Force at Critical Section 0 278 control 278 control 278 control 278 control 278 control 275 control 276.3628 contro	KN/m KN I, LL and D.L KN KN LL and D.L KN.m KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear wh nber. 100 252 27	ere it cause conse2000 8 KN 8 KN	es shear failure at critical
Ycanorete WseFwrt /expesimental /orit,D.L /orit,LL /u Moirt,D.L Moirt,D.L Mu BRL	7.068 278 Force at Critical Section 0 278 278 enent at Critical Section, 25.76286 750.6 776.36286	KN/m KN LL and D.L KN KN KN LL and D.L KN.m KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the shear whe	ere it cause conse2000 8 KN 8 KN 4	es shear failure at critical
Yconorete WseFwet (expesimental /orit,D.L /orit,LL /u Moirt,D.L Moirt,D.L Mu BRL	7.068 278 Force at Critical Section 0 278 278 278 278 275.76286 750.6 750.6 776.36286 100 SIMPLY SUPPOR Member Properties 5.4	KN/m KN LL and D.L KN KN LL and D.L KN.m KN.m KN.m KN.m STEDC CASE: S: m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the shear whe	ere it cause conse2000 8 KN 8 KN 4	es shear failure at critical
Ycanorete WseF-wt (expesimental /orit,D.L /orit,LL /u Moirt,D.L Moirt,D.L Mu BRL Mu fotal Spans Length width, w	7.068 278 Force at Critical Section 0 278 278 ment at Critical Section, 25.76286 750.6 776.36285 100 SIMPLY SUPPOR Member Properties 5.4 0.3	KN/m KN LL and D.L KN KN KN.m KN.m KN.m KN.m KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the shear whe	ere it cause conse2000 8 KN 8 KN 4	es shear failure at critical
γconcrete       WselFwt       (expesimental       /crit,D.L       /crit,LL       /u       Moint,D.L       Micrit,D.L       Micrit,D.L       Micrit,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,LL       Mu       BRL       Gotal Spans Length       widthy, w       eight, h	7.068       278         278       278         Force at Critical Section       278         278       278         278       278         278       278         100       5.76286         776.36286       776.36286         1       1	KN/m KN LL and D.L KN KN KN KN.m KN.m KN.m KN.m STEDC CASE: m m m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the shear whe	ere it cause conse2000 8 KN 8 KN 4	es shear failure at critical
γconcrete       WselFwt       (expesimental       /crit,D.L       /crit,LL       /u       Moint,D.L       Micrit,D.L       Micrit,D.L       Micrit,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,LL       Mu       BRL       Gotal Spans Length       widthy, w       eight, h	7.068 278 Force at Critical Section 0 278 278 ment at Critical Section, 25.76286 750.6 776.36285 100 SIMPLY SUPPOR Member Properties 5.4 0.3	KN/m KN LL and D.L KN KN KN.m KN.m KN.m KN.m KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the rule rule is the shear when the rule of the shea	ere it cause conse 2000 8 KN 8 KN 4 4 4 4 4 7 4 7 4 7 4 7 4 7 4 7 4 7 4 7 7 4 7 7 4 7 7 4 7 7 7 7 7 7 7 7 7 7 7 7 7	es shear failure at critical Control : M-Phi .4
Υconcrete       WselF-wt       (experimental       /crit,D.L       /crit,LL       /u       Moint,D.L       /u       Moint,D.L       /u       Moint,D.L       /u       Moint,D.L       /u       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,D.L       Moint,L.L       Mu       Fotal Spans Length       width, w       neight, h       xitical section from	7.068       278         278       278         Force at Critical Section       278         278       278         278       278         278       278         100       5.76286         776.36286       776.36286         100       SIMPLY SUPPOR         Member Properties       5.4         0.3       1	KN/m KN LL and D.L KN KN KN KN.m KN.m KN.m KN.m STEDC CASE: m m m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the rule rule is the shear when the rule of the shea	ere it cause conse2000 8 KN 8 KN 4	es shear failure at critical
Ycanarete WseFwit (experimental cert,D.L /orit,D.L /orit,LL /u Maint,D.L Adirt,LL /u Vu Stal Spans Length vidth, w leight, h ritical section from right support, L	7.068 278 278 Force at Critical Section 0 278 278 cont at Critical Section, 25.76286 776.36286 776.3628 100 SIMPLY SUPOR Member Properties 5.4 0.3 1 2.7	KN/m KN , LL and D.L KN KN KN LL and D.L KN.m KN.m KN.m KN.m KN.m KN.m KN.m	section of the mer Vresp2( Vexp Vexp/V	ntal is the shear when the rule rule is the shear when the rule of the shea	ere it cause conse 2000 8 KN 8 KN 4 4 4 4 4 7 4 7 4 7 4 7 4 7 4 7 4 7 4 7 7 4 7 7 4 7 7 4 7 7 7 7 7 7 7 7 7 7 7 7 7	es shear failure at critical Control : M-Phi .4
Ycanarete WseFwt (espekinnental Carit,D.L /arit,D.L /arit,LL /arit,LL /arit,D.L /arit,	7.068 278 278 Force at Critical Section 0 278 278 ment at Critical Section, 25.76286 776.36286 100 SIMPLY SUPPOR Member Propurties 5.4 0.3 1 2.7 23.56	KN/m KN KN KN KN KN KN KN KN KN.m KN.m KN.m	section of the mer	ntal is the shear when the respondence of the shear when the shear	ere it cause 50005e2000 8 KN 8 KN 4 4 4 1.0	es shear failure at critical Control : M-Phi .4
Yconcrete WseFwrt (experimental crit,D.L /crit,D.L /crit,LL /u Moirt,D.L /dirt,LL /u Moirt,D.L /dirt,LL /u /u /crit,D.L /crit,D.L /dirt,LL /u /u /crit,D.L /	7.068 278 278 Force at Critical Section 0 278 278 278 278 278 275.76286 750.6 776.3628  100 SIMPLY SUPPOR 100 SIMPLY SUPPOR 25.4 0.3 1 2.7 23.56 1 2.7 23.56 1 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	KN/m KN	section of the mer	ntal is the shear when the rule is the shear when the rule of the shear when the	ere it cause 50005e2000 8 KN 8 KN 4 4 4 1.0	es shear failure at critical Control : M-Phi .4
Ycanarete WseFwt (expetimental Shear 1 /orit,D.L /orit,D.L /orit,LL /orit,LL /orit,D.L	7.068 278 278 278 278 278 278 278 278 278 27	KN/m KN	Section of the mer	ntal is the shear when the rule is the shear when the rule of the shear when the	ere it cause 50005e2000 8 KN 8 KN 4 4 4 1.0	es shear failure at critical Control : M-Phi .4
Ycanarete       WseFwit       Yenpesimental       Yent,D.L       Yarit,LL       Yu       Maint,D.L       Maint,D.L       Maint,D.L       Maint,D.L       Maint,D.L       Maint,D.L       Maint,L.L       Mu       Status       Total Spans Length       width, w       reight, h       critical section from       right support, L       Yamental       Vereiswet       Vereiswetal       Shear       Varit,D.L	7.068       278         277       278         Force at Critical Section       278         0       278         278       278         1278       278         100       SIMPLY SUPOR         100       SIMPLY SUPOR         100       SIMPLY SUPOR         5.4       0.3         1       2.7         2.3.56       2.7         103       163         Force at Critical Section       0	KN/m KN	Section of the mer	ntal is the shear where the sh	ere it cause	es shear failure at critical Control : M-Phi .4
Ycanarete WseF-wt  (expeisimental  (expeisimental  (arit,D,L /arit,LL /a  Adirt,D,L /b	7.068     278       278     278       Force at Critical Section     0       278     278       278     278       278     278       278     776       25.76286     776.3628       776.36282     776.3628       100     SIMPLY SUPOR       Member Properties     5.4       5.4     0.3       1     1       2.7     23.56       7.068     163       Force at Critical Section       0     163	KN/m KN	Section of the mer	ntal is the shear when ber.	ere it cause	es shear failure at critical Control : M-Phi .4
Ycanarete WseFwt  (expesimental  (expesimental  (expesimental  (arit,D,L /u  (arit,LL /u  (arit,D,L /u  (arit,L,L /u  (arit,D,L /u )	7.068     278       278     278       Force at Critical Section     278       277     278       278     278       278     278       277     277       25.76286     776.3628       776.36287     776.3628       100     SIMPLY SUPPORT       5.4     0.3       2.7     23.56       2.7     23.56       7.068     163       Force at Critical Section     0       163     163	KN/m KN	Section of the mer	ntal is the shear where the sh	ere it cause	es shear failure at critical Control : M-Phi .4
Υconcrete         WseF-wt         Verit, D.L         Moint, D.L         Moint, D.L         Moint, D.L         Moint, D.L         Moint, L.L         Mu         Fotal Spans Length         width, w         neight, h         vitical section from         ritical section from         Verit, D.L	7.068     278       277     278       Force at Critical Section     0       278     278       278     278       278     278       278     278       278     278       278     278       278     278       278     278       278     278       776.36286     776.36286       776.36286     776.36286       100     SIMPLY SUPOR       Member Properties     5.4       5.4     0.3       1     2.7       2.3.56     163       Force at Critical Section     0       163     163       163     163	KN/m KN	Section of the mer	ntal is the shear wh nber. Resp 100 252 27 resp2000 1.09968 ol : V-Gxy 100 1.09968 100 1.	ere it cause	es shear failure at critical Control : M-Phi .4
Ycanarete  WseFwt  Verpeinmental  Verit,D.L  Varit,LL  Vu  Mairt,D.L  Mairt,D.L  Mairt,D.L  Mu  Fotal Spans Length width, w height, h  aritical section from right support, L  Yamerete  WseFwt Verpeinmental  Verit,D.L  Varit,D.L  Varit,D.L  Varit,D.L  Varit,D.L  Varit,D.L Vari	7.068     278       278     278       Force at Critical Section     278       277     278       278     278       278     278       277     277       25.76286     776.3628       776.36287     776.3628       100     SIMPLY SUPPORT       5.4     0.3       2.7     23.56       2.7     23.56       7.068     163       Force at Critical Section     0       163     163	KN/m KN	Section of the mer	ntal is the shear where the sh	ere it cause	es shear failure at critical Control : M-Phi .4

RM <sup>2</sup>	100 SIMPLY SUPPOR		Control : V-Gxy	Control : M-Phi
Divi.			317.5 874.	.9
	Member Properties			
fotal Spans Lengt	5.4 0.3	m		
width, w neight, h	1	m		
ritical section from				
right support, L	2.7	m	6.7	3.9
Yconcrete	23.56	KN/m <sup>3</sup>	1	
Wself-wt	7.068	KN/m		
/ <sub>expeirimental</sub>	342	KN	Note : Vexperimental is the shear where it ca	uses shear failure at critical
Shear F	orce at Critical Section	, LLand D.L	section of the member.	
erit,D.L	0	KN		
erit,LL	342	KN	Response200	00
/u	342	KN	Vresp2000 256.6 KN	
Mom	ent at Critical Section,	LL and D.L	Vexp 342 KN	
M <sub>cirt,D.L</sub>	25.76286	KN.m	Vexp/Vresp2000 1.332814	
M <sub>cirt.L.L</sub>	923.4	KN.m		
Mu	949.16286	KN.m		
BM1		RTEDC CASE:	Control : V-Gxy 308.8	Control : M-Phi
	Member Properties	5:		
Fotal Spans Length	5.4	m		
width, w	0.3	m		
neight, h	1	m		
ritical section from right support, L	2.7	m	7.6	3.8
Yconcrete	23.56	KN/m <sup>3</sup>		
W <sub>self-wt</sub>	7.068	KN/m		
/expeirimental	461	KN	Note : Vexperimental is the shear where it ca	uses shear failure at critical
Shear F	orce at Critical Section	, LLand D.L	section of the member.	
/ <sub>crit,D.L</sub>	0	KN		
	461	KN	Response200	00
/u	461	KN	Vresp2000 308.8 KN	
Mom	ent at Critical Section,	LL and D.L	Vexp 461 KN	
M <sub>cirt,D.L</sub>	25.76286	KN.m	Vexp/Vresp2000 1.492876	
M <sub>cirt,LL</sub>	1244.7	KN.m		

## (Continuous Beam)

SE1	00A-45 CONTINUOU	S CASE:	_	Control - M C	21012		Control	: M-Phi	
	Member Properties:		244.7	Control : V-C	×y	299.1			
otal Span lengths	9.2	m			$\sim$		_	$\sim$	
vidth, w	0.295	m			$\sim$				
eight, h	1	m							
ritical section from right support, L	1.19968	m							
Ycancrete	23.56	KN/m <sup>3</sup>			1.0				0.9
Wself-wt	6.9502	KN/m		1					1
speirimental	201	KN	Note: V	experimental is t	the shear w	he re it ca	uses shear	failure at cr	itical
Shear F	orce at Critical Section, L	L and D.L		of the member.					
:rit,D.L	23.63290406	KN	*Vresp2	2000=Vresp2000 <sub>A4</sub>	dual <sup>-V</sup> oritO.L				
crit,L.L	201	KN			Resp	onse 2000	)		
u	224.6329041	KN		Vresp2000	221.0671	KN			
Mom	ent at Critical Section, LL	and D.L		Vexp	201	KN	_		
Cirt, D.L.	33.35339783	KN.m		Vexp/Vresp20	0.909226		1		
A <sub>cirt,L.L</sub>	241.13568	KN.m							
Лu	274.4890778	KN.m							
SE1	.00B-45 солтілиои	S CASE:		Control M	C	[	C 1-	I. M DL	<u> </u>
	Member Properties:		285.2	Control : V-	GXY	346		ol:M-Ph	
otal Span lengths	9.2	m	2032			340			
vidth, w	0.295	m					/		
eight, h	1	m							
ritical section from right	1.19968	m	/						
support, L			/			/			
Ycancrete	23.56	KN/m <sup>3</sup>	L		0.	6			1.1
W <sub>self-wt</sub>	6.9502	KN/m				• •			
expeirimental	281	KN		experimental is to of the member.	the shear w	he re it ca	uses shear	ailure at cr	itical
	orce at Critical Section, L		section	or the member.					
crit,D.L	23.63290406	KN							
crit,L.L.	281	KN				onse 2000			
u Mom	304.6329041 ent at Critical Section, LL	KN		Vresp2000 Vexp	261.5671 281		-		
	33.35339783	KN.m		Vexp/Vresp20			-		
	22.2222202			vexp/viespzc	L 0/4294				
	222 44000								
cirt,L.L	337.11008	KN.m							
cirt,L.L	<b>337.11008</b> 370.4634778								
<b>fcirt,LL</b> 1u	370.4634778	KN.m KN.m							
<b>Acirt,LL</b> Nu		KN.m KN.m		Control : V	-Gxy		Со	ntrol : M	Phi
Acirt,LL Nu SE1	370.4634778	KN.m KN.m	280.		-Gxy	3	<u>Со</u> 10.4	ntrol : M	Phi
Acirt,LL Au SE1 Otal Span lengths	370.4634778 00A-83 continuou Member Properties: 9.2	KN.m KN.m S CASE: m	280.		-Gxy	3		ntrol : M	Phi
Acirt,LL Au SE1 otal Span lengths ridth, w	370.4634778 00A-83 continuou Member Properties: 9.2 0.295	KN.m KN.m IS CASE: m m	280.		-Gxy	3		ntrol : M	Phi
Acirt,LL Au SE1 Otal Span lengths ridth, w eight, h	370.4634778 00A-83 continuou Member Properties: 9.2	KN.m KN.m S CASE: m	280.		-Gxy	3		ntrol : M	Phi
Acirt,LL Mu SE1	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968	KN.m KN.m SCASE: m m m m	280.		-Gxy	3		ntrol : M	Phi
Acirt,LL Au SE1 otal Span lengths <i>r</i> idth, w eight, h	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56	KN.m KN.m IS CASE: m m m m KN/m <sup>3</sup>	280.			.8		ntrol : M	
kirt,LL Iu Dtal Span lengths idth, w eight, h itical section from right support, L	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502	KN.m KN.m IS CASE: m m m m KN/m <sup>3</sup> KN/m		1		).8	40.4		0.9
irt,LL J SE1 Span lengths dth, w ight, h tical section from right support, L Yanacte Wsaffwt	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m	Note: V	1 ////////////////////////////////////		).8	40.4		0.9
teir,LL U SE1 Stal Span lengths idth, w sight, h titical section from right support, L Yconcete Wsoffwet speinnostal Shear F	370.4634778 00A-83 CONTINUOU Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L	KN.m KN.m SCASE: m m m KN/m <sup>3</sup> KN/m KN/m KN	Note: V	1		).8	40.4		0.9
Acirt,LL Au SE1 Stal Span lengths ridth, w eight, h itical section from right support, L Yconcete Wsdi wt capcimotal Shear F	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m	Note: V	1 ////////////////////////////////////		).8	40.4		0.9
Acirt,LL Au SE1 Stal Span lengths ridth, w eight, h itical section from right support, L Yanacete W <sub>safi wt</sub> capatimental Shear F crit,D.L crit,LL	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L 23.63290406 303	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m KN/m KN/m KN/m	Note: V	1 Pexperimental is to of the member.	the shear w	).8 here it ca	10.4		0.9
kirt,LL lu SE1 Stal Span lengths ridth, w eight, h itical section from right support, L Ycancete Wselfwet capcininestal Shear F crit,D.L crit,LL	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L 23.63290406 303 326.6329041	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m KN/m KN KN	Note: V	1 Texperimental is to of the member. Vresp2000	the shear w Resp 256.3671	0.8 here it ca ponse 2000 KN	10.4		0.9
Acirt,LL Au SE1 Stal Span lengths ridth, w eight, h ritical section from right support, L Ycancete Wsafiwt 'capcimental Shear F crit,D.L crit,LL U Mom	370.4634778 00A-83 CONTINUOU Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L 326.6329040 ent at Critical Section, LL	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m KN/m KN KN KN KN KN KN KN KN KN KN	Note: V	1 Texperimental is to of the member. Vresp2000 Vexp	( the shear w 256.3671 303	0.8 here it ca ponse 2000 KN	10.4		0.9
Acirt,LL Au SE1 Stal Span lengths ridth, w eight, h ritical section from right support, L Yconcete Wsdf-wt Yconcete Shear F (erit,D.L frit,LL fu Mom Acirt,DL	370.4634778 00A-83 continuou Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L 23.63290405 303 326.6329041 ent at Critical Section, LL 33.35339783	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m KN/m KN/m KN/m KN KN KN KN KN KN KN KN KN KN KN KN KN	Note: V	1 Texperimental is to of the member. Vresp2000	( the shear w 256.3671 303	0.8 here it ca ponse 2000 KN	10.4		0.9
Acirt,LL Au SE1 Stal Span lengths ridth, w eight, h ritical section from right support, L Yconcete Wsdfwt (entitle Shear F (erit,D.L (erit,LL (u) Mom	370.4634778 00A-83 CONTINUOU Member Properties: 9.2 0.295 1 1.19968 23.56 6.9502 303 orce at Critical Section, L 326.6329040 ent at Critical Section, LL	KN.m KN.m SCASE: m m m m KN/m <sup>3</sup> KN/m KN/m KN KN KN KN KN KN KN KN KN KN	Note: V	1 Texperimental is to of the member. Vresp2000 Vexp	( the shear w 256.3671 303	0.8 here it ca ponse 2000 KN	10.4		0.9

SE10	00B-83 солтілиои	S CASE:	Control : V-Gxy		Control : M-Phi
	Member Properties:		320.8	388.6	
Fotal Span lengths	9.2	m			
width, w	0.295	m			
height, h	1	m	/		
ritical section from right support, L	1.19968	m			
Yconcrete	23.56	KN/m <sup>3</sup>		0.5	1.1
W <sub>self-wt</sub>	6.9502	KN/m	L	V	
experimental	365	KN	Note : Vexperimental is the	shear where it cau	ses shear failure at critical
	orce at Critical Section, L.	L and D.L	section of the member.		
/ <sub>crit,D.L</sub>	23.63290406	KN			
/crit,LL	365	KN		Response 2000	
/u	388.6329041	KN		97.1671 KN	
	ent at Critical Section, LL		Vexp	365 KN	
M <sub>cirt,D.L</sub>	33.35339783	KN.m	Vexp/Vresp200	L.228265	
M <sub>cirt,LL</sub>	437.8832	KN.m			
Mu	471.2365978	KN.m			
SE100	DA-M-69 CONTINUC	OUS CASE:	Control : V-Gx	/	Control : M-Phi
	Member Properties:		545.2	658.5	
otal Span lengths	9.2	m			
vidth, w	0.295	m			
neight, h	1	m	———————————————————————————————————————		· · · · ·
itical section from right support, L	1.19968	m	(		
Yconcrete	23.56	KN/m <sup>3</sup>		7.8	2.9
W <sub>selF-wt</sub>	6.9502	KN/m		i   '	
expeirimental	516	KN	Note : Vexperimental is the	shear where it cau:	ses shear failure at critical
	orce at Critical Section, L.		section of the member.		
crit,D.L	23.63290406	KN			
arit,LL	516	KN		Response 2000	
/u	539.6329041	KN		521.5671 KN	
	ent at Critical Section, LL		Vexp	516 KN	
M <sub>cirt,D.L</sub>	33.35339783	KN.m	Vexp/Vresp200	).989326	
M <sub>cirt,LL</sub>	619.03488	KN.m			
Лu	652.3882778	KN.m			
SE10	B-M-69 course				
SE100B-M-69 CONTINUOUS CASE:		Control : V-G		Control : M-Phi	
otal Span Jonatha	Member Properties: 9.2	-	661.2	797	<b>.</b> 9
otal Span lengths vidth, w	0.295	m m			
neight, h	1	 m			
ritical section from right	1 10069				
support, L	1.19968	m			
Yconcrete	23.56	KN/m <sup>3</sup>		9.7	3.0
WselFwt	6.9502	KN/m	L		1
experimental	583	KN	Note : Vexperimental is the	shear where it cau	ses shear failure at critical
Shear Fo	orce at Critical Section, L	L and D.L	section of the member.		
crit,D.L	23.63290406	KN			
/ <sub>crit,LL</sub>	583	KN		Response 2000	
/u	606.6329041	KN		537.5671 KN	
Mome	ent at Critical Section, LL	and D.L	Vexp	583 KN	
M <sub>cirt,D.L</sub>	33.35339783	KN.m	Vexp/Vresp200	) <mark>.914414</mark>	
	33.35339783 699.41344	KN.m KN.m	Vexp/Vresp200(	).914414	

# Appendix C - Solved Examples using the Developed MathCAD Design Tool

### Example 1:

This example calculates the shear / Torsion reinforcement for a section of the pre-stressed girder shown in Figure C. 1. Geometry and reinforcement arrangement is shown in Figure C. 2.





Figure C. 1 the girder used in this example, and a cross section of the bridge

The cross-section geometry and reinforcement is as follows:

Girder height	=72 in.
$f_c$ of the girder concrete	=8000 psi
Deck thickness	=7.5 in.
Deck thickness on the girder flange	=8 in.
$f_c$ of the Deck concrete	=4000 psi
Total height (including the Deck part)	=80 in.
Effective width (b <sub>eff</sub> )	=98 in.
Width of the web	=8 in.






Figure C. 2 Beam cross section showing general geometry and reinforcement

Demanded shear and moment values at various locations along the beam are shown in Figure C. **3**. These values have been evaluated using the AASHTO loading standards and the envelope is provided at tenth points. Note that there was no torsion in this bridge, which was selected as a sample to be used to test the program. However, for demonstration purpose, various levels of torsion will be considered to check the program performance.




Figure C. 3 Demanded shear and moment values at various locations along the beam

#### **Preparing the input data:**

Before calculating the required input data, it should be noted that the values of the input data for various parameters depend on factors that are beyond the scope of this project. So, it is assumed that for each case, the user, will calculate the necessary values and provides them as the input data. The "designed" shear and torsion reinforcement depends on the accuracy of the input data.

On the other hand, depending of the case (girder geometry, demanded load level, reinforcement arrangement, and location of the section) the Strut-and-Tie Model should be used in lieu of the process implemented the program. Decrease in pre-stressing force based on the bonding situation is another factor that needs to be addressed by the user.

### Section:

The section located at a distance equal to 20% of the girder length (span) is selected for design in this example. The distance between the supports, center to center, is equal to 103 feet. So, the distance between the support and the center of the span, is 51' 6".

The demanded values at this section, located at 0.2\*103'=20'7.2'' from the support are:  $M_u=6864$  kip-ft

V<sub>u</sub>=293 kips N<sub>u</sub>=0.0 kips T<sub>u</sub>=988 kip-in

The profile of the pre-stressing strands is shown in Figure C. **1**. The slope of the prestressing strands starts at a distance 34' 4" (34.33') away from the support, where the centroid of the pr-stressing strands is located at a height of 7.33" from the lower edge of the section. This centroid is at a height of 14.92" on the support. So, the tangent of the angle of the pre-stressing force and the horizontal direction will be:

$$\tan \gamma = \frac{14.92 - 7.33}{34.33 \times 12} = 0.0184$$
 (Eq. C. 1)

Therefore

$$\tan \alpha_p = \frac{1}{0.0184} = 54.34 \tag{Eq. C. 2}$$

So, the angle:

$$\alpha_p = 88.95 \, deg \tag{Eq. C. 3}$$

Note that design of the girder includes flexural design as well, and it is, in turn, related to the shear/torsion. As example, the amount of longitudinal reinforcement comes not only from flexure but also the amount needed for torsion. Following, shows the brief calculations for evaluation of the flexural strength at the mid-span, as compared to the demanded value.




Figure C. 4 Calculation of the flexural strength at the mid-span

Area of the pre-stressing steel on the tensile side of the section:

Number of strands: 54

Area of each strand:  $0.153 \text{ in}^2$ 

$$A_{ps}=54\times0.153 \text{ in}^2=8.262 \text{ in}^2$$

 $A_s=0.0 \text{ in}^2$  (Area of regular steel)

The length of the outside perimeter of the concrete section

 $P_{c}=2\times(14+8+\sqrt{2\times 64}+44+\sqrt{2\times 64}+\sqrt{9+13^{2}}+5+21)$ 

$$P_c=249.31$$
 in or  $P_c=250$  in

Perimeter of the centerline of the closed transverse torsion reinforcement (in.)

$$P_h=2\times(76+5)$$
  $P_h=162$  in

Total area enclosed by outside perimeter of concrete cross-section (in2):

$$A_{cp}=2\times((5+8)\times\frac{13}{2}+(8+12)\times\frac{4}{2}+4\times72+)+(8+16)\times\frac{10}{2}$$
$$A_{cp}=1065 \text{ in}^2 \quad A_{ct}=580 \text{ in}^2$$

Width of web adjusted for the presence of ducts (in.); width of the interface (in.)

$$b_v=8$$
 in.  $b_w=8$  in.




Figure C. 5 Calculating the section properties at 0.2L

Area enclosed by the shear flow path, including any area of holes therein (in2)

 $A_o=5\times76$   $A_o=380$  in<sup>2</sup>

Distance from extreme compression fiber to the centroid of the pre-stressing tendons (in.):  $d_p=80-10.73$   $d_p=69.6$  in.

## Example-1 MathCAD Solution:

#### LRFD Shear and Torsion, using Sectional Model (SECTION 5, Interim 2008, Revised based on 2010)

# IMPORTANT to Note: changing the unit system will lead to inaccuracy of the results, since most of the factors are based on teh US system

**Example 1** (Please see the WORD File for detailed information)

1) Please see the WORD file for graphical definition of the parameters.

2) The **PDF file with links** can help you with jumping to a desired location

 $\beta$ ) Some parameters such as  $A_0$ ,  $P_h$ , etc., need to be evaluated beforehand due to possible

irregularities associated with various sections. Also, demanded loads are closely related to the bridge configuration and related load combination. This file, ONLY addresses shear/torsion part of design.

If the distance between zero-shear point and the face of support is less than 2d (d is the distance between the compression side and centriod of tensile reniforcement) OR a concentrated load causing more than 1/2 of the shear at a support is closer than 2d from the face of support, this method is not applicable. You need to use Stut-and-Tie Model (Section 5.6.3). IN GENATRAL: Where the "plane sections assumption of felxural theory" is NOT valid, strut-and-Tie Model should be used.

#### Enter your data in the highlighted (yellow) fields

### INPUT DATA:

#### Section Geometry:

h := 80in	Overall section depth (in)
$h_{nc} \approx 75in$	Depth of the non-composite section (in)
$A_{cp} \coloneqq 1160in^2$	total area enclosed by outside perimeter of concrete cross-section (in <sup>2</sup> ). Having the section, this value needs to be calculated
p <sub>c</sub> := 220in	the length of the outside perimeter of the concrete section (in.). Having the section, this value needs to be calculated
$A_0 := 380 in^2$	area enclosed by the shear flow path, including any area of holes therein (in <sup>2</sup> ). Having the section, this value needs to be calculated
$p_h := 162in$	perimeter of the centerline of the closed transverse torsion reinforcement (in.). Having the section, this value needs to be calculated
$b_V := 8in$	width of web adjusted for the presence of ducts (in.); width of the interface (in.)
	OR: effective web width taken as the minimum web width, measured parallel to the neutral axis, between the resultants of the tensile and compressive forces due to flexure, or for circular sections, the diameter of the section, modified for the presence of ducts where applicable (in )

$b_{W} := 8 in$	width of web (in.)
$d_s := 72in$	distance from extreme compression fiber to the centroid of the nonprestressed tensile reinforcement (in.)
d <sub>p</sub> := 69in	distance from extreme compression fiber to the centroid of the prestressing tendons (in.)
SecType := "	Solid" Type of the cross section to design
$d_t := 74in$ $c_{comp} := 20i$	distance from extreme compression fiber to the centroid of the extreme tensile reinforcement on teh section (it is different from d <sub>s</sub> ) Depth of the compression zone (you need to calculate it depending on the geometry of the section, amount of the reinforcement on tensile and compression side and material properties)

The section will be specified depending on the input data for regular and/or prestressing steel to check if the girder is nonprestressed, prestressed, or partially prestressed.

### Reinforcement:

$A_{s} := 0.0 in^{2}$	area of the non-prestressing tensile reinforcement on the section
E <sub>s</sub> := 29000ksi	modulus of elasticity of reinforcing bars (ksi)
$A_{ps} := 8.262 in^2$	area of the pre-stressing steel on tensile side of the member as in Fig 1 (Word) file or PDF file page 5-73
$A_b := 0.31 in^2$	area of the cross section of the lateral reinforcement (here #5, change accordingly)
$n_{leg} := 2$	Number of the legs of the lateral reinforcement
$A_v := A_b \cdot n_{leg}$	Area of the shear reinforcement (used for torsion as well)
HasMin := "yes	" Put "Yes" if section Contains minimum or more lateral reinforcement
Material Prope	r <u>ties:</u>
ConType := "No	ormal" put one of the: "Normal", "AllLightweight", "SandLightweight"
f <sub>c</sub> := 6ksi	compressive stregth of concrete
f <sub>y</sub> := 60ksi	yield strength of the non-prestressing tensile steel
f <sub>py</sub> := 60ksi	yield strength of prestressing steel (ksi)
f <sub>pc</sub> := 1ksi	( <b>can be calculated</b> ) compressive stress in concrete after prestress losses have occurred either at the centroid of the cross-section resisting transient loads or at the junction of the web and flange where the centroid lies in the flange (ksi)

f <sub>pu</sub> := 270ksi	specified tensile strength of prestressing steel (ksi)
$f_{ltl} := 32ksi$	Assumed value for long-term losses of prestressing steel (ksi)
$f_{pi} := 0.7 \cdot f_{pu}$	You may change the value if there are explicit information
$f_{pi} = 189 \cdot ksi$ $E_p := 28600ksi$	Modulus of elasticity of prestressing tendons (ksi)
f <sub>ct_specified</sub> :=	"No"
f <sub>ct</sub> := 0.2ksi	(If you have a lightweight concrete, put "Yes" if $f_{ct}$ available and enter the value, otherwise, put "No" and ignore $f_{ct}$ ) average splitting tensile strength of lightweight concrete
$\alpha_p := 88.95 \deg$	This is the angle between the prestressing force and postive direction of shear force (demand).
a <sub>g</sub> := 0.25in	maximum aggregate size
$\alpha := 90 \text{deg}$	angle of inclination of transverse reinforcement to longitudinal axis (°)
$K_1 \coloneqq 1.0$	correction factor for source of aggregate to be taken as 1.0 unless determined by physical test, and as approved by the authority of jurisdiction (see <u><b>5.4.2.4</b></u> )
$w_c := 0.145 \frac{kip}{ft^3}$	unit weight of concrete (kcf); refer to <u>Table 3.5.1-1</u> or <u>Article C5.4.2.4</u>
2	$A_{ct}$ is the area of concrete on the flexural tension side of the member as
$A_{ct} := 580 \text{in}^2$	shown in Figure 1 (in. <sup>2</sup> ). It is calculated as teh area bellow the centroid of the non-composite section. It can also be calculated as the area of the non-composite section, divided by the height of the non-composite section, then multiplied by half of the overall height of the section.
<sup>s</sup> CrackControl <sup>:=</sup>	= $2in$ maximum distance between layers of longitudinal crack control reinforcement, where the area of the reinforcement in each layer is not less than $0.003b_v s_x$ , as shown in Figure 3 (in.)

### Demanded Shear and Torsion, Moment, Axial Force:

The induced internal shear and torsion in the section by the applied factored loads

 $V_u := 293 \text{kip}$   $T_u := 988 \text{kip} \cdot \text{in}$   $M_u := 82368 \text{kip} \cdot \text{in}$   $N_u := 0 \text{kip}$  positive is tensile

# Calculations and Design:

average stress in prestressing steel at the time for which the nominal resistance of member is required (ksi)

$$\mathbf{f}_{\mathbf{ps}} := \mathbf{f}_{\mathbf{pi}} - \mathbf{f}_{\mathbf{ltl}}$$
 $\mathbf{f}_{\mathbf{ps}} = 157 \cdot \mathbf{ksi}$ 

 $V_p$  is the component in the direction of the applied shear of the effective prestressing force; positive if resisting the applied shear (kip) (C5.8.2.3) (can be calculated if the angle is known)

$$\begin{split} V_{p} &\coloneqq A_{ps} \cdot f_{ps} \cdot \cos(\alpha_{p}) \\ V_{p} &= 23.77 \cdot \text{kip} \\ E_{c} &\coloneqq 33000 \text{K}_{1} \cdot \text{w}_{c}^{1.5} \cdot \left(\frac{\text{ft}^{3}}{\text{kip}}\right)^{1.5} \cdot \sqrt{f_{c} \cdot \text{ksi}} \\ E_{c} &= 4.463 \times 10^{3} \cdot \text{ksi} \end{split} \qquad \text{Modulus of elasticity of concrete (ksi) (5.4.2.4)} \\ \\ PPR &\coloneqq \frac{A_{ps} \cdot f_{py}}{A_{ns} \cdot f_{ny} + A_{s} \cdot f_{y}} \end{split}$$

The string variable "Prestress" shows the prestressing condition of the section.

#### Evaluation of strength reduction factors $\phi$ , for flexure, shear, and torsion:

The following algorithm addresses Article 4.5.4.2.1, and Equations 5.5.4.2.1-1 and 5.5.4.2.1-2

(See: Article 5.5.4.2), p 5-25

▼


$$\varepsilon_{\mathbf{y}} \coloneqq \frac{\mathbf{f}_{\mathbf{y}}}{\mathbf{E}_{\mathbf{s}}} \qquad \varepsilon_{\mathbf{y}} = 2.069 \times 10^{-3}$$

ebsY := 
$$\varepsilon_y$$
 if PreStress = "Nonprestressed"  
0.002 otherwise ebsY = 2 × 10<sup>-3</sup>

Evaluation of the flexural strength reduction factor:


 $phiT := 0.9 + 0.1 \cdot PPR$  phiT = 1 This temporal variable is for implementation of prestressing condition (normal, partial, or full)

C5.5.4.2.1 states that "For sections subjected to axial load with flexure, factored resistances are determined by multiplying both  $P_n$  and  $M_n$  by the appropriate single value of  $\phi$ 



 $\phi_f = 1$   $\phi_c := \phi_f$  As per C5.5.4.2.1


Evaluation of the shear and torsional strength reduction factors based on 5.5.4.2



Calculating the value of d<sub>v</sub>:

effective shear depth taken as the distance, measured perpendicular to the neutral axis, between the resultants of the tensile and compressive forces due to flexure; it need not be taken to be less than the greater of  $0.9 d_e$  or 0.72h (in.)

To calculate  $d_v$ , using the commentary C5.8.2.9-1, assuming  $M_n = M_u/\phi$ , we have:



$$d_{V} := \max(0.9d_{e}, 0.72 \cdot h, d_{V1})$$

(Art. 5.8.2.9)  $d_v = 63.5 \cdot in$ 

Calculate the Shear Stress:

$$\mathbf{v}_{\mathbf{u}} := \frac{\begin{vmatrix} \mathbf{v}_{\mathbf{u}} - \mathbf{\phi}_{\mathbf{v}} \cdot \mathbf{v}_{\mathbf{p}} \end{vmatrix}}{\mathbf{\phi}_{\mathbf{v}} \cdot \mathbf{b}_{\mathbf{v}} \cdot \mathbf{d}_{\mathbf{v}}}$$
 (Eq 5.8.2.9-1)  
AASHTO 2010  
$$\mathbf{v}_{\mathbf{u}} = 0.594 \cdot \mathbf{ks}_{\mathbf{s}}$$
 Note that this should be  $\mathbf{v}_{\mathbf{n}}$  (equivalent to  $\mathbf{v}_{\mathbf{u}}/\mathbf{\phi}$   
and not  $\mathbf{v}_{\mathbf{u}}$  or we need to remove the strength  
reduction fator. It is the same in 2010 as well.

Calculating S<sub>max</sub> (maximum permissible spacing of lateral reinforcement) considering the demanded shear stress *(Eqs. 5.8.2.7-1 and 5.8.2.7-2)* will be done when the shear reinorcement, if needed, is designed

Following is evaluation of the  $A_{cp}^{2}/p_{c}$  so that we address a cellular case, per 5.8.2.1-5

Val := 
$$\frac{A_{cp}^{2}}{p_{c}}$$
 if SecType = "Solid"  
otherwise  
 $\frac{A_{cp}^{2}}{p_{c}}$  if  $\left(\frac{A_{cp}^{2}}{p_{c}}\right) \le 2A_{o} \cdot b_{v}$   
 $2A_{o} \cdot b_{v}$  otherwise

(Equation 5.8.2.1-4)

(Equation 5.8.2.1-5)


$$T_{cr} := \begin{array}{l} 0.125 \cdot \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \sqrt{f_c \cdot ksi}}} & \text{if ConType = "Normal"} \\ \text{otherwise} \\ 0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi}) \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi})}} & \text{if } f_{ct\_specified} = "Yes" \\ \text{otherwise} \\ 0.125 \cdot 0.75 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.75 \sqrt{f_c \cdot ksi}}} & \text{if ConType = "AllLightweight"} \\ 0.125 \cdot 0.85 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.85 \sqrt{f_c \cdot ksi}}} & \text{otherwise} \\ \end{array}$$

Check if the torsion can be ignored:

IgnoreTorsion := "Yes" if 
$$T_u \le 0.25 \cdot \phi_t \cdot T_{cr}$$
 (Equation 5.8.2.1-3)  
"No" otherwise  
IgnoreTorsion = "No"

Calculating the demanded equivalent shear force:

Note that here, since the equivalent shear can be used for checking the section, we have to use the T<sub>u</sub> regardless of being less that 0.25 times the cracking torsion or not.



This equivalent V<sub>u\_eq</sub> is just for checking the adequecy of the section, when needed, otherwise the shear and torsional steel need to be evaluated as needed and then added up (shear as per 5.8.3.3 and Torsion as per 5.8.3.6.2)

Calculating the shear strength provided by concrete, V<sub>c</sub>:



a parameter taken as modulus of elasticity of prestressing tendons multiplied by the lockedin difference in strain between the prestressing tendons and the surrounding concrete (ksi). For the usual levels of prestressing, a value of **0.7**  $f_{pu}$  will be appropriate for both pretensioned and post-tensioned members

# Calculating *ɛ*<sub>s</sub> using equation **5.8.3.4.2-4**

**IMPORTANT Note**: Deduct a portion of the area of the bars and tendons terminated less than their development length from the section that you are designing for, with the same proportion as their lack of full length (Here, the development length of a bar can be evaluated, and then having the actual length, the area can be reduced proportional to the ratio of available length to development length.

Addressing the requirement to have  $M_u$  used not to be less than  $(V_u - V_p)d_v$ , we use  $M_{u1}$  as follows:

$$M_{u1} := \begin{bmatrix} M_u & \text{if } |M_u| \ge |(V_u - V_p) \cdot d_v| \\ (V_u - V_p) \cdot d_v & \text{otherwise} \end{bmatrix}$$
$$M_{u1} = 8.237 \times 10^4 \cdot \text{kip} \cdot \text{in}$$

(Article 5.8.3.4.2)

<u>Note</u> that 1)  $A_s$  and  $A_{ps}$  should be reduced proportionally if a lack of full development length to the section under design 2) If closer than  $d_v$  to the face of support, use  $\varepsilon_s$  at distance  $d_v$  to evaluate  $\beta$  and  $\theta$ 

$$\varepsilon_{s1} \coloneqq \frac{\begin{vmatrix} M_{u1} \\ d_{v} \end{vmatrix} + 0.5N_{u} + \begin{vmatrix} V_{u} - V_{p} \end{vmatrix} - A_{ps} \cdot f_{po}}{E_{s} \cdot A_{s} + E_{p} \cdot A_{ps}}$$
(Equation 5.8.3.4.2-4)  
$$\varepsilon_{s1} = 2.051 \times 10^{-5}$$

(Article 5.8.3.4.2) <u>Page 5-72 (2008), Page 5-71 (2010)</u>

$$\varepsilon_{s2} \coloneqq \left| \frac{\left| \frac{M_{u1}}{d_{v}} + 0.5N_{u} + \left| V_{u} - V_{p} \right| - A_{ps} \cdot f_{po}}{E_{s} \cdot A_{s} + E_{p} \cdot A_{ps} + E_{c} \cdot A_{ct}} \right| \text{ if } \varepsilon_{s1} < 0.0$$

This and the follwing are evaluates  $\varepsilon_s$ , presisely and does not use zero.

$$\varepsilon_{s2} = 2.051 \times 10^{-5}$$


For pretensioned members,  $f_{po}$  can be taken as the stress in the strands when the concrete is cast around them, i.e., approximately equal to the jacking stress. For post-tensioned members,  $f_{po}$  can be conservatively taken as the average stress in the tendons when the posttensioning is completed.

#### NOTE

For sections closer than  $d_y$  to the face of support the value for  $\epsilon_s$  calculated at  $d_y$  from the face of support may be used to evaluate  $\beta$  and  $\theta$ 

If the axial tension is large enough to crack the flexural compression face of the section, the value calculated should be doubled.

$$s_x := \min(d_v, s_{CrackControl})$$
 Reinforcement in each layer not less than  $0.003b_v s_x$   
 $s_x = 2 \cdot in$ 



Designing the transverse reinforcement for <u>SHEAR</u> (Note that the  $A_v/s$  will be evaluated. Then when we have Torsion as well, we can add them appropriately depending on the type of section)

Check if we need shear reinforcement per 5.8.2.4-1

NeedShear := "Yes" if 
$$V_u > 0.5 \cdot \phi_v \cdot (V_c + V_p)$$
  
"No" otherwise (Equation 5.8.2.4-1)  
NeedShear = "Yes"

Here we need to check for mininum reinforcement as per 5.8.2.5 (AASHTO 2010)

$$s_{req} \coloneqq if \left[ V_{s} \le 0, s_{max}, \frac{A_{V} \cdot f_{y} \cdot d_{V} \cdot (\cot(\theta) + \cot(\alpha)) \cdot \sin(\alpha)}{V_{s}} \right]$$

$$s_{req} = 36.66 \cdot in$$

$$s_{W} \coloneqq \min(s_{max}, s_{req})$$

$$s = 36.66 \cdot in$$

Based on **5.8.2.7** and **5.8.2.9**, we need to evaluate the final spacing by finding the othe maximum limits as follows:

$$s_{max2} := if(v_u < 0.125 \cdot f_c, min(0.8 \cdot d_v, 24in), min(0.4 \cdot d_v, 12in))$$
 (Eqs. 5.8.2.7-1 and 5.8.2.7-2)  
 $s_{max2} = 24 \cdot in$ 

The spacing of the transversal reinforcement is as follows:

$$s_{actual} := min(s, s_{max2})$$

 $s_{actual} = 24 \cdot in$ 

To address 5.8.3.3-2, The upper limit of  $V_n$ , given by Eq. 2, is intended to ensure that the concrete in the web of the beam will not crush prior to yield of the transverse reinforcement.

$$0.25 \cdot f_{c} \cdot b_{V} \cdot d_{V} = 762 \cdot kip$$

Note that  $V_u/\phi$  -Vp should be less than 0.25  $f_c b_v d_v$  otherwise section is not enough and concrete crushes due to local shear demand.

Check if the section is enough:

SecEnough := "Yes" if 
$$\frac{V_u}{\phi_V} - V_p < 0.25 \cdot f_c \cdot b_V \cdot d_V$$
 (Equation 5.8.3.3-2)  
"STOP and Change Section" otherwise  
SecEnough = "Yes"

Also we need to specify where we have to switch to strut-and-tie model Note :  $V_p$  is the vertical component of the prestressing force (as has already been evaluated by using the angle  $\alpha_p$ )

*Finding the ratio of avss=A*,/*s for shear:* 

avss :=  $\frac{A_V}{s_{actual}}$ 

 $avss = 0.026 \cdot in$ 

#### Design for Torsional lateral reinforcement:

Note that if we have a torsion that cannot be ignored, we design the lateral reinforcement for that and we call that avst. later we add the shear and torsion reinforcement properly. Corresponding longitudinal steel will be calculated as well.

avst1 := 
$$\frac{\frac{T_u}{\phi_t}}{2 \cdot A_0 \cdot f_y \cdot \cot(\theta)}$$
 if IgnoreTorsion = "No"  
0.0 otherwise

(Equation 5.8.3.6.2-1)

 $avst1 = 0.013 \cdot in$  This is for one leg

 $avst := 2 \cdot avst1$   $avst = 0.027 \cdot in$ 

avs := avss + avst This is the total lateral reinforcement needed for shear and torsion

 $s_{\text{ShearTorsion}} \coloneqq \text{floor}\left(\frac{A_{V}}{avs \cdot in}\right) \cdot in$ 

 $s_{\text{ShearTorsion}} = 11 \cdot \text{in}$ 

Design for Torsional longitudinal reinforcement: (Article 5.8.3.6.3 Longitudinal Reinforcement) [Also consider Eq. 5.8.3.5-1]

$$tmpVal := \frac{\left| M_{u1} \right|}{\phi_{f} \cdot d_{v}} + \frac{0.5 \cdot N_{u}}{\phi_{c}} + \cot(\theta) \cdot \sqrt{\left( \left| \frac{V_{u}}{\phi_{v}} - V_{p} \right| - 0.5 \cdot V_{s} \right)^{2} + \left( \frac{0.45 \cdot p_{h} \cdot T_{u}}{2 \cdot A_{o} \cdot \phi_{t}} \right)^{2}}$$

 $tmpVal = 1.775 \times 10^3 \cdot kip$ 

$$A_{l} := 0.0 \text{ if IgnoreTorsion} = "Yes" \\ \text{otherwise} \\ \text{if SecType} = "Solid" \\ \hline 0.0 \text{ if } A_{ps} \cdot f_{ps} + A_{s} \cdot f_{y} \ge tmpVal \\ \hline \frac{1}{mpVal - A_{ps} \cdot f_{ps}}{f_{y}} - A_{s} \text{ otherwise} \\ \hline \frac{T_{u} \cdot p_{h}}{\phi_{t} \cdot 2 \cdot A_{o} \cdot f_{y}} \text{ otherwise} \\ \hline Eq. 5.8.3.6.3-2 \\ \hline eq. 5.8.3.6.3.6.3.6.3.72 \\ \hline eq. 5.$$

 $A_{l} = 7.962 \cdot in^{2}$  $A_{s\_total} := A_{s} + A_{l}$ 

Note that distribution of  $\mathbf{A}_{\mathbf{I}}$  should be evenly around the section

 $A_{s\_total} = 7.962 \cdot ir$ 

# Example-2 Solution using the Developed MathCAD Design Program

# Example-2 MathCAD Solution:

#### LRFD Shear and Torsion, using Sectional Model (SECTION 5, Interim 2008, Revised based on 2010)

IMPORTANT to Note: changing the unit system will lead to inaccuracy of the results, since most of the factors are based on teh US system

Example 2 (Using some numbers for an assumed section to check the functionality)

1) Please see the WORD file for graphical definition of the parameters.

2) The **PDF file with links** can help you with jumping to a desired location

 $\beta$ ) Some parameters such as  $A_0$ ,  $P_h$ , etc., need to be evaluated beforehand due to possible

irregularities associated with various sections. Also, demanded loads are closely related to the bridge configuration and related load combination. This file, ONLY addresses shear/torsion part of design.

If the distance between zero-shear point and the face of support is less than 2d (d is the distance between the compression side and centriod of tensile reniforcement) OR a concentrated load causing more than 1/2 of the shear at a support is closer than 2d from the face of support, this method is not applicable. You need to use Stut-and-Tie Model (Section 5.6.3). IN GENATRAL: Where the "plane sections assumption of felxural theory" is NOT valid, strut-and-Tie Model should be used.

# Enter your data in the highlighted (yellow) fields

# INPUT DATA:

### Section Geometry:

h := 54in	Overall section depth (in)
$h_{nc} := 54in$	Depth of the non-composite section (in)
$A_{cp} := (2923in)^2$	total area enclosed by outside perimeter of concrete cross-section (in <sup>2</sup> ). Having the section, this value needs to be calculated
p <sub>c</sub> := 216in	the length of the outside perimeter of the concrete section (in.). Having the section, this value needs to be calculated
$A_0 := 360 \text{in}^2$	area enclosed by the shear flow path, including any area of holes therein (in <sup>2</sup> ). Having the section, this value needs to be calculated
$p_h := 312in$	perimeter of the centerline of the closed transverse torsion reinforcement (in.). Having the section, this value needs to be calculated
$\mathbf{b}_{\mathbf{V}} := 8$ in	width of web adjusted for the presence of ducts (in.); width of the interface (in.)
	OR: effective web width taken as the minimum web width, measured parallel to the neutral axis, between the resultants of the tensile and compressive forces due to flexure, or for circular sections, the diameter of the section, modified for the presence of ducts where applicable (in.)

$d_s := 50in$ distance from extreme compression fiber to the centroid of the nonprestressed tensile reinforcement (in.)
$d_p := 47in$ distance from extreme compression fiber to the centroid of the prestressing tendons (in.)
SecType := "Solid" Type of the cross section to design
dt := 52indistance from extreme compression fiber to the centroid of the extreme tensile reinforcement on teh section (it is different from ds)ccomp := 14inDepth of the compression zone (you need to calculate it depending on the geometry of the section, amount of the reinforcement on tensile and compression side and material properties)
The section will be specified depending on the input data for regular and/or prestressing steel to check if the girder is nonprestressed, prestressed, or partially prestressed.
<u>Reinforcement:</u>
$A_s := 012.7 in^2$ area of the non-prestressing tensile reinforcement on the section
E <sub>s</sub> := 29000ksi modulus of elasticity of reinforcing bars (ksi)
$A_{ps} := 5.5in^2$ area of the pre-stressing steel on tensile side of the member as in Fig 1 (Word file or PDF file page 5-73
$A_b := 0.31 in^2$ area of the cross section of the lateral reinforcement (here #5, change accordingly)
$n_{leg} := 2$ Number of the legs of the lateral reinforcement
$A_{v} := A_{b} \cdot n_{leg}$ Area of the shear reinforcement (used for torsion as well)
HasMin := "yes" Put "Yes" if section Contains minimum or more lateral reinforcement
Material Properties:
ConType := "Normal" put one of the: "Normal", "AllLightweight", "SandLightweight"
f <sub>c</sub> := 4ksi compressive stregth of concrete
f <sub>y</sub> := 60ksi yield strength of the non-prestressing tensile steel
$f_y := 60ksi$ yield strength of the non-prestressing tensile steel $f_{py} := 300ksi$ yield strength of prestressing steel (ksi)

width of web (in.)

 $b_W := 8in$ 

fpc := 1ksi (can be calculated) compressive stress in concrete after prestress losses have occurred either at the centroid of the cross-section resisting transient loads or at the junction of the web and flange where the centroid lies in the flange (ksi)

f <sub>pu</sub> := 270ksi	specified tensile strength of prestressing steel (ksi)
$f_{ltl} := 32ksi$	Assumed value for long-term losses of prestressing steel (ksi)
$f_{pi} := 0.7 \cdot f_{pu}$	You may change the value if there are explicit information
$f_{pi} = 189 \cdot ksi$	
$E_p := 28500$ ksi	Modulus of elasticity of prestressing tendons (ksi)
f <sub>ct_specified</sub> :=	"No"
f <sub>ct</sub> := 0.6ksi	(If you have a lightweight concrete, put "Yes" if f <sub>ct</sub> available and enter the value, otherwise, put "No" and ignore f <sub>ct</sub> ) average splitting tensile strength of lightweight concrete
$\alpha_p := 90 \text{deg}$	This is the angle between the prestressing force and postive direction of shear force (demand).
$a_g := 0.25in$	maximum aggregate size
$\alpha := 90 \text{deg}$	angle of inclination of transverse reinforcement to longitudinal axis (°)
K <sub>1</sub> := 1.0	correction factor for source of aggregate to be taken as 1.0 unless determined by physical test, and as approved by the authority of jurisdiction (see <u><b>5.4.2.4</b></u> )
$w_c := 0.145 \frac{kip}{ft^3}$	unit weight of concrete (kcf); refer to <u>Table 3.5.1-1</u> or <u>Article C5.4.2.4</u>
$A_{ct} := 460.2in$	A <sub>ct</sub> is the area of concrete on the flexural tension side of the member as
$A_{ct} := 460.2 \text{ in}$	shown in Figure 1 (in. <sup>2</sup> ). It is calculated as teh area bellow the centroid of the non-composite section. It can also be calculated as the area of the non-composite section, divided by the height of the non-composite section, then multiplied by half of the overall height of the section.
<sup>s</sup> CrackControl <sup>:</sup>	= $2in$ maximum distance between layers of longitudinal crack control reinforcement, where the area of the reinforcement in each layer is not less than <b>0.003</b> <i>bvsx</i> , as shown in Figure 3 (in.)

# Demanded Shear and Torsion, Moment, Axial Force:

The induced internal shear and torsion in the section by the applied factored loads

Vu	:= 211kip	T <sub>u</sub> := 5450kip·in	M <sub>u</sub> := 12130kip∙in	N <sub>u</sub> :
----	-----------	------------------------------	-------------------------------	------------------

N<sub>u</sub> := 10kip positive is tensile

# Calculations and Design:

average stress in prestressing steel at the time for which the nominal resistance of member is required (ksi)



-

 $V_p$  is the component in the direction of the applied shear of the effective prestressing force; positive if resisting the applied shear (kip) (C5.8.2.3) (can be calculated if the angle is known)

$$V_{p} \coloneqq A_{ps} \cdot f_{ps} \cdot \cos(\alpha_{p})$$

$$V_{p} = 5.287 \times 10^{-14} \cdot \text{kip}$$

$$E_{c} \coloneqq 33000 \text{K}_{1} \cdot \text{w}_{c}^{-1.5} \cdot \left(\frac{\text{ft}^{3}}{\text{kip}}\right)^{1.5} \cdot \sqrt{f_{c} \cdot \text{ksi}}$$

$$E_{c} = 3.644 \times 10^{3} \cdot \text{ksi}$$
Modulus of elasticity of concrete (ksi) (5.4.2.4)
$$PPR \coloneqq \frac{A_{ps} \cdot f_{py}}{A_{ps} \cdot f_{py} + A_{s} \cdot f_{y}}$$
PreStress := "Prestressed" if PPR = 1.0 = "Partial prestressed" otherwise "Nonprestressed" if PPR = 0.0

"Partial prestressed" otherwise

The string variable "Prestress" shows the prestressing condition of the section.


### Evaluation of strength reduction factors $\phi$ , for flexure, shear, and torsion:

The following algorithm addresses Article 4.5.4.2.1, and Equations 5.5.4.2.1-1 and 5.5.4.2.1-2

(See: Article 5.5.4.2), p 5-25  $\varepsilon_y := \frac{f_y}{E_s}$   $\varepsilon_y = 2.069 \times 10^{-3}$ ebsY :=  $\varepsilon_y$  if PreStress = "Nonprestressed" 0.002 otherwise ebsY =  $2 \times 10^{-3}$  Evaluation of the flexural strength reduction factor:

 $phiT := 0.9 + 0.1 \cdot PPR$  phiT = 0.968 This temporal variable is for implementation of prestressing condition (normal, partial, or full)

C5.5.4.2.1 states that "For sections subjected to axial load with flexure, factored resistances are determined by multiplying both  $P_n$  and  $M_n$  by the appropriate single value of  $\phi$ 



 $\phi_f = 0.968$   $\phi_c := \phi_f$  As per C5.5.4.2.1

Evaluation of the shear and torsional strength reduction factors based on 5.5.4.2

$$\phi_{v} := \begin{array}{c} 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array} \qquad \phi_{t} := \begin{array}{c} 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array}$$

$$\phi_{t} := \begin{array}{c} 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array}$$

$$\phi_{t} = 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array}$$


$$\phi_{t} = 0.9 \text{ if ConType} = "Normal"} \\ \phi_{t} := \begin{array}{c} 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array}$$

$$\phi_{t} := \begin{array}{c} 0.9 \text{ if ConType} = "Normal"} \\ 0.7 \text{ otherwise} \end{array}$$

Calculating the value of d<sub>v</sub>:

effective shear depth taken as the distance, measured perpendicular to the neutral axis, between the resultants of the tensile and compressive forces due to flexure; it need not be taken to be less than the greater of  $0.9 d_e$  or 0.72h (in.)

To calculate  $d_v$ , using the commentary C5.8.2.9-1, assuming  $M_n = M_u/\phi$ , we have:



$$\mathbf{d}_{\mathrm{V}} \coloneqq \max\left(0.9\mathbf{d}_{\mathrm{e}}, 0.72 \cdot \mathbf{h}, \mathbf{d}_{\mathrm{V1}}\right)$$

(Art. 5.8.2.9)

 $d_V = 43.566 \cdot in$ 

Calculate the Shear Stress:

$$v_{u} := \frac{|v_{u} - \phi_{v} \cdot v_{p}|}{\phi_{v} \cdot b_{v} \cdot d_{v}}$$
(Eq 5.8.2.9-1)  
AASHTO 2010  

$$v_{u} = 0.673 \cdot ks!$$
Induced demanded shear stress  
Note that this should be  $v_{n}$  (equivalent to  $v_{u}/\phi$   
and not  $v_{u}$  or we need to remove the strength  
reduction fator. It is the same in 2010 as well.

Calculating S<sub>max</sub> (maximum permissible spacing of lateral reinforcement) considering the demanded shear stress *(Eqs. 5.8.2.7-1 and 5.8.2.7-2)* will be done when the shear reinorcement, if needed, is designed

Following is evaluation of the  $A_{cp}^{2}/p_{c}$  so that we address a cellular case, per 5.8.2.1-5

Val := 
$$\frac{A_{cp}^{2}}{p_{c}}$$
 if SecType = "Solid"  
otherwise  
 $\frac{A_{cp}^{2}}{p_{c}}$  if  $\left(\frac{A_{cp}^{2}}{p_{c}}\right) \le 2A_{o} \cdot b_{v}$   
 $2A_{o} \cdot b_{v}$  otherwise

(Equation 5.8.2.1-5)

Calculate Cracking Toresion (no segmental):

(Equation 5.8.2.1-4)

$$T_{cr} := \begin{array}{l} 0.125 \cdot \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \sqrt{f_c \cdot ksi}}} & \text{if ConType = "Normal"} \\ \text{otherwise} \\ 0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi}) \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi})}} & \text{if } f_{ct\_specified} = "Yes" \\ \text{otherwise} \\ 0.125 \cdot 0.75 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.75 \sqrt{f_c \cdot ksi}}} & \text{if ConType = "AllLightweight"} \\ 0.125 \cdot 0.85 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.85 \sqrt{f_c \cdot ksi}}} & \text{otherwise} \\ \end{array}$$

Check if the torsion can be ignored:


IgnoreTorsion := "Yes" if 
$$T_u \le 0.25 \cdot \phi_t \cdot T_{cr}$$
  
"No" otherwise

(Equation 5.8.2.1-3)

IgnoreTorsion = "Yes"

Calculating the demanded equivalent shear force:

Note that here, since the equivalent shear can be used for checking the section, we have to use the **T**<sub>u</sub> regardless of being less that 0.25 times the cracking torsion or not.



This equivalent V<sub>u\_eq</sub> is just for checking the adequecy of the section, when needed, otherwise the shear and torsional steel need to be evaluated as needed and then added up (shear as per 5.8.3.3 and Torsion as per 5.8.3.6.2)

Calculating the shear strength provided by concrete, Vc:

$$f_{po} := 0.7 f_{pu}$$

a parameter taken as modulus of elasticity of prestressing tendons multiplied by the lockedin difference in strain between the prestressing tendons and the surrounding concrete (ksi). For the usual levels of prestressing, a value of **0.7**  $f_{pu}$  will be appropriate for both pretensioned and post-tensioned members

# <u>Calculating $\underline{\varepsilon}_{s}$ using equation 5.8.3.4.2-4</u>

**IMPORTANT Note**: Deduct a portion of the area of the bars and tendons terminated less than their development length from the section that you are designing for, with the same proportion as their lack of full length (Here, the development length of a bar can be evaluated, and then having the actual length, the area can be reduced proportional to the ratio of available length to development length.

Addressing the requirement to have  $\mathbf{M}_{u}$  used not to be less than  $(\mathbf{V}_{u}-\mathbf{V}_{p})\mathbf{d}_{v}$ , we use  $\mathbf{M}_{u1}$  as follows:

$$M_{u1} := \begin{bmatrix} M_u & \text{if } |M_u| \ge |(V_u - V_p) \cdot d_v| \\ (V_u - V_p) \cdot d_v & \text{otherwise} \end{bmatrix}$$
$$M_{u1} = 1.213 \times 10^4 \cdot \text{kip} \cdot \text{in}$$

(Article 5.8.3.4.2)\_

<u>Note</u> that 1)  $A_s$  and  $A_{ps}$  should be reduced proportionally if a lack of full development length to the section under design 2) If closer than  $d_v$  to the face of support, use  $\varepsilon_s$  at distance  $d_v$  to evaluate  $\beta$  and  $\theta$ 

$$\varepsilon_{s1} \coloneqq \frac{\begin{vmatrix} M_{u1} \\ d_{v} \end{vmatrix} + 0.5N_{u} + \begin{vmatrix} V_{u} - V_{p} \end{vmatrix} - A_{ps} \cdot f_{po}}{E_{s} \cdot A_{s} + E_{p} \cdot A_{ps}}$$

$$\varepsilon_{s1} = -1.038 \times 10^{-3}$$

$$\varepsilon_{s2} \coloneqq \left| \frac{\frac{|\mathbf{M}_{u1}|}{d_{v}} + 0.5N_{u} + |\mathbf{V}_{u} - \mathbf{V}_{p}| - A_{ps} \cdot f_{po}}{E_{s} \cdot A_{s} + E_{p} \cdot A_{ps} + E_{c} \cdot A_{ct}} \right| \text{ if } \varepsilon_{s1} < 0.0$$

This and the follwing are evaluates  $\varepsilon_s$ , presisely and does not use zero.

$$\varepsilon_{s2} = -2.475 \times 10^{-4}$$

For pretensioned members,  $f_{po}$  can be taken as the stress in the strands when the concrete is cast around them, i.e., approximately equal to the jacking stress. For post-tensioned members,  $f_{po}$  can be conservatively taken as the average stress in the tendons when the posttensioning is completed.

$$\varepsilon_{s} := \varepsilon_{s} \leftarrow -0.0004 \text{ if } \varepsilon_{s2} < -4.0 \times 10^{-4}$$

$$\varepsilon_{s} \leftarrow 0.006 \text{ if } \varepsilon_{s2} > 0.006$$


$$\varepsilon_{s2} \text{ otherwise}$$
Taking care of the last condition on evaluation of  $\varepsilon_{s}$ 


$$\varepsilon_{s} = -2.475 \times 10^{-4}$$
Page 5-72 to 74 (2008).
Page 5-71 to 73 (2010)

#### NOTE

For sections closer than  $d_y$  to the face of support the value for  $\epsilon_s$  calculated at  $d_y$  from the face of support may be used to evaluate  $\beta$  and  $\theta$ 

If the axial tension is large enough to crack the flexural compression face of the section, the value calculated should be doubled.





Designing the transverse reinforcement for <u>SHEAR</u> (Note that the  $A_v/s$  will be evaluated. Then when we have Torsion as well, we can add them appropriately depending on the type of section)

Check if we need shear reinforcement per 5.8.2.4-1

NeedShear := "Yes" if 
$$V_u > 0.5 \cdot \phi_v \cdot (V_c + V_p)$$
  
"No" otherwise (Equation 5.8.2.4-1)  
NeedShear = "Yes"

Here we need to check for mininum reinforcement as per 5.8.2.5 (AASHTO 2010)

$$\begin{split} A_V &= 0.62 \cdot in^2 \\ V_n &\coloneqq min \Biggl( \frac{V_u}{\varphi_V}, 0.25 f_c \cdot b_V \cdot d_V + V_p \Biggr) \quad V_n = 234.444 \cdot kip \quad \fbox{Based on Eq. 5.8.3.3-1 and 2} \\ V_s &\coloneqq V_n - V_c - V_p \\ V_s &= 104.613 \cdot kip \end{split} \qquad Here \ \texttt{S}_{min} \ \text{actually means the "s" based on the minimum requirement, otherwise, this is the limit for spacing and the specing should be less or at most equal to this} \end{split}$$

$$s_{max} := \frac{A_V \cdot I_y}{0.0316 \cdot b_V \cdot \sqrt{f_c \cdot ksi}}$$
  $s_{max} = 73.576 \cdot in$  **Eq. 5.8.2.5-1**

$$s_{req} := if \left[ V_{s} \le 0, s_{max}, \frac{A_{V} \cdot f_{y} \cdot d_{V} \cdot (\cot(\theta) + \cot(\alpha)) \cdot \sin(\alpha)}{V_{s}} \right]$$

$$s_{req} = 28.972 \cdot in$$

$$s_{W} := \min(s_{max}, s_{req})$$
(Equation 5.8.3.3-4)

 $s=28.972\!\cdot\!in$ 

Based on **5.8.2.7** and **5.8.2.9**, we need to evaluate the final spacing by finding the othe maximum limits as follows:

$$s_{max2} := if(v_u < 0.125 \cdot f_c, min(0.8 \cdot d_v, 24in), min(0.4 \cdot d_v, 12in))$$
 (Eqs. 5.8.2.7-1 and 5.8.2.7-2)  
 $s_{max2} = 12 \cdot in$ 

The spacing of the transversal reinforcement is as follows:

$$s_{actual} := min(s, s_{max2})$$

 $s_{actual} = 12 \cdot in$ 

To address 5.8.3.3-2, The upper limit of  $V_n$ , given by Eq. 2, is intended to ensure that the concrete in the web of the beam will not crush prior to yield of the transverse reinforcement.

$$0.25 \cdot f_{\mathbf{C}} \cdot b_{\mathbf{V}} \cdot d_{\mathbf{V}} = 348.526 \cdot kip$$


Note that  $V_u/\phi$  -Vp should be less than 0.25  $f_c b_v d_v$  otherwise section is not enough and concrete crushes due to local shear demand.

Check if the section is enough:

SecEnough := "Yes" if 
$$\frac{V_u}{\phi_V} - V_p < 0.25 \cdot f_c \cdot b_V \cdot d_V$$
  
"STOP and Change Section" otherwise  
SecEnough = "Yes"

Also we need to specify where we have to switch to strut-and-tie model Note :  $V_p$  is the vertical component of the prestressing force (as has already been evaluated by using the angle  $\alpha_p$ )

Finding the ratio of avss=A,/s for shear:



 $avss = 0.052 \cdot in$ 

## Design for Torsional lateral reinforcement:

Note that if we have a torsion that cannot be ignored, we design the lateral reinforcement for that and we call that avst. later we add the shear and torsion reinforcement properly. Corresponding longitudinal steel will be calculated as well.

$$avst1 := \begin{bmatrix} \frac{T_u}{\Phi_t} \\ 2 \cdot A_0 \cdot f_y \cdot \cot(\theta) \\ 0.0 \text{ otherwise} \end{bmatrix} \text{ if IgnoreTorsion = "No"} \qquad \textbf{(Equation 5.8.3.6.2-1)}$$

$$avst1 = 0 \cdot \text{in} \qquad \text{This is for one leg}$$

$$avst1 = 0 \cdot \text{in} \qquad \text{This is for one leg}$$

$$avst := 2 \cdot avst1 \qquad avst = 0 \cdot \text{in}$$

$$avs := avss + avst \qquad \text{This is the total lateral reinforcement needed for shear and torsion}$$

$$sShearTorsion \stackrel{!=}{=} \frac{A_v}{avs} \qquad \textbf{(SchearTorsion = 12 \cdot \text{in})}$$

$$Design for Torsional longitudinal reinforcement: (Article 5.8.3.6.3 Longitudinal Reinforcement) [Also consider Eq. 5.8.3.5-1]$$

$$tmpVal := \frac{|M_{ul}|}{\Phi_f \cdot d_v} + \frac{0.5 \cdot N_u}{\Phi_c} + \cot(\theta) \cdot \sqrt{\left(\left|\frac{V_u}{\Phi_v} - V_p\right| - 0.5 \cdot V_s\right)^2 + \left(\frac{0.45 \cdot p_h \cdot T_u}{2 \cdot A_0 \cdot \Phi_t}\right)^2}$$

$$tmpVal = 2.527 \times 10^3 \cdot \text{kip}$$

$$A_1 := \begin{bmatrix} 0.0 \text{ if IgnoreTorsion = "Yes"} \\ \text{otherwise} \\ \text{if SecType = "Solid"} \\ \frac{0.0 \text{ if Aps} \cdot f_{ps} + A_s \cdot f_y \ge tmpVal \\ \frac{mpVal - A_{ps} \cdot f_{ps}}{f_y} - A_s \text{ otherwise} \\ \frac{T_u \cdot P_h}{\Phi_t \cdot 2 \cdot A_0 \cdot f_y} \text{ otherwise} \\ A_1 = 0 \cdot \text{in}^2$$

$$A_1 = 0 \cdot \text{in}^2$$

 $A_{s\_total} \coloneqq A_s + A_l$ 

1

Note that distribution of  $\mathbf{A}_{\mathbf{I}}$  should be evenly around the section

 $A_{s\_total} = 12.7 \cdot in^2$ 


# Example-3 Solution using the Developed MathCAD Design Program


# **Example 3: (No pre-stressing steel)**

Design a precast, non-pre-stressed normal-weight concrete spandrel beam for combined shear and torsion. Roof members are simply supported on spandrel ledge. Spandrel beams are connected to columns to transfer torsion. Continuity between spandrel beams is not provided.

Design Criteria:  
Live load = 
$$30 \text{ lb/ft}^2$$
  
Dead load =  $90 \text{ lb/ft}^2$  (double tee + topping + insulation + roofing)  
 $f_c = 5000 \text{ psi} (w_c = 150 \text{ pcf})$   
 $f_y = 60,000 \text{ psi}$ 

Roof members are 10 ft wide double tee units, 30 in. deep with 2 in. topping. Design of these units is not included in this design example. For lateral support, alternate ends of roof members are fixed to supporting beams.








Figure C. 7 Spandrel beam cross section

Spandrel beam height	=48 in.
$f_c$ of the beam concrete	=5000 psi
Effective width (b <sub>eff</sub> )	=16 in.
Width of the web	=16 in.
Area of the regular (non-pre-stressing)	
steel on the section: A <sub>s</sub>	$=3.0 \text{ in}^2$

# **Preparing the input data:**

Before calculating the required input data, it should be noted that the values of the input data for various parameters depend on factors that are beyond the scope of this project. So, it is assumed that for each case, the user, will calculate the necessary values and provides them as the input data. The "designed" shear and torsion reinforcement depends on the accuracy of the input data.

On the other hand, depending of the case (beam geometry, demanded load level, reinforcement arrangement, and location of the section) the Strut-and-Tie Model should be used in lieu of the process implemented in this program.

#### Section:

The section located at a distance equal to (d=45.5") of the girder length (span) is selected for design in this example. The distance between the supports, center to center, is equal to 40 feet. So, the distance between the support and the center of the span, is 20'.

The demanded values at the critical section, located at 45.5" from the support are:

M<sub>u</sub>=451.7 kip-ft (at the critical section), [M<sub>u</sub>=1316 kip-ft (at the center)]

V<sub>u</sub>=127.2 kips (at the critical section)

N<sub>u</sub>=0.0 kips

T<sub>u</sub>=1348.8 kip-in (at the critical section)

Calculate the tensile flexural steel:

 $M_u = 0.85 \times f_c' \times b \times a \times (d - \frac{a}{2})$ 

 $1316 \times 12 = 0.85 \times 5 \times 16 \times a \times (45.5 - \frac{a}{2}) \Longrightarrow a = 5.428$  in.

$$A_{s} = \frac{0.85 \times f_{c}' \times b \times a}{f_{y}} \Longrightarrow A_{s} = \frac{0.85 \times 5 \times 16 \times 5.428}{60}$$

 $A_s=6.15 \text{ in}^2$  (Area of regular steel needed)

A<sub>s</sub>=7.8 in<sup>2</sup> (Area of regular steel provided)

The length of the outside perimeter of the concrete section

 $P_c=2(16+48)+2(8) = 144$  in.

Perimeter of the centerline of the closed transverse torsion reinforcement (in.)

$$P_{h}=2\times(76+5)$$
  
 $P_{h}=162$  in

Total area enclosed by outside perimeter of concrete cross-section (in2):

 $A_{cp}=(16)(48)+(16)(8) = 768+128 = 896 \text{ in}^2.$ 

Width of web adjusted for the presence of ducts (in.); width of the interface (in.)

 $b_v=16$  in.

 $b_w = 16$  in.

Area enclosed by the shear flow path, including any area of holes therein (in2)

 $A_{oh}=(13) (45) + (8) (13) = 689 \text{ in}^2.$  $A_o=0.85 (689) = 585.6 \text{ in}^2.$  $A_o=585.6 \text{ in}^2$ 

Note: For the same section and demanded values, the spacing is 5 in. using ACI code.

### LRFD Shear and Torsion, using Sectional Model (SECTION 5, Interim 2008, Revised based on 2010)

# IMPORTANT to Note: changing the unit system will lead to inaccuracy of the results, since most of the factors are based on teh US system

**Example 3** (Please see the WORD File for detailed information)

1) Please see the WORD file for graphical definition of the parameters.

2) The **PDF file with links** can help you with jumping to a desired location

 $\beta$ ) Some parameters such as  $A_0$ ,  $P_h$ , etc., need to be evaluated beforehand due to possible

irregularities associated with various sections. Also, demanded loads are closely related to the bridge configuration and related load combination. This file, ONLY addresses shear/torsion part of design.

If the distance between zero-shear point and the face of support is less than 2d (d is the distance between the compression side and centriod of tensile reniforcement) OR a concentrated load causing more than 1/2 of the shear at a support is closer than 2d from the face of support, this method is not applicable. You need to use Stut-and-Tie Model (Section 5.6.3). IN GENATRAL: Where the "plane sections assumption of felxural theory" is NOT valid, strut-and-Tie Model should be used.

# Enter your data in the highlighted (yellow) fields

# INPUT DATA:

### Section Geometry:

h := 48in	Overall section depth (in)
$h_{nc} := 48in$	Depth of the non-composite section (in)
$A_{cp} := 896 in^2$	total area enclosed by outside perimeter of concrete cross-section (in <sup>2</sup> ). Having the section, this value needs to be calculated
p <sub>c</sub> := 114in	the length of the outside perimeter of the concrete section (in.). Having the section, this value needs to be calculated
$A_0 := 585 in^2$	area enclosed by the shear flow path, including any area of holes therein (in <sup>2</sup> ). Having the section, this value needs to be calculated
$p_h := 162 in$	perimeter of the centerline of the closed transverse torsion reinforcement (in.). Having the section, this value needs to be calculated
$b_V := 16in$	width of web adjusted for the presence of ducts (in.); width of the interface (in.)
	OR: effective web width taken as the minimum web width, measured parallel to the neutral axis, between the resultants of the tensile and compressive forces due to flexure, or for circular sections, the diameter of the section, modified for the presence of ducts where applicable (in.)

b <sub>w</sub> ∷= 16in widt	h of web (in.)
d :- 15 5112	ance from extreme compression fiber to the centroid of the nonprestressed ile reinforcement (in.)
$d \rightarrow 0.0$ in	nce from extreme compression fiber to the centroid of the prestressing ns (in.)
SecType := "Solid"	Type of the cross section to design
$d_t := 45.5in$	distance from extreme compression fiber to the centroid of the extreme tensile reinforcement on teh section (it is different from d <sub>s</sub> )
c <sub>comp</sub> := 6.785in	Depth of the compression zone (you need to calculate it depending on the geometry of the section, amount of the reinforcement on tensile and compression side and material properties)

The section will be specified depending on the input data for regular and/or prestressing steel to check if the girder is nonprestressed, prestressed, or partially prestressed.

# Reinforcement:

$A_s := 7.8 in^2$	area of the non-prestressing tensile reinforcement on the section
E <sub>s</sub> := 29000ksi	modulus of elasticity of reinforcing bars (ksi)
$A_{ps} := 0.0in^2$	area of the pre-stressing steel on tensile side of the member as in Fig 1 (Word) file or PDF file page 5-73
$A_b := 0.2in^2$	area of the cross section of the lateral reinforcement (here #5, change accordingly)
$n_{leg} := 2$	Number of the legs of the lateral reinforcement
$A_v := A_b \cdot n_{leg}$	Area of the shear reinforcement (used for torsion as well)
HasMin := "yes	Put "Yes" if section Contains minimum or more lateral reinforcement
Material Prope	rties:
ConType := "N	formal" put one of the: "Normal", "AllLightweight", "SandLightweight"
$f_c := 5ksi$	compressive stregth of concrete
$f_y := 60ksi$	yield strength of the non-prestressing tensile steel
f <sub>py</sub> := 300ksi	yield strength of prestressing steel (ksi)
$f_{pc} := 0.0ksi$	( <b>can be calculated</b> ) compressive stress in concrete after prestress losses have occurred either at the centroid of the cross-section resisting transient loads or at the junction of the web and flange where the centroid lies in the flange (ksi)

f <sub>pu</sub> := 270ksi	specified tensile strength of prestressing steel (ksi)
f <sub>lt1</sub> := 32ksi	Assumed value for long-term losses of prestressing steel (ksi)
$f_{pi} := 0.7 \cdot f_{pu}$ $f_{pi} = 189 \cdot ksi$	You may change the value if there are explicit information
$E_p := 28600 \text{ksi}$	Modulus of elasticity of prestressing tendons (ksi)
f <sub>ct_specified</sub> :=	"No"
$\mathbf{f_{ct}} \coloneqq 0.2 \mathrm{ksi}$	(If you have a lightweight concrete, put "Yes" if f <sub>ct</sub> available and enter the value, otherwise, put "No" and ignore f <sub>ct</sub> ) average splitting tensile strength of lightweight concrete
$\alpha_p := 9 \text{deg}$	This is the angle between the prestressing force and postive direction of shear force (demand).
a <sub>g</sub> := 0.25in	maximum aggregate size
$\alpha := 90 \text{deg}$	angle of inclination of transverse reinforcement to longitudinal axis (°)
K <sub>1</sub> := 1.0	correction factor for source of aggregate to be taken as 1.0 unless determined by physical test, and as approved by the authority of jurisdiction (see <u><b>5.4.2.4</b></u> )
$w_c := 0.150 \frac{kip}{ft^3}$	unit weight of concrete (kcf); refer to <u>Table 3.5.1-1</u> or <u>Article C5.4.2.4</u>
· · · · · · · · · · · · · · · · · · ·	A <sub>ct</sub> is the area of concrete on the flexural tension side of the member as
$A_{ct} := (0.0in)^2$	shown in Figure 1 (in. <sup>2</sup> ). It is calculated as the area bellow the centroid of the non-composite section. It can also be calculated as the area of the non-composite section, divided by the height of the non-composite section, then multiplied by half of the overall height of the section.
<sup>s</sup> CrackControl <sup>::</sup>	= 2in maximum distance between layers of longitudinal crack control reinforcement, where the area of the reinforcement in each layer is not less than 0.003b <sub>v</sub> s <sub>x</sub> , as shown in Figure 3 (in.)

# Demanded Shear and Torsion, Moment, Axial Force:

The induced internal shear and torsion in the section by the applied factored loads

 $V_u := 127.2 kip$  $T_u := 1348.8 kip \cdot in$  $M_u := 5420.4 kip \cdot in$  $N_u := 0 kip$ positive is tensile

# Calculations and Design:

average stress in prestressing steel at the time for which the nominal resistance of member is required (ksi)

$$f_{ps} := f_{pi} - f_{ltl}$$

 $V_p$  is the component in the direction of the applied shear of the effective prestressing force; positive if resisting the applied shear (kip) (C5.8.2.3) (can be calculated if the angle is known)

$$V_{p} := A_{ps} \cdot f_{ps} \cdot \cos(\alpha_{p})$$

$$V_{p} = 0 \cdot kip$$

$$E_{c} := 33000K_{1} \cdot w_{c}^{-1.5} \cdot \left(\frac{ft^{3}}{kip}\right)^{1.5} \cdot \sqrt{f_{c} \cdot ksi}$$

$$E_{c} = 4.287 \times 10^{3} \cdot ksi$$
Modulus of elasticity of concrete (ksi) (5.4.2.4)
$$PPR := \frac{A_{ps} \cdot f_{py}}{A_{ps} \cdot f_{py} + A_{s} \cdot f_{y}}$$
PreStress := "Prestressed" if PPR = 1.0 = "Nonprestressed" otherwise "Nonprestressed" if PPR = 0.0

▼

The string variable "Prestress" shows the prestressing condition of the section.

# Evaluation of strength reduction factors $\phi$ , for flexure, shear, and torsion:

"Partial prestressed" otherwise

The following algorithm addresses Article 4.5.4.2.1, and Equations 5.5.4.2.1-1 and 5.5.4.2.1-2

(See: Article 5.5.4.2), p 5-25


$$\varepsilon_{y} := \frac{f_{y}}{E_{s}}$$
  $\varepsilon_{y} = 2.069 \times 10^{-3}$   
ebsY :=  $\varepsilon_{y}$  if PreStress = "Nonprestressed"  
0.002 otherwise

 $ebsY = 2.069 \times 10^{-3}$ 


Evaluation of the flexural strength reduction factor:

This temporal variable is for implementation of phiT :=  $0.9 + 0.1 \cdot PPR$ phiT = 0.9prestressing condition (normal, partial, or full)

C5.5.4.2.1 states that "For sections subjected to axial load with flexure, factored resistances are determined by multiplying both  $P_n$  and  $M_n$  by the appropriate single value of  $\phi$ 




Evaluation of the shear and torsional strength reduction factors based on 5.5.4.2



<u>Calculating the value of d<sub>v</sub>:</u>

effective shear depth taken as the distance, measured perpendicular to the neutral axis, between the resultants of the tensile and compressive forces due to flexure; it need not be taken to be less than the greater of 0.9 de or 0.72h (in.)

To calculate  $d_v$ , using the commentary C5.8.2.9-1, assuming  $M_n = M_u/\phi$ , we have:



$$\mathbf{d}_{\mathrm{V}} \coloneqq \max\left(0.9\mathbf{d}_{\mathrm{e}}, 0.72 \cdot \mathbf{h}, \mathbf{d}_{\mathrm{V1}}\right)$$

(Art. 5.8.2.9)  $d_v = 40.95 \cdot in$ 

Calculate the Shear Stress:

$$v_{u} := \frac{\left|V_{u} - \phi_{v} \cdot V_{p}\right|}{\phi_{v} \cdot b_{v} \cdot d_{v}}$$

$$(Eq \ 5.8.2.9-1)$$

$$AASHTO 2010$$

$$Note that this should be v_{n} (equivalent to v_{u}/\phi)$$
and not v<sub>u</sub> or we need to remove the strength reduction fator. It is the same in 2010 as well.

Calculating S<sub>max</sub> (maximum permissible spacing of lateral reinforcement) considering the demanded shear stress *(Eqs. 5.8.2.7-1 and 5.8.2.7-2)* will be done when the shear reinorcement, if needed, is designed

Following is evaluation of the  $A_{cp}^{2}/p_{c}$  so that we address a cellular case, per 5.8.2.1-5

Val := 
$$\frac{A_{cp}^{2}}{p_{c}}$$
 if SecType = "Solid"  
otherwise  
 $\frac{A_{cp}^{2}}{p_{c}}$  if  $\left(\frac{A_{cp}^{2}}{p_{c}}\right) \le 2A_{o} \cdot b_{v}$   
 $2A_{o} \cdot b_{v}$  otherwise

Calculate Cracking Toresion (no segmental):

(Equation 5.8.2.1-4)

(Equation 5.8.2.1-5)


$$T_{cr} := \begin{array}{l} 0.125 \cdot \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \sqrt{f_c \cdot ksi}}} & \text{if ConType = "Normal"} \\ \text{otherwise} \\ 0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi}) \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot \min(4.7 \cdot f_{ct}, \sqrt{f_c \cdot ksi})}} & \text{if } f_{ct\_specified} = "Yes" \\ \text{otherwise} \\ 0.125 \cdot 0.75 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.75 \sqrt{f_c \cdot ksi}}} & \text{if ConType = "AllLightweight"} \\ 0.125 \cdot 0.85 \sqrt{f_c \cdot ksi} \cdot Val \cdot \sqrt{1 + \frac{f_{pc}}{0.125 \cdot 0.85 \sqrt{f_c \cdot ksi}}} & \text{otherwise} \\ \end{array}$$

Check if the torsion can be ignored:

IgnoreTorsion := "Yes" if 
$$T_u \le 0.25 \cdot \phi_t \cdot T_{cr}$$
 (Equation 5.8.2.1-3)  
"No" otherwise  
IgnoreTorsion = "No"

Calculating the demanded equivalent shear force:

Note that here, since the equivalent shear can be used for checking the section, we have to use the **T**<sub>u</sub> regardless of being less that 0.25 times the cracking torsion or not.



This equivalent V<sub>u\_eq</sub> is just for checking the adequecy of the section, when needed, otherwise the shear and torsional steel need to be evaluated as needed and then added up (shear as per 5.8.3.3 and Torsion as per 5.8.3.6.2)

Calculating the shear strength provided by concrete, V<sub>c</sub>:



a parameter taken as modulus of elasticity of prestressing tendons multiplied by the lockedin difference in strain between the prestressing tendons and the surrounding concrete (ksi). For the usual levels of prestressing, a value of **0.7**  $f_{pu}$  will be appropriate for both pretensioned and post-tensioned members

# Calculating *ɛ*<sub>s</sub> using equation 5.8.3.4.2-4

**IMPORTANT Note**: Deduct a portion of the area of the bars and tendons terminated less than their development length from the section that you are designing for, with the same proportion as their lack of full length (Here, the development length of a bar can be evaluated, and then having the actual length, the area can be reduced proportional to the ratio of available length to development length.

Addressing the requirement to have  $\mathbf{M}_{u}$  used not to be less than  $(\mathbf{V}_{u}-\mathbf{V}_{p})\mathbf{d}_{v}$ , we use  $\mathbf{M}_{u1}$  as follows:

$$M_{u1} := \begin{bmatrix} M_u & \text{if } | M_u | \ge | (V_u - V_p) \cdot d_v \\ (V_u - V_p) \cdot d_v & \text{otherwise} \end{bmatrix}$$
$$M_{u1} = 5.42 \times 10^3 \cdot \text{kip} \cdot \text{in}$$

(Article 5.8.3.4.2)

<u>Note</u> that 1)  $A_s$  and  $A_{ps}$  should be reduced proportionally if a lack of full development length to the section under design 2) If closer than  $d_v$  to the face of support, use  $\varepsilon_s$  at distance  $d_v$  to evaluate  $\beta$  and  $\theta$ 

$$\varepsilon_{s1} \coloneqq \frac{\begin{vmatrix} M_{u1} \\ d_{v} \end{vmatrix} + 0.5N_{u} + \begin{vmatrix} V_{u} - V_{p} \end{vmatrix} - A_{ps} \cdot f_{po}}{E_{s} \cdot A_{s} + E_{p} \cdot A_{ps}}$$
(Equation 5.8.3.4.2-4)  
$$\varepsilon_{s1} = 1.148 \times 10^{-3}$$

(Article 5.8.3.4.2) <u>Page 5-72 (2008), Page 5-71 (2010)</u>

$$\varepsilon_{s2} \coloneqq \left\{ \begin{array}{l} \frac{\left| \mathbf{M}_{u1} \right|}{\mathbf{d}_{v}} + 0.5N_{u} + \left| \mathbf{V}_{u} - \mathbf{V}_{p} \right| - \mathbf{A}_{ps} \cdot \mathbf{f}_{po} \\ \frac{\mathbf{E}_{s} \cdot \mathbf{A}_{s} + \mathbf{E}_{p} \cdot \mathbf{A}_{ps} + \mathbf{E}_{c} \cdot \mathbf{A}_{ct}}{\mathbf{E}_{s1} \quad \text{otherwise}} \right. \text{ if } \varepsilon_{s1} < 0.0$$

This and the follwing are evaluates  $\varepsilon_s$ , presisely and does not use zero.

$$\varepsilon_{s2} = 1.148 \times 10^{-3}$$


For pretensioned members,  $f_{po}$  can be taken as the stress in the strands when the concrete is cast around them, i.e., approximately equal to the jacking stress. For post-tensioned members,  $f_{po}$  can be conservatively taken as the average stress in the tendons when the posttensioning is completed.


$$\varepsilon_{s} := \left\{ \begin{array}{l} \varepsilon_{s} \leftarrow -0.0004 & \text{if } \varepsilon_{s2} < -4.0 \times 10^{-4} \\ \varepsilon_{s} \leftarrow 0.006 & \text{if } \varepsilon_{s2} > 0.006 \\ \varepsilon_{s2} & \text{otherwise} \end{array} \right\} \text{Taking care of the last condition on evaluation of } \varepsilon_{s} \left\{ \begin{array}{l} \text{Article 5.8.3.4.2} \\ \text{Page 5-72 to 74 (2008),} \\ \text{Page 5-71 to 73 (2010)} \end{array} \right\}$$

#### NOTE

For sections closer than  $d_y$  to the face of support the value for  $\epsilon_s$  calculated at  $d_y$  from the face of support may be used to evaluate  $\beta$  and  $\theta$ 

If the axial tension is large enough to crack the flexural compression face of the section, the value calculated should be doubled.





Designing the transverse reinforcement for <u>SHEAR</u> (Note that the  $A_v/s$  will be evaluated. Then when we have Torsion as well, we can add them appropriately depending on the type of section)

Check if we need shear reinforcement per 5.8.2.4-1

NeedShear :=	"Yes" if $V_u > 0.5 \cdot \varphi_V \cdot \left( V_c + V_p \right)$	(Equation 5.8.2.4-1)
	"No" otherwise	NeedShear = "Yes"

Here we need to check for mininum reinforcement as per 5.8.2.5 (AASHTO 2010)

$$\begin{split} A_V &= 0.4 \cdot in^2 \\ V_n &:= \min \Biggl( \frac{V_u}{\varphi_V}, 0.25 f_c \cdot b_V \cdot d_V + V_p \Biggr) \quad V_n = 141.333 \cdot kip \quad \fbox{Based on Eq. 5.8.3.3-1 and 2} \\ V_s &:= V_n - V_c - V_p \\ V_s &= 21.9 \cdot kip \\ V_s &= 21.9 \cdot kip \end{split} \qquad Here \ S_{min} \ actually \ means \ the "s" \ based \ on \ the \ minimum \ requirement, \ otherwise, \ this \ is \ the \ limit \ for \ spacing \ and \ the \ specing \ should \ be \ less \ or \ at \ most \ equal \ to \ this \ A_V \cdot f_V \end{split}$$

$$s_{max} := \frac{A_V \cdot I_y}{0.0316 \cdot b_V \cdot \sqrt{f_c \cdot ksi}}$$
  $s_{max} = 21.228 \cdot in$  **Eq. 5.8.2.5-1**

$$s_{req} := if \left[ V_{s} \le 0, s_{max}, \frac{A_{v} \cdot f_{y} \cdot d_{v} \cdot (\cot(\theta) + \cot(\alpha)) \cdot \sin(\alpha)}{V_{s}} \right]$$

$$s_{req} = 69.062 \cdot in$$

$$s_{v} := \min(s_{max}, s_{req})$$

$$s = 21.228 \cdot in$$

Based on **5.8.2.7** and **5.8.2.9**, we need to evaluate the final spacing by finding the othe maximum limits as follows:

$$s_{max2} := if(v_u < 0.125 \cdot f_c, min(0.8 \cdot d_v, 24in), min(0.4 \cdot d_v, 12in))$$
 (Eqs. 5.8.2.7-1 and 5.8.2.7-2)  
 $s_{max2} = 24 \cdot in$ 

The spacing of the transversal reinforcement is as follows:

 $s_{actual} := min(s, s_{max2})$ 

 $s_{actual} = 21.228 \cdot in$ 

To address 5.8.3.3-2, The upper limit of  $V_n$ , given by Eq. 2, is intended to ensure that the concrete in the web of the beam will not crush prior to yield of the transverse reinforcement.

$$0.25 \cdot \mathbf{f}_{\mathbf{c}} \cdot \mathbf{b}_{\mathbf{V}} \cdot \mathbf{d}_{\mathbf{V}} = 819 \cdot \mathbf{kip}$$

Note that  $V_u/\phi$  -Vp should be less than 0.25  $f_c b_v d_v$  otherwise section is not enough and concrete crushes due to local shear demand.

Check if the section is enough:


SecEnough := "Yes" if 
$$\frac{V_u}{\phi_V} - V_p < 0.25 \cdot f_c \cdot b_v \cdot d_v$$
  
"STOP and Change Section" otherwise

SecEnough = "Yes"

Also we need to specify where we have to switch to strut-and-tie model

Note :  $V_p$  is the vertical component of the prestressing force (as has already been evaluated by using the angle  $\alpha_p$ )

Finding the ratio of avss=A<sub>v</sub>/s for shear:



 $avss = 0.019 \cdot in$ 

#### Design for Torsional lateral reinforcement:

Note that if we have a torsion that cannot be ignored, we design the lateral reinforcement for that and we call that avst. later we add the shear and torsion reinforcement properly. Corresponding longitudinal steel will be calculated as well.

avst1 := 
$$\frac{\frac{T_u}{\phi_t}}{2 \cdot A_0 \cdot f_y \cdot \cot(\theta)} \text{ if IgnoreTorsion = "No"}$$
$$0.0 \text{ otherwise}$$

(Equation 5.8.3.6.2-1)

 $avst1 = 0.014 \cdot in$  This is for one leg

$$avst := 2 \cdot avst1$$
  $avst = 0.028 \cdot in$ 

avs := avss + avst This is the total lateral reinforcement needed for shear and torsion

$$s_{\text{ShearTorsion}} \coloneqq \text{floor}\left(\frac{A_{V}}{avs \cdot in}\right) \cdot in$$

<sup>s</sup>ShearTorsion = 8·in

<u>Design for Torsional longitudinal reinforcement: (Article 5.8.3.6.3 Longitudinal</u> <u>Reinforcement) [Also consider Eq. 5.8.3.5-1]</u>

$$tmpVal := \frac{\left| M_{u1} \right|}{\phi_{f} \cdot d_{V}} + \frac{0.5 \cdot N_{u}}{\phi_{c}} + \cot(\theta) \cdot \sqrt{\left( \left| \frac{V_{u}}{\phi_{V}} - V_{p} \right| - 0.5 \cdot V_{s} \right)^{2} + \left( \frac{0.45 \cdot p_{h} \cdot T_{u}}{2 \cdot A_{o} \cdot \phi_{t}} \right)^{2}}$$

 $tmpVal = 393.872 \cdot kip$ 

$$A_{l} := \begin{array}{c} 0.0 \quad \text{if IgnoreTorsion} = "Yes" \\ \text{otherwise} \\ \text{if SecType} = "Solid" \\ \hline \\ 0.0 \quad \text{if } A_{ps} \cdot f_{ps} + A_{s} \cdot f_{y} \ge \text{tmpVal} \\ \hline \\ \frac{1}{mpVal - A_{ps} \cdot f_{ps}} - A_{s} \quad \text{otherwise} \\ \hline \\ \frac{T_{u} \cdot p_{h}}{\phi_{t} \cdot 2 \cdot A_{o} \cdot f_{y}} \quad \text{otherwise} \\ \hline \\ A_{l} = 0 \cdot \text{in}^{2} \qquad A_{s \quad \text{total}} := A_{s} + A_{l} \end{array}$$
Note that  $A_{l}$  is the additional steel needed due to torsion
$$Eq. 5.8.3.6.3-1$$

$$Eq. 5.8.3.6.3-2$$

 $A_{s\_total} = 7.8 \cdot in^2$ 

Note that distribution of  $\mathbf{A}_{\mathbf{I}}$  should be evenly around the section