

GRADUATING THESIS.

TESTS ON THE EFFICIENCY OF THE
POWER PLANT AT THE KANSAS STATE AGRICULTURAL COLLEGE.

BY

GLICK FOCKELE,

MURRAY S. COLE.

274

TESTS ON THE EFFICIENCY OF THE
POWER PLANT AT THE KANSAS AGRICULTURAL COLLEGE.

The plant is designed to furnish heat and power for the various departments at the Kansas State Agricultural College of Manhattan, Kansas. It was originally intended by the writers to include in their work, tests on the heating power of the plant, but the arrangement of their other college work during the year, made it impossible for them to conduct the experiments at a time when the heating plant was in operation. Another drawback was the absence of suitable apparatus for the determination of the calorific power of the coal.

The heating plant consists of six externally fired, horizontal, multitubular boilers, designated as No. 1, 2, 3, 4, 5 and 6. Five are of 60 nominal horsepower and one, No. 6, is of 100 nominal horsepower. The tests were conducted upon No. 1, for the reason that it was the only high pressure boiler which was piped for individual feed water, and with this boiler is our interest concerned. None of the connections with other boilers could possibly affect results of these tests except in the test on April 28th, when No. 3 was turned in on account of the heavy load on the engine. In this case neither boiler made more steam than the engine could use, so the pressure in neither one was affected in the least and the conditions of the test were kept uniform. The boiler itself is 54" diameter, with 34 flues 3-3/4 inches in diameter and 16 feet long. The grates are 4-1/2' by 4-1/2". The boiler was built by Joseph Bromich of Topeka, Kansas. It was installed in 1898. It was in very good condition for all tests.

The fuel used was the coal furnished by the state for use in the institution, and was of very poor quality. It comes from the state mines near Leavenworth, and is mined by the prisoners from the state penitentiary.

The engine tested was the one in general use as a source of power at the plant and was manufactured by A. L. Ide & Sons, of Springfield, Illinois. It is generally called the "Ideal," and is of 100 horsepower, and is direct connected with a 60 kilowatt dynamo. All apparatus used, such as thermometers and guages, were standard and were carefully tested as to correctness. By comparing the tachometer with an ordinary speed counter we found an error of nine revolutions per minute less than actual speed. The tabulated results are the corrected results.

The first boiler test was run on February 14, 1902. The steam generated was used in the heating system of the college. This test was run under the direction of W. M. Sawdon, Assistant in Engineering. The per cent of water was determined as recommended in "Smart's Laboratory Practice," the weight before exposure to heat being 14 lbs., 10-1/4 oz. and afterwards 13 lbs., 15-1/8 oz., showing a loss of 11-1/8 oz., or 4-3/4 per cent water.

Following are the data and results of the boiler tests. On the general forms:

$$\text{Item } 5 = 3 - (4 \times 3) + 6$$

$$\text{" } 7 = 6 \div 3$$

$$\text{" } 9 = \frac{\text{amount of water in steam} + \text{steam condensed}}{\text{steam condensed.}}$$

$$\text{" } 10 = 8 \times \frac{\text{total heat (supposing all to be vaporized)}}{\text{heat of vaporization.}}$$

$$\text{" } 11 = \frac{8 \times \text{heat of liquid} + 8 \times 9 \times \text{heat of vaporization}}{\text{heat of vaporization.}}$$

$$\text{" } 14 = 8 \div 2$$

$$\text{" } 15 = 11 \div 2$$

$$\text{" } 16 = 15 \div \text{area of surface}$$

$$\text{" } 23 = 15 \div 34\frac{1}{2} \text{ lbs.}$$

$$\text{" } 25 = 23 \div 24$$

$$\text{Item } 26 = 8 \div 3$$

$$" \quad 27 = 11 \div 3$$

$$" \quad 28 = 27 \div (100 \% - 4)$$

$$" \quad 29 = 11 \div 5$$

We will here take the opportunity of thanking Messrs.

D. V. Corbin and Alexis J. Reed, of the Junior class, for the service rendered us in the taking of data on the boiler tests and also Messrs. C. E. Peterson and J. O. Baylor for their efficient services as firemen during the progress of the tests.

DATA AND RESULTS OF EVAPORATIVE TESTS.

Arranged in accordance with the short form advised by the boiler test committee of the American Society of Mechanical Engineers.

Grate surface.....	20$\frac{1}{2}$	Sq. FT.
Water heating surface	606	" "
Ratio of grate to water heating surface	1.30	
Kind of fuel.....		LEAVENWORTH

TOTAL QUANTITIES.

1. Date of trial.....	FEB. 24, 1902
2. Duration of trial in hours	6
3. Weight of coal fired.....	1871 LBS.
4. Per cent of water in coal	4$\frac{3}{4}$
5. Total weight of coal consumed, in pounds	1550
6. Total ash and refuse.....	232 LBS.
7. Percentage ash and refuse in coal	12.5
8. Total weight of water fed to boiler	9930$\frac{1}{2}$ LBS.
9. Condition of steam	90.8%
10. Equivalent water apparently evaporated from and at 212° F.....	11,059 LBS.
11. Equivalent water actually evaporated from and at 212°F(corrected for moisture in steam).....	11,041.7 "

HOURLY QUANTITIES.

12. Pounds coal consumed per hour.....	258$\frac{1}{2}$
13. Coal per hour per square foot of grate surface	12.7 LBS.
14. Pounds feed water per hour	165.5
15. Equivalent water evaporated per hour from and at 212° F. (corrected for moisture in steam).....	1890 "
16. Equivalent water evaporated per square foot of heating surface per hour.....	2.76 "

AVERAGE BOILER PRESSURES, TEMPERATURES, ETC.

17. Average boiler pressure, pounds per square inch, gage	59.8
18. Average boiler pressure, pounds per square inch, absolute	74.5
19. Average temperature of feed water,° Fahrenheit	49.8
20. Average temperature of boiler room,° Fahrenheit.....	65.16
21. Average temperature of outside air,° Fahrenheit.....	
22. Barometer.....	

HORSE-POWER.

23. Horse-power developed	53.3
24. Builders' rated horse-power.....	60
25. Percentage of builders' rated horse-power	89.5

ECONOMIC RESULTS.

26. Water apparently evaporated per pound of coal under actual conditions	5.3	LBS.
27. Equivalent water actually evaporated from and at 212° F., per pound of coal fired.....	5.9	"
28. Equivalent evaporation from and at 212° F., per pound of dry coal.....	6.2	"
29. Equivalent evaporation from and at 212° F., per pound of combustible.....	7.1	"

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

TEST MADE AT THE COLLEGE POWER PLANT
MANHATTAN, KANSAS.
ON BOILER No 1.
DATE FEB. 24, 1902.

LOG OF BOILER TRIAL

OBSERVERS:

GLICK FOCKELE
MURRAY S. COLE.

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWER PLAN

MANHATTAN, KANSAS

ON BOILER No. 1

DATE FEB. 24 1902

PRIMING LOG

(SEPARATING CALORIMETER.)

OBSERVERS:

GLICK FOCKELE.
MURRAY S. COLE.

DATA AND RESULTS OF EVAPORATIVE TESTS.

Arranged in accordance with the short form advised by the boiler test committee of the American Society of Mechanical Engineers.

Grate surface.....	204	SQ.FT.
Water heating surface	606	"
Ratio of grate to water heating surface	1.30	
Kind of fuel.....	LEAVENWORTH	

TOTAL QUANTITIES.

1. Date of trial.....	APR. 19, 1902
2. Duration of trial in hours	8
3. Weight of coal fired.....	3985 LBS
4. Per cent of water in coal	4 3/4
5. Total weight of coal consumed, in pounds	2990.21
6. Total ash and refuse.....	855.2 LBS.
7. Percentage ash and refuse in coal	21 1/2
8. Total weight of water fed to boiler	1820.6 LBS.
9. Condition of steam	87%
10. Equivalent water apparently evaporated from and at 212° F.....	2157.1 LBS.
11. Equivalent water actually evaporated from and at 212°F(corrected for moisture in steam).....	1641.27 "

HOURLY QUANTITIES.

12. Pounds coal consumed per hour.....	367 1/2
13. Coal per hour per square foot of grate surface	18.14 LBS.
14. Pounds feed water per hour	2275 3/4
15. Equivalent water evaporated per hour from and at 212° F. (corrected for moisture in steam).....	2051.6 LBS.
16. Equivalent water evaporated per square foot of heating surface per hour.....	3.87 "

AVERAGE BOILER PRESSURES, TEMPERATURES, ETC.

17. Average boiler pressure, pounds per square inch, gage	65 3/11
18. Average boiler pressure, pounds per square inch, absolute	79.97
19. Average temperature of feed water,° Fahrenheit	55.8
20. Average temperature of boiler room,° Fahrenheit.....	69.2
21. Average temperature of outside air,° Fahrenheit.....	51.58
22. Barometer.....	

HORSE-POWER.

23. Horse-power developed	59 1/2
24. Builders' rated horse-power.....	60
25. Percentage of builders' rated horse-power	99 1/2

ECONOMIC RESULTS.

26. Water apparently evaporated per pound of coal under actual conditions	4.5	LBS.
27. Equivalent water actually evaporated from and at 212° F., per pound of coal fired.....	4.1	"
28. Equivalent evaporation from and at 212° F., per pound of dry coal.....	4.3	"
29. Equivalent evaporation from and at 212° F., per pound of combustible.....	5.58	"

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

TEST MADE AT THE COLLEGE POWER PLANT
MANHATTAN, KANSAS.
ON BOILER NO 1.
DATE APRIL 14, 1902

LOG OF BOILER TRIAL

OBSERVERS:

GLICK FOCKELE
MURRAY S COLE.

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWER PLANT
 MANHATTAN, KANSAS
 ON BOILER No. 1,
 DATE APRIL 14, 1902

OBSERVERS:

PRIMING LOG. (SEPARATING CALORIMETER.)

GLICK FOCKELE,
 MURRAY S. COLE

No.	Time.		Scale reading.		Amount of water in steam.	Weight on scales.		Condensed steam.	Quality of steam.	Remarks.
	Start.	Stop.	Start.	Stop.		oz.	lbs. oz.			
1	9:4	9:8	3	5	2	oz	15 - 14	16 - 10 $\frac{1}{2}$	0 - 12 $\frac{1}{2}$	86%
2	9:35	9:38 $\frac{1}{2}$	3	4	1		20 - 11	21 - 6 $\frac{1}{2}$	0 - 12 $\frac{1}{4}$	91% $\frac{1}{2}$
3	10:6 $\frac{1}{2}$	10:10 $\frac{1}{2}$	2.5	5	2.5		19 - 1 $\frac{3}{4}$	20 - 0 $\frac{1}{4}$	0 - 19 $\frac{1}{2}$	85%
4	11:4 $\frac{1}{2}$	11:8 $\frac{1}{2}$	2	4.5	2.5		19 - 2 $\frac{1}{4}$	19 - 15	0 - 12 $\frac{3}{4}$	83 $\frac{3}{4}$ %
5	12:6	12:11	3.3	7.5	4.2		18 - 5 $\frac{1}{2}$	19 - 7 $\frac{1}{4}$	1 - 1 $\frac{3}{4}$	80.86%
6	1:34	1:38	3.3	4.2	0.9		18 - 12	19 - 9 $\frac{1}{4}$	0 - 13 $\frac{1}{4}$	93.7%
7	2:3	2:7	2	4.9	2.9		21 - 2 $\frac{1}{4}$	22 - 0	0 - 13 $\frac{1}{4}$	82%
8	2:52	2:56	2.4	5.9	3.1		21 - 0 $\frac{1}{2}$	21 - 15	0 - 14 $\frac{1}{2}$	80 $\frac{1}{2}$ %
9	3:33	3:36	2.6	3.2	0.6		18 - 10	19 - 3 $\frac{3}{4}$	0 - 9 $\frac{3}{4}$	94 $\frac{1}{2}$ %
10	4:21	4:25	3.3	5	1.7		21 - 13 $\frac{1}{2}$	22 - 11	0 - 13 $\frac{1}{2}$	88 $\frac{1}{2}$ %
									AVERAGE	87%

DATA AND RESULTS OF EVAPORATIVE TESTS.

Arranged in accordance with the short form advised by the boiler test committee of the American Society of Mechanical Engineers.

Grate surface.....	20 $\frac{1}{4}$	SQ. FT.
Water heating surface	60.6	" "
Ratio of grate to water heating surface	1.130	
Kind of fuel.....	LEAVENWORTH	

TOTAL QUANTITIES.

1. Date of trial.....	APRIL 28, 1902	
2. Duration of trial in hours	7	
3. Weight of coal fired.....	2,115	LBS
4. Per cent of water in coal	4 $\frac{3}{4}$	%
5. Total weight of coal consumed, in pounds	1,934	.36
6. Total ash and refuse.....	349.5	"
7. Percentage ash and refuse in coal	14 $\frac{1}{2}$	%
8. Total weight of water fed to boiler	13,218	"
9. Condition of steam	84%	
10. Equivalent water apparently evaporated from and at 212° F.....	15,882	.4
11. Equivalent water actually evaporated from and at 212° (corrected for moisture in steam).....	11,548	

HOURLY QUANTITIES.

12. Pounds coal consumed per hour.....	276.3	
13. Coal per hour per square foot of grate surface	13.64	
14. Pounds feed water per hour	1,888.28	
15. Equivalent water evaporated per hour from and at 212° F. (corrected for moisture in steam).....	1,649.7	.485
16. Equivalent water evaporated per square foot of heating surface per hour.....	2.7	"

AVERAGE BOILER PRESSURES, TEMPERATURES, ETC.

17. Average boiler pressure, pounds per square inch, gage	65.34	
18. Average boiler pressure, pounds per square inch, absolute	80.04	
19. Average temperature of feed water, Fahrenheit	56.3	
20. Average temperature of boiler room, Fahrenheit.....	77	
21. Average temperature of outside air, Fahrenheit.....	67.55	
22. Barometer.....		

HORSE-POWER.

23. Horse-power developed	47.8	
24. Builders' rated horse-power.....	60.	
25. Percentage of builders' rated horse-power	80	

ECONOMIC RESULTS.

26. Water apparently evaporated per pound of coal under actual conditions	5.4	LBS
27. Equivalent water actually evaporated from and at 212° F., per pound of coal fired.....	4.72	"
28. Equivalent evaporation from and at 212° F., per pound of dry coal.....	4.9	"
29. Equivalent evaporation from and at 212° F., per pound of combustible.....	5.9	"

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWER PLANT
MANHATTAN, KANSAS.
ON BOILER No. 1.
DATE APRIL 28, 1902.

PRIMING LOG. (SEPARATING CALORIMETER.)

OBSERVERS:

GLICK FOCKELE
MURRAY S. COLE.

No.	Time.		Scale reading.		Amount of water in steam.	Weight on scales.		Condensed steam.	Quality of steam.	Remarks.
	Start.	Stop.	Start.	Stop.		Start.	Stop.			
1	9:4 A.M.	9:8 A.M.	0.6	6.5	5.9 oz.	18 - 6 $\frac{1}{4}$	19 - 8	1 - 1 $\frac{3}{4}$	75%	
2	9:51:30 ..	9:54:30 ..	3.5	8.6	5.1	18 - 5 $\frac{1}{4}$	19 - 8 $\frac{1}{2}$	1 - 3 $\frac{1}{4}$	79%	
3	10:37 "	10:40 "	3.0	5.25	2.25	18 - 9 $\frac{1}{2}$	19 - 10 $\frac{1}{2}$	1 - 1	83%	
4	11:36 "	11:39 "	3.9	9.9	6.0	15 - 6 $\frac{1}{2}$	16 - 8 $\frac{1}{4}$	1 - 1 $\frac{3}{4}$	74.7%	
5	12:24 P.M.	12:27 P.M.	2.0	3.3	1.1	19 - 9	20 - 8	0 - 15	93.7%	
6	1:34 ..	1:37 ..	2.35	6.6	4.25	17 - 12 $\frac{1}{2}$	18 - 11 $\frac{1}{2}$	0 - 15	77.4	
7	2:24:30 ..	2:27:30 ..	4.05	4.9	0.85	16 - 5 $\frac{1}{2}$	17 - 5 $\frac{1}{2}$	1 - 0	95%	
8	2:39:30	2:36:30	1.6	2.8	1.2	19 - 15 $\frac{1}{4}$	21 - 2 $\frac{1}{2}$	1 - 2 $\frac{3}{4}$	93.9%	
9	3:31:30	3:18:30	4.0	5.7	1.7	20 - 6 $\frac{1}{2}$	21 - 8	1 - 1 $\frac{1}{2}$	91.2%	

AVERAGE 84%

The discrepancy between the calorimeter logs for the boiler tests and those of the engine tests is explained by the fact that during the latter, two boilers were in use and thus vaporization was less rapid in each boiler than in the one in use during the boiler tests, and for this reason there was less tendency to priming.

Reference to the tables following will show the high quality of steam in use during the engine tests. It was originally the intention of the writers to derive the efficiency of the piping from the quotient of the quality at the engine by the quality at the boiler, but this was impracticable for the reason that we had but one calorimeter.

As is shown on the log of the engine trial opposite, the brake load was determined from the switch board in volts and amperes, and the brake horsepower was computed from the equation

$$B. H. P. = \frac{\text{volts} \times \text{amperes}}{746}$$

In determining the indicated horsepower we made use of the equation:

$$I. H. P. = K \times M. E. P. \times r. p. m.$$

where K is the constant of cylinder, viz: .004022 and .003954 for the head and crank ends respectively. That is,

$$K (\text{crank end}) = \frac{\text{area of crank end piston in inches} \times \text{stroke in feet}}{33000}$$

$$\text{and } K (\text{head end}) = \frac{\text{area of head end piston in inches} \times \text{stroke in feet}}{33000}$$

The mean effective pressure was determined from the indicator cards in the usual way, by taking the quotient of the area by the length \times strength of spring, 50 lbs. The efficiency, E , of the engine was computed as follows:

$$E = \frac{B. H. P.}{I. H. P.}$$

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWER PLANT

MANHATTAN, KANSAS.

ON THE IDEAL ENGINE

DATE MAY 21, 1902

PRIMING LOG. (SEPARATING CALORIMETER.)

OBSERVERS:

GLICK FOCKELE
MURRAY SCOLE.

No.	Time.		Scale reading.		Amount of water in steam.	Weight on scales.		Condensed steam.	Quality of steam.	Remarks.
	Start.	Stop.	Start.	Stop.		lbs.	oz.	lbs.	oz.	
1	1:21:15	1:29:15	4.3	5.9	.02	17 - 12 $\frac{1}{4}$	18 - 7 $\frac{1}{2}$	0 - 11 $\frac{1}{4}$	87 $\frac{1}{2}$ %	
2	1:50	1:53	2.6	3.6	1.0	19 - 9 $\frac{3}{4}$	20 - 10 $\frac{1}{2}$	0 - 16 $\frac{3}{4}$	93% $\frac{1}{2}$	
3	2:19	2:22	2.0	2.6	0.6	19 - 1 $\frac{1}{2}$	20 - 9	1 - 7 $\frac{1}{2}$	97 $\frac{1}{2}$ %	
4	2:47	2:50	5.2	6.2	1.0	19 - 14	20 - 19 $\frac{1}{4}$	1 - 0 $\frac{1}{4}$	94%	
5	3:21	3:24	3.5	4.6	1.1	18 - 15 $\frac{3}{4}$	20 - 0 $\frac{1}{2}$	1 - 0 $\frac{3}{4}$	94%	
6	3:56	3:59	7.4	7.8	0.4	18 - 12 $\frac{1}{4}$	19 - 14	1 - 1 $\frac{3}{4}$	98%	
7	4:32	4:35	6.6	7.6	1.0	20 - 2	21 - 8	1 - 6	95 $\frac{1}{2}$ %	
								AVERAGE	99.3%	

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

TEST MADE AT THE COLLEGE POWER PLANT
MANHATTAN, KANSAS.
ON THE IDEAL ENGINE
DATE MAY 31, 1902.

LOG OF ENGINE TRIAL

CONSTANTS OF ENGINE

Diameter of cylinder....	<u>1.3</u> in.	Area of piston H. E.	<u>132.72</u> sq. in.
Diameter of piston rod..	<u>1.76</u> in.	Area of piston C. E.	<u>130.49</u> sq. in.
Length of stroke	<u>1</u> ft.	Engine constant for H. E.,	<u>.004022</u>

OBSERVERS:

GLICK FOCKELE
MURRAY S. COLE.

No. Card.	Time.	R. P. M.	M. E. P.		I. H. P.			Brake Load (Dynamo).		B. H. P.	Remarks.
			H. E.	C. E.	H. E.	C. E.	Total.	Volts.	Amperes.		
1	8: — AM	277	12.83	12.39	14.295	13.878	27.873	220	85	25.11	
2	8: 15	277	12.54	12.975	13.97	14.22	28.19	220	85	25.11	
3	8: 30	280	14.434	14.14	16.256	15.66	31.916	220	90	26.59	
4	8: 45	281	10.55	11.56	11.925	11.738	23.663	220	75	22.11	
5	9: —	277	11.595	13.044	12.92	14.295	27.215	219	85	24.95	
6	9: 15	281	10.64	11.66	12.026	12.96	24.986	220	68	20.05	
7	9: 30	277	9.825	9.906	10.39	10.855	21.245	219	60	17.72	
8	9: 45	280	9.621	9.468	10.835	10.487	21.322	220	60	17.69	
9	10: —	281	8.822	10.59	9.971	11.77	21.791	220	28	8.257	
10	10: 15	280	3.6445	5.976	4.1045	6.18	10.2845	219	62.5	17.93	
11	10: 30	280	9.481	11.536	10.679	12.8	23.479	221	62.5	18.51	
12	10: 45	277	10.00	11.322	11.143	12.46	23.603	220	62.5	18.93	
13	11: —	280	8.565	10.375	8.646	11.49	20.136	220	59	17.4	
14	11: 15	280	10.735	11.765	12.09	13.03	25.12	219	72.5	21.28	
15	11: 30	280	13.235	14.119	14.905	15.64	30.595	220	87	25.66	
16	11: 45	281	10.994	13.404	12.422	14.9	27.322	220	76	22.41	
17	12: —	278	11.178	11.323	12.50	12.95	24.95	220	68	20.05	
18	12: 15 P.M.	273	11.195	12.538	12.294	13.54	25.834	220	70	20.64	
19	12: 30	285	2.985	6.269	3.422	7.0678	10.4898	220	22	6.988	NO LOAD EXCEPT AT THE DAIRY.
20	12: 45	281	2.187	5.394	2.472	5.995	8.467	220	21	6.192	
21	1: —	281	3.0075	5.564	3.3995	6.184	9.5835	220	23	6.782	
22	1: 15	283	2.5565	5.564	2.91	6.228	9.138	220	18	5.308	
23	1: 30	279	5.294	6.765	5.9905	7.463	13.4035	220	32	9.437	POWER FOR SHOPS THROWN ON
24	1: 45	277	11.26	19.26	12.546	20.11	32.656	218	75	21.91	
25	2: —	277	8.089	9.8465	9.012	10.79	19.802	220	57	16.81	
26	2: 15	281	8.8215	9.8465	9.97	10.995	20.915	220	57	16.81	
27	2: 30	280	8.746	9.323	9.85	10.325	20.275	220	57	16.81	
28	2: 45	280	8.746	9.767	9.85	10.818	20.768	220	57	16.81	
29	3: —	277	8.455	9.184	9.42	10.073	19.493	220	56	16.52	
30	3: 15	279	8.384	10.295	9.409	10.36	20.769	220	58	17.1	
31	3: 30	277	8.746	9.622	9.745	10.593	20.288	220	60	17.69	
32	3: 45	277	8.601	9.765	9.584	10.7	20.284	220	58	17.1	
33	4: —	280	9.826	9.926	11.18	10.995	22.175	220	57	16.81	

Maximum,	285	14.434	19.26	16.256	20.11	32.656	221	90	26.54
Minimum,	273	2.187	5.394	2.472	5.995	8.467	218	18	5.308
Total,	305.196	333.502	330.0115	359.5468	689.5583	7255	1964	561.614	
Average,	9.248	10.106	10.0003	10.895	20.8953	219.85	59.51	17.18	

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWER PLANT

MANHATTAN, KANSAS.

ON THE IDEAL ENGINE

DATE MAY 31, 1902

OBSERVERS:

GLICK FOCKELE
MURRAY'S COLE

PRIMING LOG.

(SEPARATING CALORIMETER.)

No.	Time.		Scale reading.		Amount of water in steam.	Weight on scales.		Condensed steam.	Quality of steam.	Remarks.
	Start.	Stop.	Start.	Stop.		Start.	Stop.			
1	8:49	8:52	1.5	2.8	1.3	17 - 13	18 - 8 $\frac{1}{4}$	0 - 11 $\frac{1}{4}$	89 $\frac{1}{2}$ %	
2	9:55:30	9:59:30	2.8	4.0	1.2	19 - 3 $\frac{1}{4}$	20 - 6 $\frac{1}{2}$	1 - 3 $\frac{1}{4}$	99%	
3	10:53	10:56	2.6	3.6	1.0	21 - 3 $\frac{1}{4}$	22 - 3 $\frac{1}{2}$	0 - 13	93%	
4	11:55:30	11:58:30	2.5	3.5	1.0	20 - 9 $\frac{1}{2}$	21 - 9 $\frac{1}{4}$	0 - 15 $\frac{3}{4}$	99%	
5	1:9:30	1:12:30	2.5	3.0	0.8	18 - 6 $\frac{1}{2}$	19 - 6 $\frac{1}{2}$	0 - 16	96%	
6	2:5	2:8	4.2	4.8	0.6	19 - 2	19 - 14 $\frac{1}{2}$	0 - 12 $\frac{1}{2}$	95.5%	
7	2:49	2:52	3.3	4.9	1.1	19 - 9 $\frac{1}{2}$	20 - 7 $\frac{1}{4}$	1 - 2 $\frac{3}{4}$	99.5%	
8	3:48	3:51	2.3	3.5	1.2	18 - 3 $\frac{3}{4}$	19 - 8	1 - 9 $\frac{1}{4}$	99.5%	
								AVERAGE	93.8%	

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

TEST MADE AT THE COLLEGE POWER PLANT
MANHATTAN, KANSAS.
ON THE IDEAL ENGINE
DATE JUNE 2, 1902

LOG OF ENGINE TRIAL.

CONSTANTS OF ENGINE

Diameter of cylinder....	<u>1.3</u> .in.	Area of piston H. E.....	<u>1.3273</u> sq. in.
Diameter of piston rod..	<u>1.16</u> .in.	Area of piston C. E.....	<u>1.3049</u> .sq. in.
Length of stroke	<u>1</u> .ft.	Engine constant for H. E.,	<u>0.04022</u>

OBSERVERS:

GLICK FOCKELE
MURRAY SCOLE.

DEPARTMENT OF MECHANICAL ENGINEERING, K. S. A. C.

MADE AT THE COLLEGE POWERPLANT
 MANHATTAN, KANSAS.
 ON THE IDEAL ENGINE
 DATE JUNE 2, 1902.

PRIMING LOG. (SEPARATING CALORIMETER.)

OBSERVERS:

GLICK FOCKELE
 MURRAY S. COLE.

No.	Time.		Scale reading.		Amount of water in steam.	Weight on scales.		Condensed steam.	Quality of steam.	Remarks.
	Start.	Stop.	Start.	Stop.		oz.	lbs.	oz.	lbs.	
1	7:48	7:51	3.7	4.0	0.3	19 - 14	21 - 9	1 - 11	99%	
2	7:55	7:58	4.4	4.7	0.3	19 - 3½	20 - 5	1 - 1½	98.5%	
3	8:56	8:59	2.3	2.8	0.5	19 - 12½	21 - 2¾	1 - 6¼	98%	
4	10:5	10:8	1.6	2.5	0.9	18 - 2½	19 - 11½	1 - 9	96.5%	
5	11:5	11:8	1.7	2.8	1.1	20 - 9¾	21 - 15	1 - 5¾	95%	
6	12:5	12:8	1.3	1.9	0.6	19 - 14½	21 - 9¾	1 - 6½	97.5%	
7	1:7	1:10	3.1	3.5	0.9	20 - 2½	21 - 5½	1 - 3	98%	
8	2:20	2:23	2.3	2.9	0.6	19 - 0½	20 - 8½	1 - 8	97.5%	
								AVERAGE	97.5%	